

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. 62.63 / निर्माण / 2022

सिस्टम टेंडर नं.111005

कोरबा दिनांक 03.10.2022

ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अनियता लोक निर्माण विभाग, रायपुर द्वारा सड़क कार्य हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदाएं आमंत्रित की जाती हैं :-

क्र	कार्य का नाम	प्रवर्कलन राशि (लाख में)	धरोहर राशि	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	नगर निगम क्षेत्र के कोसाबाडी ज्ञान अंतर्गत वार्ड क 22 एच.आई.जी. कॉलोनी, एम.पी. नगर एवं शिवाजी नगर, वार्ड क 28 आर. पी.नगर में बी.टी.रोड निर्माण कार्य	298.40	225000/-	06 माह (वर्षा ऋतु छोड़कर)	वर्ग बी एवं प्रवर श्रेणी	28.10.2022 से

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पैन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयको में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्कुरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- निविदा उन्ही ठेकेदारों को प्रदाय किये जावेगे जो कि कर्मचारी भविष्य निधि सगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रदाय नहीं किया जावेगा।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में बैंड शपथपत्र देना अनिवार्य होगा।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- सशर्त निविदा स्वीकार नहीं की जावेगी। निविदा उन्ही ठेकेदारों को दी जाएगी जिन्हें इस प्रकार के कार्य का अनुभव हो।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- अन्य सूचनाएं नगर पालिक निगम, साकेत भवन रामपुर कोरबा कार्यालय में प्राप्त की जा सकती हैं।
- बिना कारण बताये निविदा स्वीकृत/अस्वीकृत या पूर्ण रूप से अमान्य करने का अधिकार सक्षम अधिकारी/प्राधिकारी को रहेगा।
- डामरीकरण कार्य का निविदा प्रपत्र क्रय करते समय ठेकेदार को स्वयं के स्वामित्व के आटोमेटिक ड्रम निक्स प्लाट, रोलर एवं अन्य मशीनरी, हॉट निक्स प्लाट, पेवर फिनिशर एवं रोड रोलर आदि मशीनों के प्रमाण पत्र आवेदन के साथ सलग्न करना आवश्यक होगा तथा निविदाकार का 60 किमी की परिधि में हॉल निक्स प्लाट होना आवश्यक है।
- ठेकेदार द्वारा 60/70 ग्रेड का डामर IOC, BPCL, HPCI से ही क्रय कर लगाना होगा। ठेकेदार को तेल कंपनी को दी जाने वाली प्रदाय आदेश की प्रतिलिपि इस कार्यालय को देनी होगी।
- कार्य में प्रयुक्त डामर खरीदी के देयक (बिल) कार्यालय में प्रस्तुत करने पर ही भुगतान किया जायेगा।
- जब निविदा के दरों में असामान्य कमी प्रतीत हो तब सफल निविदादाता से अनुबध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी, जबकि निविदा की दरों में काफी कमी हो, जैसे निविदादाता को अनुमानित लागत से 10 प्रतिशत से कम निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत के अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर. पोस्ट ऑफिस टाईम डिपॉजिट, एन.एस.सी. जो कि संबंधित निकाय के आयुक्त/मुख्य नगर पालिका अधिकारी के नाम से देय होगा, जमा कराना अनिवार्य होगा उपरोक्त राशि को जमा न कराने की दशा में निविदा निरस्त कर दी जावेगी।

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		03.10.22	10.30	03.10.22	10.30	Release Tender
2		Bid Submission	03.10.22	10.30	27.10.22	17.30	
3	Tender Open		28.10.22	10.30	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
 For, Commissioner Korba (C.G.)

Handwritten initials

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

Name of work:-Renovable of Bitumen road of Hig colony, MP nagar Colony, and Shivaji nagar colony at ward no 22

Schedule of rates public works department[PWD ROAD-01-01-2015]

S.N.	SOR Ref.	DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	5.1	Tack coat Providing and applying tack coat with bitumen emulsion (RS-1, grade confirming to IS:8887) using emulsion pressure distributor on the prepared bituminous/granular surface cleaned with mechanical broom and as per clause 503								
		Bituminous surface @ 0.25 kg /Sqm								
		HIG COLONY	2	1800.00	3.60		12960.00			
			2	226.15	7.00		3166.10			
		MP NAGAR	2	3600.00	3.60		25920.00			
		SHIVAJI NAGAR	2	3160.00	3.60		22752.00			
			4	265.00	5.00		5300.00			
						total=	70098.10	sqm	15.00	1051471.50
2	5.3	4.10 Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 406.)								
		HIG COLONY	2	150.00	4.50	0.25	337.50			
		MP NAGAR	1	163.00	4.50	0.25	183.38			
						Total=	520.88	Cum	1434.00	746934.75
3	3.3	Prime coat (Providing and applying primer coat with oil based bitumen emulsion (SS-1, grade confirming to IS:8887) on prepared surface of granular Base including clearing of road surface and								
		i) on WBM/WMM surface @0.85 Kg/sq	2	150.0	4.50		1350.0			
			1	163.0	4.50		733.5			

5.	Bituminous Macadam (Providing and laying bituminous macadam as per clause 504 with mixed prepared in minimum 40-60 TPH capacity hot mix plant using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction)				Total=	2083.50	sqm	64.00	133344.00
	B With mechanical paver finisher								
	(ii) for Grading-II(19 mm nominal maximum size, bitumen content								
	HIG COLONY	1	1800.00	3.60	0.05	324.00			
		1	226.15	7.00	0.05	79.15			
	MP NAGAR	1	3600.00	3.60	0.05	648.00			
	SHIVAJI NAGAR	1	3160.00	3.60	0.05	568.80			
		2	265.00	5.00	0.05	132.50			
					Total=	1752.45	Cum	6255.00	10961590.39
5	5.5 Close Graded Premix Surfacing/Mixed Seal Surfacing (Mechanical means using minimum 40-60 TPH capacity of HMP. Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness using bitumen to the required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a								
	II. With mechanical paver finisher								
	ii) Type B (13.2 mm to 0.09 mm size aggregates)								
	HIG COLONY	1	1800.00	3.60		6480.00			
		1	226.15	7.00		1583.05			
	MP NAGAR	1	3600.00	3.60		12960.00			
	SHIVAJI NAGAR	1	3160.00	3.60		11376.00			
		2	265.00	5.00		2650.00			
					Total=	35049.05	Sqm	146.00	5117161.30

8.13	Road Marking with Hot Applied Thermoplastic Compound with reflectorizing Glass Beads on Bituminous Surface (Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorizing glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35-1997. The finished surface to be level, uniform and free from streaks and holes.)								
	HIG COLONY	2	1800	0.15		540.00			
		0.5	1800	0.15		135.00			
	MP NAGAR	2	3600	0.15		1080.00			
	SHIVAJI NAGAR	2	3160	0.15		948.00			
						2703.00	Sqm	707.00	1911021.00

total= 19921522.94

say rs.= 19922000.00

Executive. Engineer
Municipal Corporation
Korba (C.G.)

Asstt. Engineer
Municipal Corporation
Korba (C.G.)

Sub Engineer
Municipal Corporation
Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

Name of work:-Renovable of Bitumen road of R.P.NAGAR Ward no 28

Schedule of rates public works department[PWD ROAD-01-01-2015]

S.N.	SOR Ref.	DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	5.1	Tack coat Providing and applying tack coat with bitumen emulsion (RS-1, grade confirming to IS:8887) using emulsion pressure distributor on the prepared bituminous/granular surface cleaned with mechanical broom and as per clause 503								
		Bituminous surface @ 0.25 kg /Sqm								
		R.P.NAGAR	2	3850.00	3.60		27720.00			
			4	265.00	5.00		5300.00			
						total=	33020.00	sqm	15.00	495300.00
2	5.3	4.10 Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 406.)								
		HIG COLONY	2	190.00	4.50	0.25	427.50			
		MP NAGAR	1	163.00	4.50	0.25	183.38			
						Total=	610.88	Cum	1434.00	875994.75
3	3.3	Prime coat (Providing and applying primer coat with oil based bitumen emulsion (SS-1, grade confirming to IS:8887) on prepared surface of granular Base including clearing of road surface and								
		i) on WBM/WMM surface @0.85 Kg/sq	2	190.0	4.50		1710.0			
			1	163.0	4.50		733.5			
						Total=	2443.50	sqm	64.00	156384.00

5.3	Bituminous Macadam (Providing and laying bituminous macadam as per clause 504 with mixed prepared in minimum 40-60 TPH capacity hot mix plant using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction)								
	B With mechanical paver finisher								
	(ii) for Grading-II(19 mm nominal maximum size, bitumen content								
	R.P.NAGAR	1	3850.00	3.60	0.050	693.00			
		2	265.00	5.00	0.050	132.50			
					Total=	825.50	Cum	6255.00	5163502.50
5.5	Close Graded Premix Surfacing/Mixed Seal Surfacing (Mechanical means using minimum 40-60 TPH capacity of HMP. Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness using bitumen to the required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a								
	II. With mechanical paver finisher								
	ii) Type B (13.2 mm to 0.09 mm size aggregates)								
	R.P.NAGAR	1	3850.00	3.60		13860.00			
		2	265.00	5.00		2650.00			
					Total=	16510.00	Sqm	146.00	2410460.00

8.13	Road Marking with Hot Applied Thermoplastic Compound with Reflectorizing Glass Beads on Bituminous Surface (Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorizing glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35-1997. The finished surface to be level, uniform and free from streaks and holes.)								
	MP NAGAR	2	3850	0.15		1155.00			
						1155.00	Sqm	707.00	816585.00

total= 9918226.25

say rs.= 9918000.00

Executive Engineer
Municipal Corporation
Korba (C.G.)

Asstt. Engineer
Municipal Corporation
Korba (C.G.)


Sub Engineer
Municipal Corporation
Korba (C.G.)