कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क्र. 709/2026 सिस्टम टेंडर नं. 192456 कोरबा दिनांक 04.06.2026

ई–निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015,विद्युत हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई–प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र Form-A में निविदा आमंत्रित की जाती है:–

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि – 01.07.2026 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि – 01.07.2026 सायंकाल 4.00 बजे से

क.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (डिमांड ड्राफ्ट)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क्र. 60 अंतर्गत पशुजन्म नियंत्रण कक्ष में कैनल के ऊपर छाया निर्माण कार्य। (निगम मद)	14.34	10755/-	04 माह	750/-	वर्ग डी एवं प्रवर श्रेणी	01.07.2026 से .....

शर्तें:–

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरूद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नही होगी।
3. इच्छुंक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र,पेन नम्बर, **वैध जी.एस.टी.** पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमाण्ड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा ।
   - **अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं निर्धारित प्रारूप में शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से आयुक्त,नगर पालिक निगम,कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन– 495677 कोरबा के पते पर भेजना होगा। निर्धारित तिथि को सायं 03:00 बजे के पश्चात् फिजिकल सबमिशन लिफाफा स्वीकार नहीं किया जायेगा।**
   - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निर्धारित प्रारूप में वैध शपथपत्र (राशि रू. 100/– नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा कमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
   - **अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट जो कि आयुक्त, नगर पालिक निगम,कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।**
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी। सुरक्षा राशि एवं परफारमेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन(**वर्तमान तक वैधता**)एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे एवं कर्मचारी भविष्य निधि संगठन(ई.पी.एफ.) एवं विभिन्न प्रावधानों को धारा 1952 के तहत निविदार का जीवित पंजीयन होना आवश्यक है साथ ही निविदा आमंत्रण दिनांक से विगत तीन माह की अवधि में जमा किये गये **TRRN Payment Detail** चालान की प्रति प्रस्तुत करना तथा ऑनलाईन अपलोड किया जाना अनिवार्य होगा।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत् पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का **1 प्रतिशत उपकर** के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ईंट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से **15 दिवस** के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
10. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नही किया जावेगा।
11. निविदा प्रपत्र फार्म –ए की कंडिका 11 Price Adjustment (एस्कलेशन) देय नहीं होगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते है।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान कार्य विशेष हेतु बजट आबंटन एवं राशि उपलब्ध होने पर किया जाएगा।
16. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
17. कार्य कियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
18. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

प्रतिलिपि–

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		04.06.2026	15.30	04.06.2026	15.30	Release Tender
2		Bid Submission	04.06.2026	15.30	25.06.2026	17.30	
3		Physical Document Submmission	04.06.2026	15.30	01.07.2026	15.00	
4	Tender Open		01.07.2026	16.00	--	--	

EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)

DETAILED ESTIMATE

Name Of Work :- वार्ड क्र 60 अंतर्गत पशुजन्म नियंत्रण कक्ष में कैनल के ऊपर छाया निर्माण कार्य।

As Per SOR :- SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING - 01.01.2015]

S. N.	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	1.2	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).								
			1	18.00	10.00		180.00			
						Total	180.00	sqm	7.20	1296.00
2	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1.1	In all types of soils.								
		Post	15	0.60	0.60	0.60	3.24			
		Wall	2	15.40	0.50	0.50	7.70			
			2	8.40	0.50	0.50	4.20			
						Total	15.14	Cum	185.00	2800.90
3	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.								
							7.57			
						Total	7.57	Sqm	65.00	492.05
4	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
			15	0.60	0.60	0.10	0.54			
			2	15.40	0.50	0.10	1.54			
			2	8.40	0.50	0.10	0.84			
			1	17.00	10.00	0.20	34.00			
						Total	36.92	Cum	371.00	13697.32

	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	1.4	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size).								
			1	16.50	9.50	0.10	15.68			
			15	0.50	0.50	0.10	0.38			
			2	15.40	0.50	0.08	1.23			
			2	8.40	0.50	0.08	0.67			
						Total	17.95	Cum	3552.00	63772.61
6	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
			15	0.40	0.40	0.70	1.68			
						Total	1.68	Cum	4163.00	6993.84
7	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:								
	12.1	Thermo-Mechanically treated bars FE 415					200.00	Kg	54.50	10900.00
8	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.								
			15	4.00	0.40	0.70	16.80			
			4	16.50		0.10	6.60			
			2	9.50		0.10	1.90			
			15	4.00	0.50	0.10	3.00			
			2	10.00		0.15	3.00			
			4	2.40		0.15	1.44			
						Total	32.74	Sqm	139.00	4550.86

	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:								
	5.3	Cement Mortar 1:5 (1 cement : 5 coarse sand)								
			2	15.40	0.40	0.20	2.46			
			2	15.40	0.20	1.00	6.16			
			2	8.40	0.40	0.20	1.34			
			2	15.40	0.20	1.00	6.16			
							16.13			
		Deduction (-)								
		D	2	1.50	0.20	0.70	0.42			
						Total	0.42			
					G.Total =		15.71	Cum	3350.00	52621.80
10	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
			2	15.40	0.20	0.10	0.62			
			2	8.40	0.20	0.10	0.34			
			2	10.00	2.40	0.15	7.20			
						Total	8.15	Cum	4073.00	33203.10
11	9.3	Steel work in tubular (round, square or rectangular hollow tubes etc.)structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holdingdown bolts, wind ties bracing (if required), bolts, nuts and washers forfastening etc. complete with applying a priming coat of red oxide zinc chromate primer								
	3.2	Electric resistance or induction butt welded tubes Grade-300								
							350.00	kg	93.50	32725.00

	9.2	Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.								
							380.00	kg	66.00	25080.00
13	9.6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer								
	6.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similarworks.								
							90.00	kg	68.00	6120.00
14	9.43	Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete								
	43.1	Aperture 50x50mm								
			2	15.00		2.00	60.00			
			2	8.40		2.00	33.60			
						Total	93.60	sqm	331.00	30981.60
15	10.10	Extra for providing and fixing wind ties of 40x6mm flat iron section								
			6	5.00		8.40	252.00	metre	331.00	83412.00
16	10.12	Supply and fixing of polymer precoated galvalume profile sheets (PPGL) of approved size, shape and pitch of corrugation, total coated thickness (TCT) 0.60 mm +/- 5%, epoxy primer on both side of the sheet and colour polyester top coat 18-20 microns and 6-7 microns on bottom.								
			1	9.00		16.00	144.00	sqm	693.00	99792.00
17	11.2	Providing and making 12mm thick cement plaster of mix								

	2.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)								
			2	15.00		1.10	33.00			
			2	8.40		1.10	18.48			
						Total	51.48	Sqm	96.50	4967.82
18	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:								
	3.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)								
			2	15.40		1.10	33.88			
			2	8.40		1.10	18.48			
						Total	52.36	Sqm	113.00	5916.68
19	12.9	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.								
	9.2	Size above 300x300mm								
			1	15.00		8.00	120.00			
						Total	120.00	Sqm	728.00	87360.00
20	20.6	Providing, lowering, laying, aligning, fixing in position at and jointing at all level/ depths ISI marked HDPE pipes of PE-100 grade and PN 6 for sewer application as								
	6.2	150 mm dia					25.00	metre	771.00	19275.00
21	20.7	Constructing brick masonry manhole with well burnt modular clay bricks crushing strength not less than 35kg/cm2 in cement mortar 1:4 (1 cement : 4 coarse sand), R.C.C. top slab with 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), foundation in cement concrete 1:4:8 mix								
	7.1	Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions total weight of cover and frame to be not less than 38 kg								
							2.00	Each	6703.00	13406.00

	56	Providing and applying 2mm thick white cement based polymeric exterior grade putty with minimum 3 coat applied @ 5.4 kg/10 sqm as per relevant IS code 17545:2021 (product such as birla wall care asian trucare JK wall putty berger bison wall putty) to make the surface smooth and even with all tools tackles and labour etc complete for the work.								
							104.72	Sqm	86.00	9005.92
23	14.60	Providing and applying of Acrylic primer on all surface applied @ 0.80 litrs/10 sqm as per relevant I.S. code 15489:1974 (product such as asian spark/suprimo J.K. primer Dulux Acrylic primer) With all tools tackles and labour etc complete for the work .								
							104.72	sqm	37.00	3874.64
24	14.64	providing and applying premium plastic emulsion paint with roller application minimum three coat applied @ 0.75 lit/ 10 sqm up to final finish as per relevant IS code 15489:2013 type 1 class D & C (Glossy and semi Glossy finish) Cleanin of door window floor and surface as required with all tools tackles and labour etc complete for the work with 3 year warranty								
							52.36	Sqm	84.00	4398.24
25	14.68	P/A on exterior surface with premium exterior emulsion paint of required shade to give protective and water proof finish minimum 3 coat applied @ 1.40lit/10sqm up to final finish as per relevant IS Code 15489:2013 type 2 class D, C (Glossy/semi slossy finish) window floor and surface as required with all tools tackles and labour etc complete for the work (with 3 year Warranty)								
							52.36	Sqm	84.00	4398.24

	.71	providing and applying satin/matt finish Enamel paint minimum 2 coat in all surface applying @ 0.75 lit/10 sqm up to required finish as per relevent IS code 2932:2013 of (product such as asian satin enamel dulux promise premium enamel nerolac synthatic enamel opus prime enamel) inclusive of providing abro tape on edges and article and cleaning of door windows floor and surface as requrred with all tools tackle and labour etc complete for the work					50.00	Sqm	133.00	6650.00
27	19.5	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings							
	5.1	15 mm nominal outer dia .Pipes.					48.00	metre	133.00	6384.00
	5.2	20 mm nominal outer dia .Pipes.					24.00	metre	167.00	4008.00
	5.3	25 mm nominal outer dia .Pipes					12.00	metre	213.00	2556.00
28	19.13	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:								
	13.2	Bib cock (350 grams)					16.00	Each	237.00	3792.00
	13.3	stop cock (350 grams)					16.00	Each	237.00	3792.00
29	19.16	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end):								
	16.1	25 mm nominal bore					1.00	Each	436.00	436.00
30	19.17	Providing and fixing ball valve (brass) of approved quality, High or lowpressure, with plastic floats complete								
	17.1	15 mm nominal bore					8.00	Each	284.00	2272.00
	17.2	20 mm nominal bore					4.00	Each	394.00	1576.00
31	19.42	Providing and placing on terrace (at all floor levels) polyethylene waterstorage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflowpipes but without fittings and the base support for tank					1000.00	litre	7.30	7300.00

	19.11	Providing and fixing G.I. Union in G.I. pipe (New work) including cutting and threading the pipe and making long screws etc. complete								
	11.1	15 mm nominal bore					8.00	Each	85.00	680.00
	11.2	20 mm nominal bore					4.00	Each	98.00	392.00
33	1.19	Providing filling and compacting local earth (from approved source pit) in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete	1	15.00	8.00	0.20	24.00			
						Total	24.00	Cum	242.00	5808.00
		ELECTRICAL PART								
27	3.1	Wiring for light/ fan/ exhaust fan / call bell point with 1.5 sqmm FR PVC insulated stranded copper conductor single core cable in concealed PVC conduit, with 5 amp piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with same size cable etc as required.								
	1.1	Short Point					8.00	Point	236.00	1888.00
	1.2	Medium Point					10.00	Point	388.00	3880.00
	1.3	Long Point					8.00	Point	553.00	4424.00
28	3.9	Extra for providing and fixing light plug point on board in concealed PVC conduit point wiring with modular type 3 pin 5 amp socket outlet and 5 amp switch including cost of base and cover plate and G. I. box etc. as required.					2.00	Point	240.00	480.00
29	3.13	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FR PVC insulated copper conductor, single core cable in concealed PVC conduit as required.								
	13.11	6 X 2.5 sq. mm in 25mm conduit					10.00	Mtr	172.00	1720.00
	13.3	6 X 2.5 sq. mm in 25mm conduit					8.00	Mtr	172.00	1376.00

	.1	Supplying and fixing following piano type switch, socket, other accessories on the existing switch box/ cover including connections etc. as required.							
	1.12	Fan regulator Electronic, step type moving all round					8.00	Each	178.00	1424.00
31	8.1	Supplying, installation, testing and commissioning of following sizes ceiling fan including wiring the down rods of standard length up to 30 cm with 1.5 sq. mm FR PVC insulated, copper conductor, single core cable, earthing etc. complete as required.							
	1.3	1400 mm sweep					8.00	Each	1637.00	13096.00
32	8.11	Supplying, installation, testing and commissioning of following T-5 fluorescent fitting (luminaries) complete with electronic ballast but without fluorescent lamp, on ceiling/ wall surface, earthing the fitting etc. as required.							
	11.1	Single box type with decorative end caps					2.00	Each	635.00	1270.00
33	8.18	Supplying, fixing, testing and commissioning of following CFL (Built in choke type) in existing lighting luminaries as							
	18.7	26 Watt					2.00	Each	289.00	578.00
	18.11	85 Watt					1.00	Each	907.00	907.00
34	8.19	Supplying, fixing, testing and commissioning of following CFL without ballast in existing CFL lighting luminaries as required.							
	19.5	36W CFL (without choke)					5.00	Each	176.00	880.00
35	8.29	Supplying, installation, testing and commissioning of following 230/250 volts CFL street light fitting with perplex cover on pole bracket complete but without lamp as required.							
	29.2	85 watt					1.00	Each	1407.00	1407.00
36	8.34	Supplying, fixing, testing and commissioning of following 230/250 volts metal halide lamp in existing lighting luminaries fixed on pole/ wall/ roof etc as required.							
	34.3	250 watt (T)					1.00	Each	1403.00	1403.00

	10	Providing and fixing metal clad, TP&N switch fuse unit (rewirable), 415/500 volts, with porcelain re-wireble fuses including drilling holes on the board, connections, earthing the body etc. as required. (Thimbeling shall be paid separately).								
	10.2	63 amps					1.00	Each	1821.00	1821.00
38	9.11	Providing and fixing porcelain re-wireble fuse carrier and base unit on wooden board including drilling holes on the board, screws, connections etc. as required. (Thimbeling shall be paid separately).								
	11.3	63 amps					1.00	Each	157.00	157.00
39	11.2	Supplying and fixing on surface/ recess following way, 240 volts SP&N MCB distribution board of sheet steel phosphatized and powder painted complete with tinned copper busbar, neutral busbar, earth bar, din bar, detachable gland plate, including interconnections, earthing etc. as required. (But without MCB/RCCB/Isolator)								
	2.1	4 way, Single door					1.00	Each	602.00	602.00
40	11.12	Supplying and fixing DP MCB, 240 volts, 'C' curve, suitable for lighting and other loads in the existing MCB DB complete with connections, testing and commissioning etc. as required.								
	12.3	40 amps					2.00	Each	684.00	1368.00
41	11.11	Supplying and fixing SP MCB, 240 volts, 'C' curve, suitable for inductive load in the existing MCB DB complete with connections, testing and commissioning etc. as required.								
	11.2	6 amps to 32 amps					3.00	Each	154.00	462.00
42	14.2	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as required.					2.00	Set	3454.00	6908.00
43	14.19	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ concealed conduit/ submain wiring/ cable as required.					8.00	Mtr	20.50	164.00

	.8	Supplying and laying following sizes one number PVC insulated/ XLPE, PVC sheathed, unarmoured, aluminium conductor power cable of 1.1 KV grade on surface/ existing cable tray with 1 mm thick GI saddle as required.								
	8.2	2 x 10 sq. mm					12.00	Mtr	88.00	1056.00
	8.13	4 x 10 sq. mm.					14.00	Mtr	108.00	1512.00
45	21.15	Supplying and fixing of 32mm dia x 2 metre long G.I pipe (light) bracket for mounting street light fittings of all types on poles including bending the pipe to the required shape, 2 Nos 40x3mm flat iron clamps with bolts and nuts including wiring with 1.5 sq. mm W.P /PVC wire etc. as required.					2.00	Each	823.00	1646.00

As per Estimate Amount Rs. **717116.61**

2 X 717116.61 = **1434233.22**

Say Rs. 14.34.000/-

Sub Er.
Nagar Palik Nigam
Korba

Astt. Er.
Nagar Palik Nigam
Korba