



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय – साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

मु.का. दूरभाष : 221288, 222672, फैक्स : 07759-221929, पो. बॉक्स नं.-12 पिन कोड – 495677

फा.क्र./8412/8420/8422/8423/टी.पी. नगर जोन/ 2019/

कोरबा, दिनांक 12.09.2019

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल/ऑनलाइन निविदा वेबसाइट से डाउनलोड कर आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि में	घरोहर राशि रु में	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने आवेदन की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र. 02 अंतर्गत सामुदायिक शेड का निर्माण एवं मरम्मत तथा जलाराम मंदिर के पास शौचालय एवं मूत्रालय का निर्माण कार्य। (महापौर मद)	12,00,000/-	9,000/-	750/-	03 माह	सक्षम श्रेणी	23.09.2019	25.09.2019	04.10.2019
2	वार्ड क्र. 31 अंतर्गत खरमोरा सामुदायिक भवन में अतिरिक्त सुविधा की व्यवस्था एवं मरम्मत कार्य। (महापौर मद)	7,00,000/-	5,500/-	750/-	03 माह	सक्षम श्रेणी	23.09.2019	25.09.2019	04.10.2019
3	वार्ड क्र. 31 अंतर्गत रिस्दी चौक झगरहा रोड में सदगुरु कबीर आश्रम के समीप शौचालय एवं मूत्रालय का निर्माण कार्य। (महापौर मद)	7,00,000/-	5,500/-	750/-	03 माह	सक्षम श्रेणी	23.09.2019	25.09.2019	04.10.2019
4	वार्ड क्र. 47 अंतर्गत जमनीपाली मोहन टाकीज मुख्य मार्ग से रेशम साहू के निवास तक सीमेंट कांक्रीट रोड एवं आर.सी.सी. नाली का निर्माण कार्य। (महापौर मद)	10,00,000/-	7,500/-	750/-	03 माह	सक्षम श्रेणी	23.09.2019	25.09.2019	04.10.2019

शर्तें:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा प्रपत्र की प्रतियाँ नगर पालिक निगम, साकेत भवन रामपुर, कोरबा कार्यालय से उपरोक्त कार्यों हेतु नाम के सममुख अंकित राशि नगद जमा कर उपर लिखित तिथि तक सायं 5:00 बजे तक अवकाश के दिनों को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा मंगाना हो तो रु. 50/- अधिक भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की जिम्मेदारी इस कार्यालय की नहीं होगी।
- निविदा प्रपत्र स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किए जावेगे। निर्धारित तिथि को 3.00 बजे के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं की जावेंगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड)की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय प्रमाण पत्र/पैन नम्बर पत्र एवं जी.एस.टी. पंजीयन प्रमाण पत्र प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र एवं घरोहर राशि सहित निविदा प्रपत्र प्राप्त करने के अंतिम तिथि को 5.30 बजे सायं तक आवेदन प्रस्तुत करना अनिवार्य होगा।
- पूर्ण रूप से भरी निविदा प्रपत्र उपरोक्त तिथि को 15.00 बजे तक प्राप्त की जा सकती है और उसी दिन 16.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहे तो उनके समक्ष खोले जावेंगे।
- सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष एवं 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्यूरिटी के रूप में रोकी जावेगी।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ठेके से संबंधित निविदा प्रपत्र उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में शपथ पत्र देना अनिवार्य होगा।
- ईट से संबंधित निर्माण कार्यों में फ्लाई ऐश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेंट की खरीदी ठेकेदारों को स्वयं करनी होगी।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।


निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा

निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधिनस्त अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।

निविदा प्रपत्र कय कर अथवा वेबसाईट से सीधे डाउनलोड कर निविदा प्रपत्र हेतु निर्धारित राशि की अतिरिक्त डिमॉंड ड्राफ्ट सहित अपनी भरी हुई निविदा नगर पालिक निगम में रजिस्टर्ड/स्पीड पोस्ट द्वारा अमानत राशि के साथ प्रस्तुत करें।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।



अधीक्षक अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

1/4

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT

Name of Work **CONSTRUCTION AND MAINTENANCE OF SAMUDAYIK BHAWAN KHARMORA WARD NO. 31**

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	23.00	185.00	4,255.00
2	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	cum	15.60	65.00	1,014.00
3	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	7.80	371.00	2,893.80
4	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	cum	10.24	2659.00	27,228.16
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum		4073.00	
5	3.13	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including form work.	cum	1.72	4237.00	7,287.64
6	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)	cum	39.26	3263.00	128,105.38
7	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	28.00	121.00	3,388.00
8	9.2	Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. ISA 70X70X10@ 10 KG/M	Kg	520.00	66.00	34,320.00
9	9.11	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with 38mm steel pulleys complete with bolts, nuts, locking arrangement stoppers, handles including applying a priming coat of red oxide zinc chromate primer.	sqm	6.30	3330.00	20,979.00
10	9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	kg	60.00	75.00	4,500.00
11	9.14	Providing and fixing steel door made of angle iron of suitable sizes with	kg	50.00	79.50	3,975.00

ITEM	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	M.S. grill of approved pattern made of M.S. flats or square or round bars coat of red oxide zinc chromate primer.				
12	9.15 Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	kg	105.00	67.50	7,087.50
13	10.10 Extra for providing and fixing wind ties of 40x6mm flat iron section.	metre	78.00	118.00	9,204.00
14	10.11 Supply and fixing of pre-coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	sqm	89.76	636.00	57,087.36
15	10.16 Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws or with polymer coated J or L hooks, bolts and nuts and or G.I. seam bolts and nuts, G.I. plain and bitumen washers complete :				
	16.1 Ridges plain (500-600mm)	metre	13.00	552.00	7,176.00
	16.6 Gutter. (600 mm over all girth).	metre	13.00	629.00	8,177.00
16	11.2 Providing and making 12mm thick cement plaster of mix:				
	2.4 In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	235.60	91.50	21,557.40
17	11.3 Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	3.4 In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	252.00	107.00	26,964.00
18	12.3 Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.				
	3.2 50 mm thick	sqm	136.00	254.00	34,544.00
19	12.7 Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.				
	7.1 Size upto 200x300mm	sqm	15.00	587.00	8,805.00
20	12.9 Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.				

REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Size 300x300mm	sqm	20.00	692.00	13,840.00
21	14.13 Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	303.00	94.50	28,633.50
22	14.14 Finishing walls with water proofing cement paint of required shade to give an even shade.				
	14.2 On old work (one or more coats applied @ 2.20 kg/10 sqm)	sqm	50.00	25.50	1,275.00
23	14.15 Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:				
	15.1 On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	sqm	300.00	56.00	16,800.00
	15.2 On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)	sqm		37.00	
24	14.22 Painting on new work (two or more coats) to give an even shade with:				
	22.1 Satin synthetic enamel paint	sqm	45.00	55.00	2,475.00
25	14.23 Painting on old work (one or more coats) to give an even shade with:				
	23.1 Satin synthetic enamel paint	sqm	40.00	35.00	1,400.00
26	3.2 Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	15.00	4163.00	62,445.00
27	3.12 Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1 Thermo-Mechanically treated bars FE 415	kg	778.00	54.50	42,401.00
28	2.1 Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1 Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	23.00	139.00	3,197.00
	1.5 Columns, Pillars, Piers and likes- rectangular or square in shape	sqm	15.00	297.00	4,455.00
	1.7 Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	15.00	235.00	3,525.00
	1.8 Beams, lintels, cantilevers & walls	sqm	15.00	202.00	3,030.00
	1.13 Weather shade, chhajja, Cornices and mouldings	sqm	20.00	294.00	5,880.00
29	12.13 Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.				
	13.1 Size 600x600mm	sqm	80.00	1151.00	92,080.00

As per Estimate Amount Rs. 699984.74

Handwritten signature

Handwritten signature

Handwritten signature