

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क्र. 881 / 2025

सिस्टम टेंडर नं. 173520

कोरबा दिनांक 11.08.2025

ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र Form-A में निविदा आमंत्रित की जाती है:-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि - 05.09.2025 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 05.09.2025 सायंकाल 4.00 बजे से

क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (डिमांड ड्राफ्ट)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क्र 62 (पूर्व वार्ड क्र. 54) अंतर्गत सर्वमंगला मंदिर के समीप हसदेव नदी में घाट एवं पहुंच मार्ग का निर्माण कार्य (अधोसंरचना मंद)	48.53	36500/-	05 माह	1500/-	वर्ग डी एवं प्रवर श्रेणी	05.09.2025 से

शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र, पैन नम्बर, वैध जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं निर्धारित प्रारूप में शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा के पते पर भेजना होगा। निर्धारित तिथि को सायं 03:00 बजे के पश्चात् फिजिकल सबमिशन लिफाफा स्वीकार नहीं किया जायेगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निर्धारित प्रारूप में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात् का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मंद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन (वर्तमान तक वैधता) एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे एवं कर्मचारी भविष्य निधि संगठन (ई.पी.एफ.) एवं विभिन्न प्रावधानों को धारा 1952 के तहत निविदाकार का जीवित पंजीयन होना आवश्यक है साथ ही निविदा आमंत्रण दिनांक से विगत तीन माह की अवधि में जमा किये गये TRRN Payment Detail चालान की प्रति प्रस्तुत करना तथा ऑनलाईन अपलोड किया जाना अनिवार्य होगा।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ईट से संबंधित निर्माण कार्यों में प्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का विल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
10. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. निविदा प्रपत्र फार्म -ए की कंडिका 11 Price Adjustment (एस्कलेशन) देय नहीं होगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त अंतिम निर्णय एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान कार्य विशेष हेतु बजट आबंटन एवं राशि उपलब्ध होने पर किया जाएगा।
16. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
17. कार्य क्रियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
18. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		11.08.2025	15.30	11.08.2025	15.30	Release Tender
2		Bid Submission	11.08.2025	15.30	03.09.2025	17.30	
3		Physical Document Submission	11.08.2025	15.30	05.09.2025	15.00	
4	Tender Open		05.09.2025	16.00	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

Work Name :- construction of ghaat and approach road for hasdeo rever near sarwamangala temple
at ward no. 62

As per SOR: Schedule of rates public works department [PWD BUILDING-01-01-2015]

S. N.	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	1.2 Surface dressing of the ground including removing vegetation and making undulations and in-equalities not exceeding 15 cms in depth/height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).								
		1	25.00	15.00		375.00			
		1	25.00	15.00		375.00			
	CC	1	380.00	5.00		1900.00			
	changing room	8	2.00	2.00		32.00			
						2682.00	sqm	7.20	19310.40
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	In all types of soil								
		1	22.00	12.00	1.50	396.00			
		1	22.00	12.00	1.50	396.00			
	CC	1	380.00	4.50	0.20	342.00			
	changing room	8	1.80	1.80	1.80	46.66			
						1180.66	Cum	185.00	218421.36
	1.1.2 In ordinary rocks.								
		1	22.00	12.00	0.50	132.00			
		1	22.00	12.00	0.50	132.00			
	changing room	8	1.80	1.80	0.50	12.96			
						276.96	Cum	267.00	73948.32
	1.6 Extra for every additional lift of 1.5 m or part thereof.								
	1.6.2 Ordinary or hard rocks	1	22.00	12.00	0.50	132.00			
		1	22.00	12.00	0.50	132.00			
	changing room	8	1.80	1.80	0.50	12.96			
						276.96	Cum	47.50	13155.60
3	1.7 Extra rate for quantity of work executed in or under water and/ or liquid mud including pumping out water. cum 51.00								
						528.00			
						528.00			
						1056.00	cum	51.00	53856.00
4	1.9 Extra rate for lead for every 50m lead or part thereof and upto 150 m beyond 50 m free lead and 1.5 m free lift by manual means only.								
	1.9.1 For Soils					150.00			
						150.00			
						300.00	cum	33.00	9900.00
	1.9.2 For Rocks.					50.00			

	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
						50.00			
5	1.10 Pumping out water caused by springs tidal or river seepage, broken water main or drains and like during Excavation or during Excavation and laying of base concrete (volume to be calculated taking height from water level to bottom of pit and to be measured and paid) . cum 146.00					100.00	cum	49.50	4950.00
						200.00			
						200.00			
6	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.					400.00	cum	146.00	58400.00
						150.00			
						150.00			
7	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.					300.00	Cum	65.00	19500.00
						23.10			
						23.10			
	CC	1	380.00	4.20	0.10	159.60			
	changing room	8	1.50	1.50	0.10	1.80			
8	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.					207.60	Cum	371.00	77019.60
	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).								
	col.	1	20.50	10.50	0.10	21.53			
		1	20.50	10.50	0.10	21.53			
	CC	1	380.00	4.20	0.10	159.60			
	changing room	8	1.50	1.50	0.10	1.80			
						204.45	Cum	2970.00	607216.50
9	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 40mm nominal size).								
		1	382.00	4.00	0.20	305.60			
						305.60	cum	4073.00	1244708.80
10	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								


ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1:1.5:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
base	1	20.00	10.00	0.20	40.00			
wall	1	20.00	0.20	2.40	9.60			
	2	6.96	0.20		2.78			
	1	20.00	0.20	0.50	2.00			
	1	9.89	20.00	0.20	39.56			
	11	0.10	20.00		22.00			
	18	0.30	0.30	1.60	2.59			
	3	19.60	0.30	0.20	3.53			
	6	9.89	0.20	0.30	3.56			
base	1	20.00	10.00	0.20	40.00			
wall	1	20.00	0.20	2.40	9.60			
	2	6.96	0.20		2.78			
	1	20.00	0.20	0.50	2.00			
	1	9.89	20.00	0.20	39.56			
	11	0.10	20.00		22.00			
	18	0.30	0.30	1.60	2.59			
	3	19.60	0.30	0.20	3.53			
	6	9.89	0.20	0.30	3.56			
changing room col	8	1.50	1.50	0.40	7.20			
pb	2	12.00	0.20	0.30	1.44			
bend beam	2	12.00	0.20	0.10	0.48			
lb	2	12.00	0.20	0.20	0.96			
					261.33	cum	4163.00	1087911.79
11 Brick work with modular well burnt (open bhatta) clay bricks of crushing strength not less than 20 kg/sqcm and water absorption not more than 25% in foundation and plinth in:								
7.5.3 Cement Mortar 1:5 (1 cement : 5 coarse sand)								
changing room	2	12.00	0.20	0.50	2.40			
	2	12.00	0.20	2.10	10.08			
	2	1.20	0.20	2.10	-1.01			
					11.47	cum	3350.00	38431.20
12 Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:								
Thermo-Mechanically treated bars FE 415								
					8010.00			
					8010.00			
changing room					500.00			
					16520.00	kg	54.50	900340.00
13 Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								

ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
Foundations, footings, bases of columns plinth below, curtain wall in any shape and size and all type of wall below plinth level.								
	2	20.50		0.12	4.92			
	2	10.50		0.12	2.52			
	2	20.00		0.20	8.00			
	2	10.00		0.20	4.00			
	4	9.60		1.70	65.28			
	1	9.89		20.00	197.80			
	2	20.00		0.50	20.00			
	2	9.89		0.20	3.96			
	2	9.89		0.20	3.96			
	2	20.00		0.20	8.00			
	11	20.00		0.20	44.00			
18*4	72	0.30		1.60	34.56			
	3	19.60		0.20	11.76			
	6	19.60		0.30	35.28			
3*2	6	9.89		0.20	11.87			
6*2	12	9.89		0.30	35.60			
	2	20.50		0.12	4.92			
	2	10.50		0.12	2.52			
	2	20.00		0.20	8.00			
	2	10.00		0.20	4.00			
	4	9.60		1.70	65.28			
	1	9.89		20.00	197.80			
	2	20.00		0.50	20.00			
	2	9.89		0.20	3.96			
	2	9.89		0.20	3.96			
	2	20.00		0.20	8.00			
	11	20.00		0.20	44.00			
18*4	72	0.30		1.60	34.56			
	3	19.60		0.20	11.76			
	6	19.60		0.30	35.28			
3*2	6	9.89		0.20	11.87			
6*2	12	9.89		0.30	35.60			
changing room	32	1.50		0.40	19.20			
	2	12.00		0.30	7.20			
					1009.41	sqm	139.00	140307.71
14 Columns, Pillars, Piers and likes- rectangular or square in shape								
above pb	8	1.50		2.50	30.00			
					30.00	sqm	297.00	8910.00
15 1.19 Providing filling and compacting local earth (from approved source pit) in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
					110.00			
					110.00	cum	242.00	26620.00

	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
16	ams, lintels, cantilevers & walls								
	lb	2	12.00		0.20	4.80			
	b b	2	12.00		0.10	2.40			
						7.20	sqm	202.00	1454.40
17	3.10 Extra for laying PCC/ RCC, in or under water or liquid mud including cost of pumping or bailing out of water and removing slush etc. complete:								
						127.43			
						127.43			
						254.86	cum	261.00	66518.46
18	PLASTIC SHEET 125 MICRON								
						400.00			
						400.00	cum	95.00	38000.00
19	Providing and making 6mm thick cement plaster of mix:								
	In Cement mortar 1:4 (1 cement : 4 fine sand)								
	col	8	1.00		2.50	20.00			
	beam	2	12.00		0.30	7.20			
	beam	2	12.00		0.20	4.80			
	slab	2	12.00		0.10	2.40			
						34.40	sqm	87.00	2992.80
20	Providing and making 12mm thick cement plaster of mix:								
	In Cement mortar 1:5 (1 cement : 5 fine sand)								
		2	12.00		2.20	52.80			
	deduction	2	1.20		2.10	-5.04			
						47.76	sqm	96.50	4608.84
21	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:								
	In Cement mortar 1:5 (1 cement : 5 fine sand)								
		2	12.00		2.20	52.80			
		2	12.00		0.50	12.00			
	deduction	2	1.20		2.10	-5.04			
						59.76	sqm	113.00	6752.88
22	14.13 Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.								
	6 mm					34.40			
	12 mm					47.76			
	15 mm					59.76			
						141.92	sqm	94.50	13411.44

	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
23	12.13 Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.								
	12.13.1 Size 600x600mm	2	3.00	3.00		18.00			
		2	12.00	0.10		2.40			
						20.40	sqm	1151.00	23480.40
24	3.13 Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including form work.								
		2	12.00	0.20	0.05	0.24			
						0.24	cum	4237.00	1016.88
25	3.16 Making 50mm thick plinth protection of plain cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded crushed stone aggregate 20mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with sand including finishing the top smooth.								
		2	12.00	1.00		24.00			
						24.00	sqm	273.00	6552.00
26	14.10 Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.								
	14.10.1 On new work (two or more coats)								
						141.92			
						141.92	sqm	44.50	6315.44
27	9.6 Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.								
	9.6.2 In gratings, frames, guard bar, ladder, railings, brackets, gates and similar								
						210.00			
						210.00	kg	68.00	14280.00
	9.57 Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.								
	9.57.1 SS Grade 204								
						119.00			
						119.00	kg	467.00	55573.00
28	14.15 Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:								
	14.15.1 On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm) sqm								
	56.00								

	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
						141.92			
						141.92	sqm	56.00	7947.52
29	14.23 Painting on old work (one or more coats) to give an even shade with:								
	14.23.1 Satin synthetic enamel paint								
						21.00			
						21.00	sqm	55.00	1155.00
TOTAL =									4852966.35
Say Rs.									4853000.00


 Sub-Engineer
 Municipal Corporation
 Korba (C.G.)


 Asstt. Engineer
 Municipal Corporation
 Korba (C.G.)