

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क. 8246 / निर्माण / 2017

सिस्टम टेंडर नं. 48890

कोरबा, दिनांक 24.01.2018


द्वितीय ई-निविदा आमंत्रण सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत राक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु ई-निविदा आमंत्रित की जाती है :-

क	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क. 58 इमली छापर अंतर्गत आर.सी. सी. कल्वर्ट का निर्माण कार्य (निगम मद)	2938000.00	22500.00	5 माह	वर्ग डी एवं प्रवर श्रेणी	13.02.2019 से


शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पैन नम्बर, **जी.एस.टी.** पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का **स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।**
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. निविदा उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रदाय नहीं किया जावेगा।
6. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में **निविदा जारी तिथि से 10 दिवस पूर्व का नोटरी सत्यापित शपथपत्र** देना अनिवार्य होगा।
7. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का **1 प्रतिशत उपकर** के रूप में प्रत्येक देयक से कटौती की जावेगी।
8. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
9. कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेंट की खरीदी ठेकेदारों को स्वयं करनी होगी।
10. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
11. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपोजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से **15 दिवस** के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
12. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
13. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
14. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
15. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।


कार्यपालन अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		24.01.19	17.30	24.01.19	17.30	Release Tender
2		Bid Submission	24.01.19	17.30	12.02.19	17.30	
3	Tender Open		13.02.19	10.30	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

Construction of R.C.C. Culvert at ward no 58 Imlichhapar

Schedule of rates public works department (PWD BUILDING-01-01-2015)

S. N.	SOR Ref.	DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1	In all types of soil								
			1	27.00	10.00	0.90	243.00			
			4	3.00	0.50	0.80	4.80			
						Total=	247.80	Cum	185.00	45843.00
2	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
			1	27.00	10.00	0.15	40.50			
			4	3.00	0.50	0.10	0.60			
						Total=	41.10	Cum	371.00	15248.10
3	2.1	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	1	Foundations, footings, base of columns and plinth beam in any shape and size.								
			2	27.0		0.40	21.6			
			16	10.0		0.40	64.0			
						Total=	85.60	Sqm	139.00	11898.40
	2	Wall of any thickness including attached pilasters, buttresses etc.								
			8x2	6.0		3.50	336.0			
			8x4	0.5		3.50	56.0			
			4x2	3.0		2.80	67.2			
						Total=	459.20	Sqm	228.00	104697.60
	7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)								
			2	27.00		0.30	16.20			
			8	8.00		0.30	19.20			
			1	27.00	6.00		162.00			
						Total=	197.40	Sqm	235.00	46389.00
4	3.1	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.								
	3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).								
			1	27.00	10.00	0.15	40.50			
			4	3.00	0.50	0.15	0.90			
						Total=	41.40	Cum	2970.00	122958.00

		Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.											
1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).												
		1	27.00	10.00	0.40	108.00							
		4	3.00	0.35	2.80	11.76							
		8	6.00	0.35	3.50	58.80							
		2	27.00	0.30	0.30	4.86							
		1	27.00	6.00	0.30	48.60							
							Total=	232.02	Cum	4163.00	965899.26		
6	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:											
1	Thermo-Mechanically treated bars FE 415						Total=	25525.00	Kg	54.50	1391112.50		
19.36	Providing and fixing approved pipe hand rail to walls (ramps, stair cases) including cutting chases and repairing the same to original condition, applying a priming coat of red oxide zinc chromate primer.												
1	M.S Pipe												
							Total=	243.50	Kg	71.00	17288.50		
7	1.9	Extra rate for lead for every 50m lead or part thereof and upto 150 m beyond 50 m free lead and 1.5 m free lift by manual means only.											
1	For Soils (Extra lead 150 m)							76.90	Cum	99.00	7613.10		
8	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.						170.90	Cum	65.00	11108.50		
9	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.											
5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).												
		2	27	6.0	0.15	48.60							
							Total=	48.60		4073.00	197947.80		
										TOTAL =	2938003.76		

Say Rs.= 2938000.00

Sl. No. 57 / Banki Mongra Zone Dt. 28-06-17
Technically Approved for construction of R-C-C Culvert
at ward no. 58

Asstt. Engineer
Municipal Corporation
Korba (C.G.)

Sub Engineer
Municipal Corporation
Korba (C.G.)

In ward No. 58 for Rs. 29,38,000.00
(In words) Rs. twenty nine lakh thirty eight thousand only

Executive Engineer
Municipal Corporation
KORBA (C. G.)