

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क./निर्माण /2018/ 437

सिस्टम टेन्डर नं. 46203
तृतीय ई-निविदा आमंत्रण सूचना

कोरबा, दिनांक 04/10/2018

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई-निविदा आमंत्रित की जाती है :-

क्र	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क 06 में विकास भवन का मरम्मत एवं जीम सामग्री का प्रदाय एवं स्थापना कार्य	700000.00	5500/-	02 माह	वर्ग डी एवं प्रवर श्रेणी	17.01.2019 से


शर्त:-

1. निविदा दरे प्रबलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पैन नम्बर, **जी.एस.टी.** पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का **स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।**
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. निविदा उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा नियम, रायपुर से पंजीयन करारक कोड प्राप्त कर लिया हो अन्यथा निविदा प्रदाय नहीं किया जावेगा।
6. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में **निविदा जारी तिथि से 10 दिवस पूर्व का नोटरी सत्यापित** शपथपत्र देना अनिवार्य होगा।
7. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का **1 प्रतिशत उपकर** के रूप में प्रत्येक देयक से कटौती की जावेगी।
8. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
9. कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेंट की खरीदी ठेकेदारों को स्वयं करनी होगी।
10. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
11. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपोजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से **15 दिवस** के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
12. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
13. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
14. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
15. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		04.10.18	13.00	04.10.18	10.30	Release Tender
2		Bid Submission	04.10.18	10.30	16.01.19	17.30	
3	Tender Open		17.01.19	10.30	—	--	


EXECUTIVE ENGINEER
KORBA (CG)
 For, ~~Commissioner~~ Korba (C.G.)

DETAILED ESTIMATE

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

Powered By : Estimate Maker Software Pg. 1

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		screws complete:								
	65.1	125 mm								
			4				4.00			
						Total	4.00	each	55.50	222.00
9	18.76	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.								
	76.3	150 mm dia pipe.								
			1	6.00			6.00			
						Total	6.00	metre	440.00	2640.00
10	18.77	Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.								
	77.1	Tee/ Tee with door/ Bend 45° / Bend 90°								
	7.1.3	150 mm								
			2				2.00			
						Total	2.00	each	273.00	546.00
11	14.45	Removing dry or oil bound distemper by scraping sand papering and preparing the surfaces smooth including necessary repair to								

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		Scratches etc. complete.								
		-HALL	2X2	6.10	3.30		80.52			
			2X2	9.40	3.30		124.08			
		-CEILING	2X1	6.10	9.40		114.68			
		Deduction--W	5	0.50	1.20	1.50	-4.50			
		Deduction--D	5	0.50	1.10	2.40	-6.60			
		Deduction--W	1	0.50	2.40	1.50	-1.80			
		-BEAM	1	6.10	1.10		6.71			
		-TOILET	2	1.35	3.30		8.91			
			2	2.85	3.30		18.81			
			1	1.35	2.85		3.84			
		Deduction--V	2	0.50	0.60	0.45	-0.27			
		Deduction--D	1	0.50	1.10	2.40	-1.32			
			2	6.65	3.30		43.89			
			2	3.00	3.30		19.80			
		-CEILING	1	6.65	3.00		19.95			
			1	4.00	1.00		4.00			
		Deduction--DOOR	3	0.50	1.10	2.05	-3.38			
		-ROOM	2X2	3.45	3.30		45.54			
			2X2	3.00	3.30		39.60			
		Deduction--W	2	0.50	1.80	1.50	-2.70			
		Deduction--D	2	0.50	1.10	2.05	-2.25			
		-HALL	2X2	9.38	3.30		123.81			
			2X2	6.10	3.30		80.52			
		-CEILING	2X1	9.35	6.10		114.07			
		Deduction--W	3	0.50	1.80	1.50	-4.05			
		Deduction--W	2	0.50	1.20	1.50	-1.80			
		Deduction--D	5	0.50	1.10	2.40	-6.60			
		-COLUMN	2X2	1.20	3.30		15.84			
			2X1	2.50	3.30		16.50			
			2X1	4.80	3.30		31.68			
		-ROOM	2X2	3.20	3.30		42.24			
			2X2	4.50	3.30		59.40			
			2X1	3.20	4.50		28.80			
		Deduction--W	1	0.50	1.20	1.50	-0.90			
		Deduction--W	1	0.50	1.80	1.50	-1.35			
		Deduction--D	4	0.50	1.10	2.10	-4.62			
		-BATH ROOM	2	4.80	3.30		31.68			
		Deduction--	3	0.50	1.10	2.05	-3.38			
		Deduction--V	2	0.50	0.60	0.45	-0.27			
			2X2	4.40	3.30		58.08			
			2X2	3.40	3.30		44.88			
			2X1	4.40	3.40		29.92			
		Deduction--W	1	0.50	1.10	1.50	-0.82			
			2X2	5.60	3.30		73.92			
			2X2	3.00	3.30		39.60			
			2X2	3.00	5.60		67.20			

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT	
							Total	169.65	sqm	35.00	5937.75
16	NS-2	405 Commercial Make - Aerofit	1				1.00				
							Total	1.00	Nos	157000.00	157000.00
17	NS-4	Plan Bench Commercial Model No - SB-20 Make Aerofit	2				2.00				
							Total	2.00	Nos	6600.00	13200.00
18	NS-5	Crazy Fit Machine DC Motor 1 H P Mo. No. EXFOO 1 C Make Aerofit	3				3.00				
							Total	3.00	No	48600.00	145800.00
19	NS-7	Magnetic Uprit + Bike Mo. No. 350U Make Aerofit	2				2.00				
							Total	2.00	Nos	28000.00	56000.00
20	NS-8	Romming Machine Modle No 403 B	1				1.00				
							Total	1.00	Nos	27150.00	27150.00
21	NS-9	AB Circle Commercial Model No. A F 007	1				1.00				
							Total	1.00	Nos	21100.00	21100.00
22	NS-11	Rebber Plats Commercial	1				1.00				
							Total	1.00	100 kg	9500.00	9500.00
23	NS-13	Steel Rod	99				99.00				
							Total	99.00	20 ft	90.00	8910.00
As per Estimate Amount Rs.										666587.07	

As per Estimate Amount Rs. 666587.07
Say Rs.

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)

DETAILED ESTIMATE

Name of Work : INTERNAL ELECRIFACTION OF VIKASH BHAWAN WARD NO 06
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD ELECTRICAL-01-08-2015]

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	4.7	Wiring for light/ fan/ exhaust fan / call bell point with 1.5 sqmm FR PVC insulated stranded copper conductor single core cable in surface PVC conduit, with 5 amp modular switch, modular base and cover plate, suitable size G.I. box and earthing the point with same size cable as required.								
	1	Short Point	3				3.00			
						Total	3.00	Point	252.00	756.00
	2	Medium Point	3				3.00			
						Total	3.00	Point	394.00	1182.00
	3	Long Point	2				2.00			
						Total	2.00	Point	518.00	1036.00
2	4.9	Extra for providing and fixing light plug point on board in surface PVC conduit point wiring with modular type 3 pin 5 amp socket outlet and 5 amp switch including cost of base and cover plate and G. I. box etc. as required.								
			4				4.00			
						Total	4.00	Point	240.00	960.00
3	8.6	Supplying, installation, testing and commissioning of following sizes heavy duty (continuous running) 1400 rpm exhaust fan in existing opening in wall including earthing etc.								

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		complete as required.								
	1	300 mm sweep								
			2				2.00			
						Total	2.00	Each	2558.00	5116.00
4	8.18	Supplying, fixing, testing and commissioning of following CFL (Built in choke type) in existing lighting luminaries as required.								
	5	20 Watt								
			6				6.00			
						Total	6.00	Each	233.00	1398.00
5	11.3	Supplying and fixing on surface/ recess following way, 240 volts SP&N MCB distribution board consumer unit of sheet steel phosphatized and powder painted, complete with tinned copper busbar, neutral busbar, earth bar, din bar, detachable gland plate, including interconnections, earthing etc. as required. (But without MCB/RCCB/Isolator)								
	2	2 + 8 way								
			1				1.00			
						Total	1.00	Each	816.00	816.00
6	11.10	Supplying and fixing SP MCB, 240 volts, 'B' curve, suitable for lighting and other loads in the existing MCB DB complete with connections, testing and commissioning etc. as required.								
	1	6 amps to 32 amps								
			1				1.00			
						Total	1.00	Each	154.00	154.00
7	14.2	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories,								

		DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as required.								
			1				1.00			
						Total	1.00	Set	3454.00	3454.00
8	14.18	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing as required.								
			1	25.00			25.00			
						Total	25.00	Metre	37.50	937.50
9	17.8	Supplying and laying following sizes one number PVC insulated/ XLPE, PVC sheathed, unarmoured, aluminium conductor power cable of 1.1 KV grade on surface/ existing cable tray with 1 mm thick GI saddle as required.								
	13	4 x 10 sq. mm.								
			1	15.00			15.00			
						Total	15.00	Metre	108.00	1620.00
10	26.3	Supplying, installation, testing and commissioning of submersible pump set for water supply system with submersible motor directly coupled to multi-stage submersible pump of specified discharge capacity, head, delivery size in existing bore well including 2 sets of suitable size holding clamps made out of 50 mm X 6 mm MS flat, connection with suitable submersible cable of standard length etc. as required.								
	1	1.0 HP, single phase								
			1				1.00			

REF ITEM DESCRIPTION

N

L

B

H/D

QTY

UNIT

RATE

AMOUNT

Total

1.00

Each

15866.00

15866.00

As per Estimate Amount Rs.

33295.50

Say Rs.

PART A - 6,66,587.07

6,99,882.57

54

7,00,000.00



Sub Engineer
Nagar Palik Nigam
Korba (C.G.)

Astt. Engineer
Nagar Palik Nigam
Korba (C.G.)

E.E. Engineer
Nagar Palik Nigam
Korba (C.G.)