कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

क्र.क./549/निर्माण कोरबा जोन/2019 कोरबा, दिनांक 11.10.2019

निविदा आमंत्रण सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में निर्माण कार्य हेतु पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (सक्त) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर एवं शेड्यूल अनुसार कार्यो हेतु मैन्युअल/ऑनलाईन निविदा वेबसाइड से डाउनलोड कर आमंत्रित की जाती है :–

क	कार्य का नाम (प्रभारी मंत्री मद)	प्राक्कलन राशि	धरोहर राशि	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने हेतु आवेदन प्रस्तुत करने की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1.	वार्ड क्र. 10, सीतामणी कुम्हार मोहल्ला में बिसाहूराम कुम्मकार निवास के पास सार्वजनिक मंच का निर्माण कार्य। (प्रभारी मंत्री मद)	5,00,000/–	5,000 /–	750/–	03 माह	सक्षम श्रेणी	25.10.2019	26.10.2019	31.10.2019

शर्तें :–

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथके से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा प्रपत्र की प्रतियॉं नगर पालिक निगम, साकेत भवन रामपुर, कोरबा कार्यालय से उपरोक्त कार्यों हेतु नाम के सम्मुख अंकित राशि नगद जमा कर उपरलिखि तिथि तक सायं 5.00 बजे तक अवकाश के दिनों को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा मांगाना हो तो रू. 50/– अधिक भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की ज़िम्मेदारी इस कार्यालय की नही होगी।
3. निविदा प्रपत्र स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किए जावेगे। निर्धारित तिथि को 3.00 बजे के पश्चात प्राप्त निविदाऐं स्वीकार नही की जावेंगीं।
4. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य ना किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरूद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नही होगी।
5. निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड)की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकरी पिछले वित्तीय वर्ष का आय प्रमाण पत्र/पेन नम्बर पत्र, जी. एस. टी. प्रमाण पत्र एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र एवं धरोहर राशि निविदा प्रपत्र प्राप्त करने के तिथि के 5.30 बजे तक अनिर्वाय होगा।
6. निविदा प्रपत्र उन्ही ठेकेदारो को दिया जायेगा जिन्हे इस प्रकार के कार्यों का अनुभव हो।
7. पूर्ण रूप से भरी निविदा प्रपत्र उपरोक्त तिथि को 15.00 बजे तक प्राप्त की जा सकती है और उसी दिन 16.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहे तो उनके समक्ष खोले जावेंगे।
8. सम्पूर्ण किये गये कार्यों के लिये प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिये एवं मरम्मत एवं संधारण प्रवृति के कार्य को छोड़कर 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में प्रत्येक चल देयकों में से 03 वर्ष के लिये रोकी जावेगी।
9. आवेदन के साथ रू. 10.00 लाख या उससे अधिक लागत के निर्माण कार्यो की निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत् पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
10. ठेके से संबंधित निविदा प्रपत्र उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
11. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यो का विवरण राशि सहित मूलप्रति में शपथ पत्र देना अनिवार्य होगा।
12. कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेंन्ट की खरीदी ठेकेदारों को स्वयं करनी होगी।
13. निविदा प्रपत्र अहस्तांतरणीय होगा।
14. निविदा दरों असमान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
15. सशर्त निविदाओं पर विचार नही किया जावेगा।
16. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधिनस्त अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
17. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
18. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा (कोरबा जोन) से प्राप्त किये जा सकते है।

नोटः–
1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जाव

कार्यपालन अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

OFFICE OF THE MUNICIPAL CORPORATION,KORBA(C.G.)

DETAILED ESTIMATE

ne of work:- Construction of Community Manch Near Bisahuram Kumbhkar House At Sitamani Ward no - 10

As per SOR:Schedule of rates public works department[PWD BUILDING-01-01-2015]

	SOR Ref.	ITEM DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1	In all types of soil								
		column	4	1.50	1.50	1.50	13.50			
			4	1.50	0.40	0.60	1.44			
			1	40.00	2.50	0.30	30.00			
						Total =	44.94	Cum	185.00	8313.90
2	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.								
		footing	4	4	0.6	0.40	3.84			
			4	4	1.2	0.80	15.36			
		plinth beam	4	2	4.400	0.30	10.56			
						Total =	29.76	Sqm	139.00	4136.64
	5	Columns, Pillars, Piers and likes- rectangular or square in shape								
			4	1.2		2.9	13.92			
						Total =	13.92	sqm	297.00	4134.24
	7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)								
		SLAB	1	4.60	4.60		21.16			

			2	4.60	0.125		1.15			
			2	4.60	0.125		1.15			
						Total =	23.46	sqm	235.00	5513.10
	8	Beams, lintels, cantilevers & walls								
		lintel+ top	16	4.40	0.20		14.08			
			1	4.60	0.60		2.76			
						Total =	16.84	sqm	202.00	3401.68
3	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
		column	4	1.50	1.50	0.15	1.35			
			4	1.50	0.40	0.15	0.36			
		filling under floor	1	4.40	4.40	0.60	11.62			
			1	40.00	2.50	0.10	10.00			
						Total =	23.33	Cum	371.00	8653.95
4	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	3	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).								
		column	4	1.50	1.50	0.15	1.35			
			4	1.50	0.40	0.10	0.24			
		filling under floor	1	4.40	4.40	0.15	2.90			
			1	40.00	2.50	0.10	10.00			
						Total =	14.49	Cum	2659.00	38539.55

5	3.7	Filling from available excavated stuff (Excluding rock) in trenches, plinth,sides of foundation etc. in layers not exceeding 20cm in depthconsolidating each deposited layer by ramming and watering with a leadupto 50 M. and lift upto 1.5 M.								
						Total =	50.00	Cum	65.00	3250.00
6	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
		raft c1	4	1.50	1.50	0.30	2.70			
		footing	4	0.60	0.6	0.40	0.58			
		column below plinth	4	0.30	0.300	0.80	0.29			
		plinth beam	4	4.40	0.200	0.30	1.06			
		C1	4	0.30	0.30	2.90	1.04			
			1	4.40	0.60	0.10	0.26			
		LINTEL BEAM	8	4.40	0.20	0.20	1.41			
		TOP BEAM	8	4.40	0.20	0.20	1.41			
		SLAB	1	4.60	4.60	0.125	2.65			
			4	0.60	0.60	0.10	0.14			
		C1	4	0.30	0.30	0.40	0.14			
			2	5.00	0.60	0.10	0.60			
						Total =	12.28	Cum	4163.00	51109.15
7	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:								
			100		12.40		1240.00			
						Total =	1240.00	kg	54.50	67580.00

8	19	Providing filling and compacting local earth (from approved source pit) in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. Complete								
			1	4.40	4.40	0.80	15.49			
						Total =	15.49	Cum	242.00	3748.10
9	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:								
	3	Cement Mortar 1:5 (1 cement : 5 coarse sand)								
			4	3.90	0.20	0.80	2.50			
			4	3.90	0.20	2.90	9.05			
			4	3.90	0.20	0.40	1.25			
						Total =	12.79	Cum	3350.00	42853.20
10	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
			1	68.00	2.50	0.15	25.50			
			1	3.00	2.50	0.10	0.75			
						Total =	26.25	Cum	4073.00	106916.25

11	12.3	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete								
	1	Size 600x600mm								
			1	4.60	4.60		21.16			
						Total =	21.16	sqm	1151.00	24355.16
12	12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.								
	2	Size above 200x300mm								
			8	2.40		2.10	40.32			
			8	2.00		2.10	33.60			
			1	6.00		1.80	10.80			
						Total =	84.72	sqm	587.00	49730.64

13	9.5	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.								
		window	3	50.00			150.00			
						Total =	150.00	Kg	67.50	10125.00
14	9.11	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with 38mm steel pulleys complete with bolts, nuts, locking arrangement stoppers, handles including applying a priming coat of red oxide zinc chromate primer.								
			1	3.50		2.10	7.35			
						Total =	7.35	sqm	3330.00	24475.50
15	11.1	Providing and making 6mm thick cement plaster of mix								
	2	In Cement mortar 1:4 (1 cement : 4 fine sand)								
			1	4.6	4.60		21.16			
						Total =	21.16	sqm	87.00	1840.92
16	11.2	Providing and making 12mm thick cement plaster of mix								
	4	In Cement Mortar 1:6 (1 cement : 6 fine sand)								
			4	4.40		5.95	104.72			
						Total	104.72			

17	13	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:								
	4	In Cement Mortar 1:6 (1 cement : 6 fine sand)								
			4	4.00		3.30	52.80			
						Total	52.80	sqm	107.00	5649.60
18	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.								
							178.68			
						Total	178.68	sqm	94.50	16885.26
19	14.1	Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.					73.96	sqm	44.50	3291.22
	1	On new work (Two or more coats)								
20	14.14	Finishing walls with water proofing cement paint of required shade to give an even shade.					104.72	sqm	41.00	4293.52
	1	On new work (Two or more coats)								
21	14.22	Painting on new work (two or more coats) to give an even shade								
	2	Premium synthetic enamel paint	3	1.50	1.20		5.40			
			3	3.50	2.10		22.05			
						Total =	27.45	sqm	47.00	1290.15
									TOTAL=	**499668.60**
									Say rs.=	**500000.00**

Asstt. Engineer
Municipal Corporation
Korba (C.G.)

Sub Engineer
Municipal Corporation