



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

दर्दी जोन

फा.क्र./726,728,730,731,732,733, 735, 734 /निर्माण (दर्दी जोन)/2025/

कोरबा, दिनांक 09.06.2026

प्रथम निविदा आमंत्रण की सूचना

लोक निर्माण विभाग में एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित निर्माण कार्य हेतु मैनुवल निविदा वेबसाईड से डाउनलोड कर मुहरबंद लिफाफे में निविदा आमंत्रित की जाती है :-


- निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने की अंतिम तिथि
- निविदा खुलने की अंतिम तिथि

- दिनांक 01.07.2026 सायंकाल 3:00 बजे तक
- दिनांक 01.07.2026 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1.	वार्ड कं. 48 हसदेव कमांक 01 अंतर्गत मॉ कलमी दाई के पास सार्वजनिक सामुदायिक एवं सांस्कृतिक भवन का संधारण एवं भवन में नयी सुविधा की व्यवस्था। (पार्षद मद)	7,00,000/-	5,300/-	750/-	Form-A	04 माह	सक्षम श्रेणी	01.07.2026
2.	वार्ड कं. 59 फर्टिलाइजर बर पेंड शिव मंदिर के पास अहाता निर्माण एवं अन्य विस्तार कार्य। (विधायक-प्रभारी मंत्री मद वर्ष 2025-26)	3,00,000/-	3,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.07.2026
3.	वार्ड कं. 55 नागिन भांठा सुमेधा में स्वास्थ्य केन्द्र के पास निर्माण। (विधायक-प्रभारी मंत्री मद वर्ष 2025-26)	5,00,000/-	5,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.07.2026
4.	वार्ड कं 54 जमनीपाली स्थित कबार आश्रम में शेड निर्माण कार्य। (विधायक-प्रभारी मंत्री मद वर्ष 2025-26)	5,00,000/-	5,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.07.2026
5.	वार्ड कं. 49 ओडिया बस्ती में मंच के सामने शेड निर्माण कार्य। (विधायक-प्रभारी मंत्री मद वर्ष 2025-26)	5,00,000/-	5,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.07.2026
6.	वार्ड कं. 52 जनकपुरी पाईप लाईन शिव मंदिर के पास मंच निर्माण। (विधायक-प्रभारी मंत्री मद वर्ष 2025-26)	5,00,000/-	5,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.07.2026
7.	वार्ड कं. 58 श्यामनगर साडा कालोनी में जोगी जनरल स्टोर्स के पास का जीर्णोद्धार एवं अन्य विस्तार कार्य। (विधायक-प्रभारी मंत्री मद वर्ष 2025-26)	5,00,000/-	5,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.07.2026
8.	वार्ड कं. 53 जनकपुरी मोहल्ला हनुमान मंदिर पावर सिटी पाईप लाईन के पास मंच निर्माण। (विधायक-प्रभारी मंत्री मद वर्ष 2025-26)	5,00,000/-	5,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.07.2026

उपरोक्त कार्यों की निविदा की सामान्य शर्त, धरोहर निविदा विज्ञप्ति, निविदा दस्तावेज व अन्य जानकारी कार्यालयीन अवधि में कार्यालय से प्राप्त की जा सकती है, साथ ही यह जानकारी विभागीय वेबसाईट Website : www.korbamunicipal.in एवं www.uad.cg.gov.in में देखा एवं डाउनलोड किया जा सकता है।

// स्वच्छ भारत निर्माण में योगदान दें //


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)



OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)
DETAIL ESTIMATE

Name Of Work :- वार्ड क्र. 52 जनकपुरी पाईप लाईन शिव मंदिर के पास मंच निर्माण कार्य।

As Per SOR :- SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING - 01.01.2015]

S. N.	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	1.2	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).								
			1	12.00	10.00		120.00			
							120.00	Sqm	7.20	864.00
2	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1.1	In all types of soils.								
		col	6	2.20	2.20	1.80	52.27			
		wall	1	13.88	0.50	0.40	2.78			
			1	9.90	0.50	0.40	1.98			
							57.03	Cum	185.00	10550.18
3	1.6	Extra for every additional lift of 1.5 m or part thereof.								
	6.1	All types of soils								
		col	6	2.20	2.20	0.30	8.71			
						Total	8.71	Cum	26.50	230.87
4	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.								
							37.68	Sqm	65.00	2449.20

5	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
			6	2.20	2.20	0.12	3.48			
			1	6.00	7.00	0.20	8.40			
			1	7.50	2.40	0.20	3.60			
							15.48	Cum	371.00	5744.86
6	1.19	Providing filling and compacting local earth (from approved source pit) in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete								
			1	6.00	7.00	0.50	21.00			
			1	7.50	2.40	0.30	5.40			
							26.40	Cum	242.00	5082.00
7	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.								
		col	24	1.80		0.12	5.18			
			2	10.00		0.12	2.40			
			3	4.00		0.12	1.44			
			24	1.60		0.50	19.20			
			6	1.20		1.63	11.74			
			2	25.88		0.30	15.53			
							55.49	Sqm	139.00	7712.83
	1.3	Window sills, anchor blocks, string course, bends, copings, bed plates and like.								
			2	18.38		0.10	3.68			
			2	31.40		0.08	5.02			
							8.70	Sqm	184.00	1600.80
	1.4	Edge of slab, breaks in floor and walls upto 200mm								
			1	32.20			32.20			

		1	13.00			13.00			
						45.20	metre	34.00	1536.80
1.5	Columns, Pillars, Piers and likes- rectangular or square in shape								
		6	1.20		3.90	28.08			
						28.08	Sqm	297.00	8339.76
1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)								
		1	7.40	8.70		64.38			
						64.38	Sqm	235.00	15129.30
1.8	Beams, lintels, cantilevers & walls								
		1	18.38	0.20		3.68			
		2	18.38	0.20		7.35			
		1	18.38	0.20		3.68			
		2	18.38	0.30		11.03			
		1	6.00	0.20		1.20			
		2	6.00	0.50		6.00			
		1	7.50	0.20		1.50			
		2	7.50	0.50		7.50			
		2	1.00	0.20		0.40			
		4	1.00	0.20		0.80			
						43.13	Sqm	202.00	8712.66
1.13	Weather shade, chhajja, Cornices and mouldings								
		2	7.15	0.50		7.15			
		2	7.15	0.08		1.14			
		4	0.50	0.09		0.18			
						8.47	Sqm	294.00	2491.36
8	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.							
	1.2	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size).							
	col	6	1.80	1.80	0.12	2.33			
	wall	1	25.88	0.40	0.10	1.04			
		1	11.50	0.40	0.10	0.46			
	step	2	1.60	1.30	0.10	0.42			
						4.24	Cum	3552.00	15074.69

			1	25.88	0.20	0.08	0.41			
			1	11.90	0.20	0.08	0.19			
							0.60	Cum	4237.00	2561.18
13	3.14	Providing and mixing water proofing material in PCC/ RCC work in the proportion recommended by the manufacturer.								
							30.00	Kg	43.50	1305.00
14	3.16	Making 50mm thick plinth protection of plain cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded crushed stone aggregate 20mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with sand including finishing the top smooth.								
			1	34.80	0.40		13.92	sqm	273.00	3800.16
15	4.13	Grading roof for water proofing treatment with:								
	13.1	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)								
			1	7.40	8.70	0.03	1.93			
							1.93	Cum	3817.00	7372.15
16	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:								
	5.3	Cement Mortar 1:5 (1 cement : 5 coarse sand)								
			1	25.88	0.20	0.60	3.11			
			1	11.90	0.20	0.40	0.95			
			1	18.38	0.20	2.80	10.29			
			1	11.90	0.20	0.50	1.19			
			2	1.50	1.20	0.40	1.44			
			2	1.50	0.90	0.20	0.54			
			2	1.50	0.60	0.20	0.36			
			4	2.00	0.20	1.50	2.40			
		Deduction ----					15.48	Cum	3350.00	51859.34

17	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:					6.15	Cum	121.00	744.15
18	9.15	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.					150.00	kg	67.50	10125.00
19	9.16	Providing and fixing M.S. frames of doors, windows, ventilators and cupboards joints mitred and welded with 15x3 mm lugs 10cm long embedded in cement concrete blocks 15x10x10cm of grade M-10 or with wooden plugs and screws or with dash fastener or rawl plugs and screws or with fixing clips or with bolts and nuts as required including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer					50.00	kg	73.50	3675.00
	16.2	Angle-iron frames								
20	9.57	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete								
	57.2	SS Grade 304					40.00	kg	525.00	21000.00

