# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

## मुख्य कार्यालय – साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

मु.का. दूरभाष : 221288, 222672, फैक्स : 07759–221929, पो. बॉक्स नं.–12 पिन कोड – 495677

फा.क्र./8414 से 8419 तक/टी.पी. नगर जोन/ 2019/ कोरबा, दिनांक 12.09.2019

# निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्युल अनुसार आयटम दरो पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल/ऑनलाईन निविदा वेबसाईट से डाउनलोड कर आमंत्रित की जाती है :–

| क्र. | कार्य का नाम | प्राक्कलन राशि में | धरोहर राशि रू में | निविदा प्रपत्र का मूल्य | कार्यावधि | ठेकेदार का वर्ग | निविदा प्रपत्र प्राप्त करने आवेदन की अंतिम तिथि | निविदा प्रपत्र प्राप्त करने की अंतिम तिथि | निविदा खुलने की अंतिम तिथि |
|---|---|---|---|---|---|---|---|---|---|
| 1 | वार्ड क्र. 16 अंतर्गत पार्थ फाउण्डेशन के शौचालय एवं मूत्रालय का निर्माण कार्य। **(महापौर मद)** | 3,00,000/– | 3,000/– | 750/– | 03 माह | सक्षम श्रेणी | 20.09.2019 | 24.09.2019 | 01.10.2019 |
| 2 | वार्ड क्र. 23 अंतर्गत वाल्मिकी निवास में निर्मित मंच का जीणोद्धार एवं छत का निर्माण कार्य। **(महापौर मद)** | 3,00,000/– | 3,000/– | 750/– | 03 माह | सक्षम श्रेणी | 20.09.2019 | 24.09.2019 | 01.10.2019 |
| 3 | वार्ड क्र. 25 अंतर्गत सर्वराजी पेटी ठेकेदार संघ बैठक स्थल के पास शौचालय एवं मूत्रालय का निर्माण कार्य। **(महापौर मद)** | 3,00,000/– | 3,000/– | 750/– | 03 माह | सक्षम श्रेणी | 20.09.2019 | 24.09.2019 | 01.10.2019 |
| 4 | वार्ड क्र. 25 पेंटर संघ बैठक स्थल के पास शौचालय एवं मूत्रालय का निर्माण कार्य। **(महापौर मद)** | 3,00,000/– | 3,000/– | 750/– | 03 माह | सक्षम श्रेणी | 20.09.2019 | 24.09.2019 | 01.10.2019 |
| 5 | वार्ड क्र. 25 प्रेस कर्मचारी कल्याण संघ बैठक स्थल के पास शौचालय एवं मूत्रालय का निर्माण कार्य। **(महापौर मद)** | 4,00,000/– | 4,000/– | 750/– | 03 माह | सक्षम श्रेणी | 20.09.2019 | 24.09.2019 | 01.10.2019 |
| 6 | वार्ड क्र. 30 मानिकपुर में खडिया समाज भवन के पास शौचालय एवं मूत्रालय का निर्माण कार्य। **(महापौर मद)** | 3,00,000/– | 4,000/– | 750/– | 03 माह | सक्षम श्रेणी | 20.09.2019 | 24.09.2019 | 01.10.2019 |

शर्तें:–

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा प्रपत्र की प्रतियॉ नगर पालिक निगम, साकेत भवन रामपुर, कोरबा कार्यालय से उपरोक्त कार्यों हेतु नाम के सममुख अंकित राशि नगद जमा कर उपर लिखि तिथि तक सायं 5:00 बजे तक अवकाश के दिनों को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा मंगाना हो तो **रू. 50/– अधिक** भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की जिम्मेदारी इस कार्यालय की नहीं होगी।
3. निविदा प्रपत्र स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किए जावेगे। **निर्धारित तिथि को 3.00 बजे के पश्चात् प्राप्त निविदाऐं स्वीकार नही की जावेंगीं।**
4. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरूद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नही होगी।
5. निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड)की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकरी पिछले वित्तीय वर्ष का आय प्रमाण पत्र/पेन नम्बर पत्र एवं जी.एस.टी. पंजीयन प्रमाण पत्र प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र एवं **धरोहर राशि सहित निविदा प्रपत्र प्राप्त करने के अंतिम तिथि को 5.30 बजे सायं तक आवेदन प्रस्तुत करना अनिवार्य होगा।**
6. पूर्ण रूप से भरी निविदा प्रपत्र उपरोक्त तिथि को 15.00 बजे तक प्राप्त की जा सकती है और उसी दिन **16.00 बजे** ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहे तो उनके समक्ष खोले जावेंगे।
7. सम्पूर्ण किये गये कार्यों के लिये **5 प्रतिशत** सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष एवं **5 प्रतिशत पृथक से 03** वर्ष की गारंटी के लिये परफार्मेंस सिक्यूरिटी के रूप में रोकी जावेगी।
8. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन ) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत् पंजीयन कराना आवष्यक होगा तथा निर्माण लागत का **1 प्रतिशत उपकर** के रूप में प्रत्येक देयक से कटौती की जावेगी।
9. ठेके से संबंधित निविदा प्रपत्र उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि **कर्मचारी भविष्य निधि संगठन** एवं **कर्मचारी राज्य बीमा निगम रायपुर से पंजीयन** कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
10. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यो का विवरण राशि सहित मूल प्रति में शपथ पत्र देना अनिवार्य होगा।
11. ईंट से संबंधित निर्माण कार्यों में फ्लाई ऐश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
12. कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेंन्ट की खरीदी ठेकेदारों को स्वयं करनी होगी।

निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से **15 दिवस** के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।

14. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नही किया जावेगा
15. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधिनस्त अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
16. निविदा प्रपत्र कय कर अथवा वेबसाईट से सीधे डाउनलोड कर निविदा प्रपत्र हेतु निर्धारित राशि की अतिरिक्त डिमॉड ड्राफ्ट सहित अपनी भरी हुई निविदा नगर पालिक निगम में रजिस्टर्ड/स्पीड पोस्ट द्वारा अमानत राशि के साथ प्रस्तुत करें।

नोटः–
1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

**अधीक्षण अभियंता**
नगर पालिक निगम
कोरबा (छ.ग.)

# OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

## ABSTRACT

**Name of Work : Construction of Urinal & Toilet Near Painter Sangh Baithak Sthal, Ward No. 25**

**As per Sor : Schedule of Rates Public Works Department [ PWD BUILDING 01.01.2015]**

| S.N. | ITEM DESCRIPTION | Qty | Unit | Rate | Amount |
|---|---|---|---|---|---|
| 1 | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead pto 50 m,( at leas 5m away from the excavated area), including dressing | | | | |
| | In all types of soil | 34.84 | Cum | 185.00 | 6445.40 |
| 2 | 1.17 Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead | 21.25 | Cum | 65.00 | 1381.25 |
| 3 | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. | 1.35 | Cum | 371.00 | 500.85 |
| 4 | providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation , plinth and at ground level | | | | |
| | 1:3:6 (1 cement : 3 Coarde sand : 6 graded stone aggrgate 40mm nominal | 4.21 | Cum | 2970.00 | 12503.70 |
| | 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm | 1.55 | Cum | 4073.00 | 6313.15 |
| 5 | Provinding and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work . | | | | |
| | 1:1 1/2 :3 (1Cement :1 1/2 coarse sand : 3 graded stone aggrgate 20mm | 11.82 | Cum | 4163.00 | 49206.66 |
| 6 | Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth: | 4.06 | Cum | 97.50 | 395.85 |
| 7 | Providing and placing in position reinforcement for R.C.C. work including straightening cutting bending binding etc. complete as per drawings including cost of binding wire all complete. | | | | |
| | Thermo-Mechanically treated bars | 876.12 | Kg | 54.50 | 47748.54 |
| 8 | providing and fixing formwork inxluding centering shuttering strutting staging propping braxing etc. complete and inxluding its removal at all | | | | |
| | Foundations, footings, base of columns and plinth beam in any shape and | 19.02 | Sqm | 139.00 | 2643.78 |
| | Columns, Pillars, Piers and likes- rectangular or square in shape | 17.40 | Sqm | 297.00 | 5167.80 |
| | Beams, lintels, cantilevers & walls | 10.66 | Sqm | 202.00 | 2153.32 |
| | Suspended floors, roofs, access platform, balconies (plain surfaces) and | 19.68 | Sqm | 235.00 | 4624.80 |
| 9 | Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: | | | | |
| | Cement Mortar 1:5 (1 Cement : 5 Coarse Sand) | 16.12 | Cum | 3350.00 | 54002.00 |
| 10 | Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth: | 10.36 | Cum | 121.00 | 1253.56 |
| 11 | Providing and mixing water proofing material in PCC/ RCC work in the proportion recommended by the manufacturer. | 5.00 | Kg | 43.50 | 217.50 |
| 12 | Providing and fixing steel door with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings | 180.72 | Kg | 75.00 | 13554.00 |
| 13 | Providing and making 6mm thick cement plaster of mix: | | | | |
| | In Cement mortar 1:4 (1 cement : 4 fine sand) | 30.50 | Sqm | 87.00 | 2653.50 |
| 14 | Providing and making 12mm thick cement plaster of mix | | | | |
| | In Cement Mortar 1:5 (1 cement : 5 fine sand) | 92.06 | Sqm | 96.50 | 8883.79 |
| 15 | 15mm thick cement plaster on the rough side of single or half brick wall of mix: | | | | |
| | In Cement Mortar 1:5 (1 cement : 5 fine sand) | 94.22 | Sqm | 113.00 | 10646.86 |

| | ITEM DESCRIPTION | Qty | Unit | Rate | Amount |
|---|---|---|---|---|---|
| | viding and fixing ceramic glazed wall tiles conforming to IS : 156[illegible] of approved make, colours, shades and size on wall and dados over 1[illegible]m thick bed of cement Mortar 1:3 (1 cement : 3 coarse | | | | |
| | Size upto 200x300mm | 42.00 | Sqm | 587.00 | 24654.00 |
| 17 | Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the | | | | |
| | Size 300x300mm | 14.08 | Sqm | 692.00 | 9743.36 |
| 18 | Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the | 140.20 | Sqm | 94.50 | 13248.90 |
| 19 | 14.11 Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade | | | | |
| | On new work (two or more coats) | 187.28 | Sqm | 52.50 | 9832.20 |
| 20 | 14.22 Painting on new work (two or more coats) to give an even shade with | | | | |
| | Satin synthetic enamel paint | 15.18 | Sqm | 55.00 | 834.90 |
| 21 | 18.2 Providing and fixing vitreous china water closet squatting pan (Indian type) including cutting and making good the walls and floors wherever required | | | | |
| | White Long pattern W.C. pan of size 580 mm | 4.00 | Each | 999.00 | 3996.00 |
| 22 | Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required | | | | |
| | 110 mm dia pipe. | 12.00 | Mtr. | 267.00 | 3204.00 |
| 23 | Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring | | | | |
| | Tee/ Tee with door/ Bend 45°/ Bend 90° | | | | |
| | 110 mm | 6.00 | Each | 154.00 | 924.00 |
| | Nahani trap 110x75mm | 4.00 | Each | 90.50 | 362.00 |
| 24 | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps | | | | |
| | 15 mm nominal outer dia .Pipes. | 3.00 | Mtr. | 154.00 | 462.00 |
| | 20 mm nominal outer dia .Pipes | 10.00 | Mtr. | 90.50 | 905.00 |
| 25 | Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass | | | | |
| | Bib cock (400 grams) | 4.00 | Each | 382.00 | 1528.00 |
| | **Total Amount As Per S.O.R. Rs.** | | | | **299990.67** |
| | **Say Amount Rs.** | | | | **300000.00** |

**Sub Engineer**
**Municipal Corporation**
**Korba (C.G.)**

**Asst. Engineer**
**Municipal Corporation**
**Korba (C.G.)**