

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. 526 / 2026

सिस्टम टेंडर नं. 195039

कोरबा दिनांक 09.07.2026

ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015, विद्युत हेतु दिनांक 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र Form-A में निविदा आमंत्रित की जाती है:-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि — 05.08.2026 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि — 05.08.2026 सायंकाल 4.00 बजे से

क.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (डिमांड ड्राफ्ट)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क 04 अंतर्गत राताखार टावर मोहल्ला गणेश चौक के पास सामुदायिक भवन का मरम्मत एवं अतिरिक्त विकास कार्य (अधोसंरचना मद)	15.00	11250/-	04 माह	750/-	वर्ग डी एवं प्रवर श्रेणी	05.08.2026 से

शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र, पेन नम्बर, वैध जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं निर्धारित प्रारूप में शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा के पते पर भेजना होगा। निर्धारित तिथि को सायं 03:00 बजे के पश्चात् फिजिकल सबमिशन लिफाफा स्वीकार नहीं किया जायेगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निर्धारित प्रारूप में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन (वर्तमान तक वैधता) एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे एवं कर्मचारी भविष्य निधि संगठन (ई.पी.एफ.) एवं विभिन्न प्रावधानों को धारा 1952 के तहत निविदाकार का जीवित पंजीयन होना आवश्यक है साथ ही निविदा आमंत्रण दिनांक से विगत तीन माह की अवधि में जमा किये गये TRRN Payment Detail चालान की प्रति प्रस्तुत करना तथा ऑनलाईन अपलोड किया जाना अनिवार्य होगा।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
10. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. निविदा प्रपत्र फार्म -ए की कंडिका 11 Price Adjustment (एस्कलेशन) देय नहीं होगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान कार्य विशेष हेतु बजट आबंटन एवं राशि उपलब्ध होने पर किया जाएगा।
16. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
17. कार्य क्रियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
18. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		09.07.2026	15.30	09.07.2026	15.30	Release Tender
2		Bid Submission	09.07.2026	15.30	31.07.2026	17.30	
3		Physical Document Submission	09.07.2026	15.30	05.08.2026	15.00	
4	Tender Open		05.08.2026	16.00	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)


OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

566 1.5.25 DETAILED ESTIMATE

Name of work: - Construction Extension and maintenance of Community building near tower chowk at ward no 04 Ratakhhar

As per SOR: Schedule of rates public works department [PWD BUILDING-01-01-2015]

S. N.	SOR Ref.	ITEM DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of								
	1	In all types of soil								
		column	10	1.50	1.50	1.50	33.75			
			5	4.70	0.60	0.60	8.46			
			3	2.60	0.60	0.60	2.81			
			3	3.20	0.60	0.60	3.46			
			3	3.00	0.60	0.60	3.24			
		SEPTIC TANK	1	3.20	2.40	1.90	14.59			
						Total	66.31	Cum	185.00	12266.61
2	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.								
		Raft	10	4	1.30	0.30	15.60			
		footing	10	4	0.60	0.60	14.40			
		column below plinth	10	2	0.300	1.10	6.60			
			10	2	0.200	1.10	4.40			
		plinth beam	2	2	12.400	0.30	14.88			
			5	2	6.400	0.30	19.20			
						Total	75.08	Sqm	139.00	10436.12
	5	Columns, Pillars, Piers and likes- rectangular or square in shape								
			10	1		2.9	29			
			10	1		0.6	6			
						Total	35.00	sqm	297.00	10395.00
	7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)								
		SLAB	1	15.40	6.80		104.72			
			2	12.70	0.125		3.18			
			2	10.90	0.125		2.73			
		chajja	4	1.80	0.600		4.32			
			4	2.40	0.100		0.96			
			1	10.40	0.600		6.24			
						Total	122.14	sqm	235.00	28702.90
	8	Beams, lintels, cantilevers & walls								

	INTEL	4	12.40	0.20		9.92			
		6	10.60	0.20		12.72			
		2	3.20	0.20		1.28			
		4	1.90	0.20		1.52			
		4	12.40	0.20		9.92			
	TOP	6	10.60	0.20		12.72			
		2	3.20	0.20		1.28			
		4	1.90	0.20		1.52			
		4	6.00	0.50		12.00			
	latken beam	2	6.00	0.20		2.40			
					Total	65.28	sqm	202.00	13186.56
	Wall of any thickness including attached pilasters, buttresses etc. in super								
		4	3		1.8	21.60			
		6	1.8		1.8	19.44			
						41.04	SQ	228.00	9357.12
3	1.18 Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including								
	column	10	1.50	1.50	0.10	2.25			
		5	4.70	0.60	0.10	1.41			
		3	2.60	0.60	0.10	0.47			
		3	3.20	0.60	0.10	0.58			
		3	3.00	0.60	0.10	0.54			
	SEPTIC TANK	1	3.20	2.40	0.10	0.77			
	filling under floor	1	15.00	6.00	0.40	36.00			
					Total	42.01	Cum	371.00	15586.45
4	3.1 Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	3 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).								
	column	10	1.50	1.50	0.10	2.25			
		5	4.70	0.60	0.10	1.41			
		3	2.60	0.60	0.10	0.47			
		3	3.20	0.60	0.10	0.58			
		3	3.00	0.60	0.10	0.54			
	SEPTIC TANK	1	3.20	2.40	0.10	0.77			
	filling under floor	1	15.00	6.00	0.10	9.00			
						0.50			
					Total	15.51	Cum	2659.00	41246.41
5	1.17 Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a								
					Total	66.31	Cum	65.00	4309.89
6	3.2 Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form								

1.1½:3 (1 cement : 1½ coarse sand :
3 graded stone aggregate 20mm
nominal size).

raft c1	10	1.30	1.30	0.30	5.07			
footing	10	0.60	0.6	0.60	2.16			
column below plinth	10	0.20	0.300	1.10	0.66			
plinth beam	2	12.40	0.200	0.30	1.49			
	5	6.00	0.200	0.30	1.80			
	1	3.00	0.200	0.30	0.18			
	2	1.90	0.200	0.30	0.23			
				Total	11.59	Cum	4163.00	48232.52

super structure 3.2.1+3.4

LINTEL	2	15.40	0.20	0.20	1.23			
	3	6.00	0.20	0.20	0.72			
	1	3.20	0.20	0.20	0.13			
	2	1.90	0.20	0.20	0.15			
TOP	2	15.40	0.20	0.20	1.23			
	3	6.00	0.20	0.20	0.72			
	1	3.20	0.20	0.20	0.13			
	2	1.90	0.20	0.20	0.15			
latken beam	2	6.00	0.20	0.50	1.20			
chajja	6	1.80	0.600	0.10	0.65			
	1	15.400	0.600	0.100	0.92			
	10	0.200	0.300	0.600	0.36			
SEPTIC TANK	1	3.400	2.200	0.250	1.87			
	2	3.000	0.200	1.800	2.16			
	3	1.800	0.200	1.800	1.94			
	1	3.000	2.200	0.150	0.99			
slab	1	15.400	6.800	0.125	13.09			
				Total	27.65	Cum	4260.50	117802.83
					0.00	Cum	97.50	

7 3.4 Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and

8 3.12 Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth

110		39.24		4315.96				
			Total	4315.96	kg	54.50	235219.82	

1.19 Providing filling and compacting local earth (from approved source pit) in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. Complete

1	12.00	10.20	0.80	97.92				
			Total	97.92	Cum	242.00	23696.64	

9 7.5 Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:

3 Cement Mortar 1:6 (1 cement : 6 coarse sand)


		3	11.60	0.20	0.90	6.26			
		4	9.70	0.20	0.90	6.98			
		1	3.20	0.20	0.90	0.58			
		2	1.90	0.20	0.90	0.68			
		3	11.60	0.20	2.90	20.18			
		4	9.70	0.20	2.90	22.50			
		1	3.20	0.20	2.90	1.86			
		2	1.90	0.20	2.90	2.20			
		2	12.40	0.20	0.60	2.98			
		2	10.60	0.30	0.60	3.82			
	DEDUCT DOOR WINDOW	-6	1.50	0.20	1.20	-2.16			
		-2	3.90	0.20	2.10	-3.28			
		-3	0.90	0.20	2.10	-1.13			
	STAGE	1	6.00	0.30	1.20	2.16			
	STEPS	3	4.50	0.90	0.20	2.43			
		3	4.50	0.60	0.20	1.62			
		3	4.50	0.30	0.20	0.81			
		6	1.20	0.90	0.20	1.30			
		6	1.20	0.45	0.20	0.65			
					Total	70.44	Cum	3263.00	229852.25
12	12.13	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete							
	1	Size 600x600mm	1	12.20	10.40	126.88			
					Total	126.88	sqm	1151.00	146038.88
13	12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment							
	2	Size above 200x300mm	4	3.20		2.10	26.88		
			4	4.00		2.10	33.60		
			-2	0.80		2.10	-4.62		
	deduct				Total	55.86	sqm	587.00	32789.82
14	12.9	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment							
	1	Size 300x300mm	1	3.20	4.00	12.80			
					Total	12.80	sqm	692.00	8857.60

Granite stone slab in risers and treads of steps skirting dado and pillars laid on 12mm (Average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry including rubbing and polishing etc. complete (single stone is to be used for risers and treads of steps and width of stone for skirting and dado shall be equal to the height of skirting & dado and length of 1.0 m).

1	Granite stone grey/pink								
	STEPS	3	4.50	0.30		4.05			
		3	4.50	0.15		2.03			
		1	6.00	0.30		1.80			
		6	1.20	0.30		2.16			
		6	1.20	0.15		1.08			
						6.50			
					Total =	17.62	sqm	1869.00	32922.44
16	9.15 Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.								
	door	3	45.00			135.00			
	window	6	40.00			240.00			
	ventilator	2	20.00			40.00			
					Total =	415.00	Kg	67.50	28012.50
17	9.11 Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with 38mm steel pulleys complete with bolts, nuts, locking arrangement stoppers, handles including applying a priming coat of								
		1	3.90		2.10	8.19			
					Total	8.19	sqm	3330.00	27272.70
18	11.1 Providing and making 6mm thick cement plaster of mix								
	2 In Cement mortar 1:4 (1 cement : 4 fine sand)								
		1	12.4	10.60		131.44			
		4	1.80	0.60		4.32			
					Total	135.76	sqm	87.00	11811.12
19	11.2 Providing and making 12mm thick cement plaster of mix								
	4 In Cement Mortar 1:6 (1 cement : 6 fine sand)								
		2	12.40		4.75	117.80			
		2	10.60		6.20	131.44			
		-2	1.80		1.20	-4.32			

					Total	244.92	sqm	91.50	22410.18
	3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:							
	4	In Cement Mortar 1:6 (1 cement : 6 fine sand)							
		4	12.00		3.30	158.40			
		2	10.20		3.30	67.32			
		4	4.00		3.30	52.80			
		2	3.20		3.30	21.12			
		4	1.90		3.30	25.08			
		-3	0.90		2.10	-5.67			
		-2	0.80		2.10	-3.36			
		-3	1.50		1.20	-5.40			
					Total	310.29	sqm	107.00	33201.03
21	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.							
						690.97			
					Total	690.97	sqm	94.50	65296.67
22	14.1	Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.							
		1	On new work (Two or more coats)						
						446.05	sqm	44.50	19849.23
23	14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per							
		1	On new work (Two or more coats)						
						244.92	sqm	56.00	13715.52
35	14.22	Painting on new work (two or more coats) to give an even shade with:							
		2	3.90	2.10		16.38			
		2	3.50	2.10		14.70			
		5	0.90	0.60		2.70			
					Total	33.78	sqm	47.00	1587.66
	8.13	Providing and fixing flush door shutters, conforming to IS 2202 (Part 1), interior grade, commercial type, core of block board construction with frame of first class hard wood and well matched commercial ply veneering with vertical grains, cross bands and							
		3	0.90		2.1	5.67	SQM	1370.00	7767.90
	8.152	8.152 Providing and fixing 30mm thick factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19mm x 19mm for styles and 15x15mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5mm thick heat moulded PVC							
		Both side Pre-laminated panel PVC							
		2	0.80		2.1	3.36	SQM	2832.00	9515.52

		Providing and fixing aluminium work for doors, windows, ventilators and partitions made out of extruded aluminium standard sections (main section with minimum 1.5mm thickness) conforming to IS: 733, IS: 1285 mitred and jointed mechanically including aluminium cleats, neoprene weather stripping gasket beveled edge beading, screws duly fixed in wall/ floor with fixing clips or hold fasteners or bolts and nuts as required aluminium sections shall be anodized transparent or dyed to approved shade according to IS: 1968 minimum anodic coating shall										
	9.47.1	For fixed portion					150.00	kg	331.00	49850.00		
37	9.47.2	For shutter of doors, windows & ventilators including providing and making provision for fixing of fitting wherever required including the cost of PVC/					137.00	kg	338.00	48308.00		
38	9.51	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete. (Cost of aluminium snap beading shall be paid in basic item):										
		9.51.2 With float glass panes of 5 mm thickness	6	1.50	1.20		10.80					
			2	0.60	0.60		0.72					
						Total =	11.52	sqm	708.00	8156.16		
TOTAL=										1365452.02		
SANITATION										74079.00		
ELECTRIFICATION										60199.00		
TOTAL=										1499730.02		
SAY RS.=										1500000.00		


 Asstt. Engineer
 Municipal Corporation
 Korba (C.G.)

Sub Engineer
 Municipal Corporation
 Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

PART - C - SANITATION WORK

18.76	Providing and fixing on wall face UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete								
	1 75 mm dia pipe.	1	44.00			44.00	metre	182.00	8008.00
	2 110 mm dia pipe.	1	30.00			30.00	metre	267.00	8010.00
2	18.4 Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required :						2 each	4415.00	8830.00
	3 White wall hung type						2 each	1430.00	2860.00
3	18.17 Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :								
	1 White Size 550x450 mm								
6	18.77 Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.								
	1 Tee/ Tee with door/ Bend 45°/ Bend 90°								
	1 75 mm					2.00	each	113.00	226.00
	2 110 mm					5.00	each	154.00	770.00
	3 Vent cover								
	1 75 mm					4.00	each	34.00	136.00
	6 Nahani trap 110x75mm					6.00	each	90.00	540.00
7	19.4 Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.								
	1 15 mm nominal outer dia. Pipes.					80.00	metre	110.00	5500.00
	3 25 mm nominal outer dia. Pipes.					30.00	metre	199.00	5970.00

		32 mm nominal outer dia .Pipes.				30.00	metre	271.00	8130.00
13		Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:							
1		Bib cock (250 grams)				6.00	each	185.00	1110.00
14		Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required:							
6		Stop cock (concealed) (600 grams)				2.00	each	494.00	988.00
4		Pillar Cock (400 grams)				2.00	each	398.00	796.00
20		CP brass water jet to be fixed in seat cover of WC with flexible connection pipe				2.00	each	577.00	1154.00
10	19.15	Providing and fixing stainless steel drain jali of approved make/quality.				6.00	each	51.00	306.00
11	19.16	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end):							
1		25 mm nominal bore				5.00	each	436.00	2180.00
2		32 mm nominal bore.				5.00	each	510.00	2550.00
12	19.51	Constructing masonry Chamber 60x60x75 cm, inside with modular well burnt clay bricks of 35 kg/ cm ² in cement mortar 1:4 (1 cement : 4 coarse sand) for fire hydrants, with C.I. surface box 350x350 mm top and 165 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) necessary excavation foundation concrete 1:5:10 (1 cement : 5 fine sand:10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick finished with a floating coat of neat cement complete as per standard design :				2.00	each	4356.00	8712.00
14	19.42	Providing and placing on terrace (at all levels) polyethylene water storage tank ISI marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.				1000.00	litre	7.30	7300.00
TOTAL =									74079.00

Say Rs.=


 Asstt. Engineer
 Municipal Corporation
 Korba (C.G.)

Sub Engineer
 Municipal Corporation
 Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

me of work :

Per SOR: Schedule of rates public works department [PWD ELECTRICAL-01-06-2020] PART- B

S. No.	SOR Ref.	ITEM DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	1.1	Wiring for light/ fan/ exhaust fan / call bell point with 3x1.5 sqmm FRLS PVC insulated stranded copper conductor wire for phase, neutral and earth in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) with 5/6 amp piano type switch, phenolic laminated sheet, suitable size M.S. box etc as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)								
	1	Short Point	25				25	Point	240.00	6000.00
	2	Medium Point	7				7	Point	376.00	2632.00
2	1.3	Extra for providing and fixing light plug point on board in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) point wiring with piano type 3 pin 5/6 amp socket outlet and 5/6 amp switch including cost of phenolic laminated sheet and M.S. box etc. as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)	2				2.00	Point	87.00	174.00
3	1.13	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, wire in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)								
	4.13.2	3 X 2.5 sq. mm in 20mm conduit	4	40.00			160.00	Metre	111.00	17760.00
4	6.1	Supplying, installation, testing and commissioning of following sizes ceiling fan including wiring the down rods of standard length up to 30 cm with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable, earthing etc. complete as required. P.F. should be greater than 0.9, with BEE Star rating from 3 star and above, IS: 374:2019 including all amendments.								
	3	1400 mm sweep	8				8	Each	1773.00	14184.00
5	6.15	Supplying, installation, testing and commissioning of following LED fitting (luminaries) Panel Light in round/ square shape complete with electronic driver heat sink capacitor and all other accessories on surface/ in false ceiling etc. as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio ≥ 100 lumens /watt.								
	8.22.5	12 Watt	12				12.00	Each	588.00	7056.00
	8.22.6	15 Watt	5				5.00	Each	679.00	3395.00

Supplying and fixing following piano type switch, socket, other accessories on the existing switch box/ cover including connections etc. as per specification.								
5.1.1	5/6 amps one way switch	2			2.00	Each	25.00	50.00
5.1.4	15/16 amps switch	6			6.00	Each	59.00	354.00
5.1.5	3 pin 5/6 amp socket outlet	8			8.00	Each	42.00	336.00
5.1.6	6 pin 15/16 amp socket outlet	4			4.00	Each	73.00	292.00
5.1.7	Plug Top 3 pin 5/6 Amps (For light plug).	4			4.00	Each	38.00	152.00
5.1.8	Plug Top 3 pin 16 Amps (For power plug).	2			2.00	Each	51.00	102.00
5.1.12	Fan regulator Electronic, step type moving all round	7			7.00	Each	130.00	910.00
5.1.13	Ceiling rose 3 pin 5 amps	7			7.00	Each	32.00	224.00
5.1.15	Batten/ angle holder	17			17.00	Each	38.00	646.00
7.9.1	Providing and fixing following rating and breaking capacity MCCB in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as per specification, IS/ IEC: 60947-2 and Ics = 100 % Icu.							
11.17.23	3 pole MCCB, 25-63A, Fixed Thermal Release, 10KA	4			4.00	Each	1483.00	5932.00
TOTAL =								60199.00

say rs. =