

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. 1471/2025

सिस्टम टेंडर नं. 177868

कोरबा दिनांक 16.10.2025

द्वितीय ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता PHE -SOR 01.06.2020 and Amendment 7/2022-23 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र फार्म A में निविदा आमंत्रित की जाती है :-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि — 06.11.2025 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि — 06.11.2025 सायंकाल 4.00 बजे से

क.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (DD)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	टी.पी.नगर महाराजा होटल से पावर हाउस रोड से टी.पी.नगर चौक तक, टी.पी. नगर चौक से सुनालिया केनाल ब्रिज बंगाली चाल डी.आई. पाईप लाईन बिछाने का कार्य (अधोसंरचना मद)	83.56	63000/-	05 माह	3000/-	वर्ग डी एवं प्रवर श्रेणी	06.11.2025 से

शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र/पैन नम्बर, वैध जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमाण्ड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का DD एवं शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से निविदा खुलने की तिथि में दोपहर 3.00 बजे तक आयुक्त,नगर पालिक निगम,कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा को उपलब्ध कराना अनिवार्य होगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का DD जो कि आयुक्त, नगर पालिक निगम,कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेस सिक्युरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन (वर्तमान तक वैधता/Form- 5A) एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ईट से संबंधित निर्माण कार्यों में पलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
10. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. निविदा प्रपत्र फार्म -ए की कंडिका 11 अनुसार एस्कलेशन देय नहीं होगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान बजट आबंटन और राशि उपलब्ध होने पर किया जाएगा।
16. ठेकेदारों को निर्माण कार्य के दौरान निर्माण एवं अपशिष्ट प्रबंधन नियम 2016 में किये गये प्रावधानों का पालन करना होगा।
17. कार्य कियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।


अधीक्षक अभियंता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		16.10.2025	15.30	16.10.2025	15.30	Release Tender
2		Bid Submission	16.10.2025	15.30	04.11.2025	17.30	
3		Physical Document Submission	16.10.2025	15.30	06.11.2025	15.00	
4	Tender Open		06.11.2025	16.00	--	--	


 Subhojit Kumar
 EXECUTIVE ENGINEER
 Municipal Corporation
 KORBA (C.G.)
 For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

Providing & Laying and Jointing of DI K-7 Pipe Line From T.P. Nagar Maharaja Hotel to Road T.P. Nagar Chauk & T.P. Nagar Chauk to Sunaliya Canal Bridge Bangali Chhal (Shifting of AC Pipe Due to Construction of Nalah)

ESTIMATE

Abstract cum Measurement Sheet

Sr. No.	Items	Nos.	Length (In Mtr)	Breadth (In Mtr)	Height (In Mtr)	Qty.	CT :	Rate (In Rs.)	Amount
1	Earth work in excavation for pipe trench in ordinary soil areas including dressing, watering, ramming and disposal of excavated earth lead up to 50m and lift up to 1.5m, disposal earth to be levelled, neatly dressed.								
	For pipeline of 200 mm Dia. DI K-7	1	750.00	0.80	1.20	720.00			
	For pipeline of 150 mm Dia. DI K-7	1	850.00	0.75	1.15	733.13			
	For pipeline of 100 mm Dia. DI K-7	1	570.00	0.70	1.00	399.00			
	Total = (CG PHE SOR Amendment No 7/ 2022-23; Item No- 18.15; Page No- 51)		2170.00			1852.13	Cum	201.00	372277.13
2	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 m lead as per direction of engineer-in-charge.								
	Dismantling of Cement Concrete Pavement by mechanical means using pneumatic tools, cutter breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials up to a lead of 1000 metres, stacking serviceable and unserviceable materials separately								
	For pipeline of 200 mm Dia. DI K-7	1	750.00	0.80	0.20	120.00			
	For pipeline of 150 mm Dia. DI K-7	1	850.00	0.75	0.20	127.50			
	For pipeline of 100 mm Dia. DI K-7	1	570.00	0.70	0.20	79.80			
	Total = (CG PHE SOR Amendment No 7/ 2022-23; Item No- 18.29.3; Page No- 52)					327.30	Cum	1227.00	401597.10
3	Pumping out water caused by springs, tides or river seepage, broken water mains or drains or well or the like.					1995.00	LK	71.00	141645.00
4	Supply & Filling moorum/river sand for pipe bedding or over the pipe (including supply)								
	(CG PHE SOR Amendment No 7/ 2022-23; Item No- 18.24; Page No- 52)	1	2170.00	0.775	0.15	252.26	Cum	864.00	217954.80

Providing, laying and jointing including testing following socket & spigot centrifugally cast (Spun) Ductile Iron pressure pipes with inside cement mortar lining (class K-7) conforming to IS: 8329/ For pipeline of 200 mm Dia. For pipeline of 150 mm Dia. For pipeline of 100 mm Dia. Total = (CG PHE SOR Amendment No 7/ 2022-23; Item No-4.1 ; Page No- 2)					750.00 850.00 570.00 2170.00	Mtr Mtr Mtr	2378.00 1804.00 1309.00	1783500.00 1533400.00 746130.00
6 Providing and Laying including testing Ductile Iron Double Socket branch flange Tee conforming to IS:9523/2000 having dimension as per table 21 of S:9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining with finishing as per clause 13 of IS:9523/2000 200 mm x 150 mm 200 mm x 200 mm 150 mm x 100 mm (For Scour) 100 mm x 100 mm (For Scour) (CG PHE SOR Amendment No 7/ 2022-23; Item No-4.23 ; Page No- 11)					2.00 1.00 2.00 2.00	Each Each Each Each	5155.00 6015.00 3150.00 2291.00	10310.00 6015.00 6300.00 4582.00
7 Providing and Laying including testing Ductile Iron Double Socket 90° Bends conforming to IS: 9523/2000 having dimension as per table 15 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining. 200 mm Dia 150 mm Dia 100 Mm Dia (CG PHE SOR Amendment No 7/ 2022-23; Item No-4.13 ; Page No- 7)					4.00 3.00 6.00	Each Each Each	4154.00 2595.00 1428.00	16616.00 7785.00 8568.00
8 Providing and Laying including testing Ductile Iron Double Socket 45° Bends conforming to IS: 9523/2000 having dimension as per table 16 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining 200 mm Dia 150 mm Dia 100 Mm Dia					5.00 4.00 8.00	Each Each Each	3376.00 2078.00 1298.00	16880.00 8312.00 10384.00

9	Providing and Laying including testing Ductile Iron Double Socket 22.5° Bends conforming to IS: 9523/2000 having dimension as per table 17 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining 200 mm Dia 150 mm Dia 100 Mm Dia (CG PHE SOR Amendment No 7/ 2022-23; Item No-4.17 ; Page No- 8)							
					7.00	Each	2856.00	19992.00
					6.00	Each	1817.00	10902.00
					6.00	Each	1167.00	7002.00
10	Providing and Laying including testing Ductile Iron Double Socket 11.25° bends conforming to IS:9523/2000 having dimension as per table 18 of S:9523/2000 in the following nominal diameter/ sizes with external bitumen coating and internal cement mortar lining. 200 mm Dia 150 mm Dia 100 Mm Dia (CG PHE SOR Amendment No 7/ 2022-23; Item No-4.19 ; Page No- 9)							
					4.00	Each	2726.00	10904.00
					2.00	Each	1687.00	3374.00
					8.00	Each	1167.00	9336.00
11	Providing and Laying including testing ductile PN 16 type iron flanged spigot conforming to IS: 9523/2000 having dimension as per table 24 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining with finishing as per clause 13 of IS: 9523/2000 200 mm Dia 150 mm Dia 100 Mm Dia (CG PHE SOR Amendment No 7/ 2022-23; Item No-4.9 ; Page No- 5)							
					2.00	Each	3294.00	6588.00
					2.00	Each	2291.00	4582.00
					6.00	Each	1432.00	8592.00
12	Providing and Laying including testing ductile iron PN 16 type flanged sockets conforming to IS: 9523/2000 having dimension as per table 23 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining with finishing as per clause 13 of IS:9523/2000. 200 mm Dia 150 mm Dia 100 Mm Dia							
					2.00	Each	3007.00	6014.00
					2.00	Each	2005.00	4010.00
					6.00	Each	1288.00	7728.00


CG PHE SOR Amendment No 7/ 2022-23;
Item No-4.7 ; Page No- 4)

13	Providing & fixing of following Cast iron double flanged sluice valves as per I.S.:14846-2000 fitted with cast iron cap including jointing & testing with cost of jointing material such as bolts, nuts, rubber insertions etc. all complete 200 mm Dia 150 mm Dia 100 Mm Dia (CG PHE SOR 2020; Item No-8.1 ; Page No-115)								
						1.00	Each	13183.00	13183.00
						3.00	Each	2005.00	6015.00
						2.00	Each	5090.00	10180.00
14	Providing and Laying including testing Ductile iron Mechanical joint collar with follower glands conforming to IS: 9523/2000 having dimension as per table 24 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen and internal cement mortar lining. 200 mm Dia 150 mm Dia 100 Mm Dia (CG PHE SOR Amendment No 7/ 2022-23; Item No-4.11 ; Page No- 6)								
						12.00	Each	5035.00	60420.00
						15.00	Each	3896.00	58440.00
						15.00	Each	2647.00	39705.00
15	Providing and Laying including testing Ductile Iron Double Socket Reducer conforming to IS: 9523/2000 having dimension as per table 21 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining with finishing as per clause 13 of IS: 9523/2000. 200 mm Dia 150 mm Dia 100 Mm Dia (CG PHE SOR Amendment No 7/ 2022-23; Item No-4.25 ; Page No- 13)								
						1.00	Each	2474.00	2474.00
						1.00	Each	2590.00	2590.00
						2.00	Each	1687.00	3374.00
16	Providing & laying mechanically mixed cement concrete 20mm nominal size graded crushed stone excluding cost of centering & shuttering. a) Reconstruction of Road (M-20 grade) 1: 1.5 :3 (M-20) grade of concrete b) Thrust Block/ Encasing work 1: 1.5 :3 (M-20) grade of concrete (CG PHE SOR 2020; Item No- 8.41; Page No-53)								
		1	750.00	0.80	0.20	120.00			
		1	850.00	0.75	0.30	191.25			
		1	600.00	0.70	0.20	84.00			
						395.25	Cum	6545.00	2586911.25


Construction of Brick masonry valve chamber with 20 cm thick wall in 1:6 C.M. with 12mm thick 1:4 Cement Plaster and base course 10 cm. thick in M-15. Inside Dimensions 110x80x100cm M-20 RCC chamber cover size 130x100cmx120cm including cost of materials, labour etc. complete. (CG PHE SOR Amendment No 7/ 2022-23; Item No-18.79 ; Page No- 58)					6.00	no.	7886.00	47316.00
18 Filling available excavated earth in trenches, lead up to 50m and lift up to 1.5m in all kind of soil excluding Watering and ramming. Back filling for 200 mm Dia. Total volume of earthwork = Deducting volume of pipe = Back filling for 150 mm Dia. Total volume of earthwork = Deducting volume of pipe = Back filling for 110 mm Dia. Total volume of earthwork = Deducting volume of pipe = Total = (CG PHE SOR Amendment No 7/ 2022-23; Item No- 18.23; Page No- 52)								
					1873.13			
					331.50			
					-23.55			
				0.785 x 0.20 x 0.20 x 750				
				0.785 x 0.15 x 0.15 x 850	-15.01			
				0.785 x 0.10 x 0.10 x 600	-5.10			
					2160.96	Cum	62.00	133979.79

Total without GST = 8355868.07

Add. 18 % GST	1504056.25
Total =	9859924.32
Say [In Rs.] =	98.60


Sub Engineer
Municipal Corporation
Korba(C.G)


Assistant Engineer
Municipal Corporation
Korba(C.G)


Executive Engineer
Municipal Corporation
KORBA (C. G.)