



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

दर्सी जोन

फा.क्र./367 एवं 368/निर्माण (दर्सी जोन)/2021/

कोरबा, दिनांक 09.03.2021

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :-

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 03.04.2021 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 03.04.2021 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र. 51 अंतर्गत लाटा में सुनिता नाग घर से श्रीराम चरण भास्कर घर तक नाली मरम्मत कार्य। (मरम्मत एवं संधारण मद)	3,99,500/-	4,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	03.04.2021
2	वार्ड क्र. 45 अंतर्गत राजीव नगर में सामुदायिक भवन का मरम्मत एवं नवीनीकरण कार्य। (मरम्मत एवं संधारण मद)	3,98,000/-	4,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	03.04.2021

निविदा की शर्त:-

1. निविदा दरें प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज हाथो-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयवाधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं. -495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
4. निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-
 - (अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी (निविदा आमंत्रण पत्र जारी दिनांक के पश्चात् का मान्य) एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
 - (ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
 - (स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवानगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
6. निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र

क्रमशः.....02

- (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर चुकता प्रमाण पत्र, पेन नम्बर, शपथ पत्र, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क्र. 04 के लिफाफा (अ) के अनुरूप प्रस्तुत करना अनिवार्य होगा।
7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
 8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
 9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
 10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
 11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
 12. शासन के विभिन्न विभागों जैसे- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
 13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
 14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
 15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
 16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत की दर से सुरक्षा निधि मद में राशि रनिंग देयकों से 01 वर्ष की अवधि हेतु सिक्यूरिटी के रूप में रोकी जावेगी।
 17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
 18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथ पत्र कंडिका क्र. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
 19. ईट से संबंधित निर्माण कार्यों में फलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
 20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
 21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
 22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
 23. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

(ठेकेदार के हस्ताक्षर)

नाम

पूर्ण पता

मोबाईल नं.-

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)
DETAILED ESTIMATE

Name of Work :- **Maintenance and Renovation of Samudayik bhawan at Rajiv Nagar ward no.45**

As per Sor :- Schedule of Rates Public Works Department [PWD BUILDING 01-01-2015]

Sno	ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
1	14.45 Removing dry or oil bound distemper by scraping sand papering and preparing the surfaces smooth including necessary repair								
	Rajiv Samudayik Bhawan	2	12.60		3.60	90.72			
		2	7.00		3.60	50.40			
		2	3.00		3.60	21.60			
		2	4.50		3.60	32.40			
					Total	195.12	sqm	5.20	1014.62
2	Dismantling bricks laid flat or on edge (each layer), or cement concrete tiles in flooring or over roofs in cement/lime mortar including stacking of								
	flooring	1	12.50	6.50		81.25			
		1	3.50	4.50		15.75			
					Total	97.00	Sqm	22.50	2182.50
3	16.42 Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.								
	roof slab	1	12.50	6.50	0.12	9.75			
	Beam	6	7.00	0.30	0.40	5.04			
		6	0.20	0.30	0.70	0.25			
					Total	15.04	Cum	768.00	11552.26
4	16.3 Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead								
	16.3.3 In cement mortar.	6	0.60	0.30	0.75	0.81			
		2	12.50	0.20	0.75	3.75			
		2	6.50	0.20	0.75	1.95			
		2	3.50	0.20	0.75	1.05			
		2	4.50	0.20	0.75	1.35			
					Total	8.91	cum	263.00	2343.33
5	17.1 Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lea								
	17.1.1 Thickness upto 15mm	4	0.90	0.90		3.24			
		8	1.20	0.60		5.76			
		12	0.60	0.45		3.24			
		8	2.50	0.90		18.00			
		1	15.00	0.45		6.75			
					Total	36.99	Sqm	132.00	4882.68

6	1.1 Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	old Septic tank Remove out Soil	1	3.00	3.00	3.30	29.70	cum	185.00	5494.50
7	Brick work with modular fly-ash lime bricks (FALG Bricks) conforming to IS:12894-2002 of class designation 40 in foundation and plinth in:								
	Cement Mortar 1:6 (1 cement : 6 coarse sand)	6	0.60	0.30	0.60	0.65			
		2	12.50	0.20	0.60	3.00			
		2	6.50	0.20	0.60	1.56			
		2	3.50	0.20	0.60	0.84			
		2	4.50	0.20	0.60	1.08			
		2	3.00	0.20	0.60	0.72			
		2	3.00	0.20	0.60	0.72			
					Total	8.57	Cum	3350.00	28702.80
8	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.								
	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	1	12.50	6.50	0.08	6.50			
		1	3.50	4.50	0.08	1.26			
					Total	7.76	Cum	2789.00	21642.64
9	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.								
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
	roof	1	12.50	6.50	0.12	9.75			
	Beam	6	7.00	0.30	0.40	5.04			
	column	6	0.20	0.30	0.75	0.27			
	septic tank cover	1	3.00	3.00	0.12	1.08			
					Total	16.14	Cum	4163.00	67190.82
10	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:								
	Thermo-Mechanically treated bars	@	70kg/cum			1130.00	Kg	54.50	61585.00
11	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	2.1.6 Columns, beams & walls- circular or any other geometrical shape other than square and rectangular in all sizes								
	Beam	2x6	7.00		0.40	37.80			
		6	7.00		0.30	12.60			
		2x6	0.20		0.75	1.80			

	12.7.2 Size above 200x300mm	2	1.80	2.10		7.56			
	Rajiv Nagar Samudayik Bhawan	1	1.80	2.10		3.78			
					Total	11.34	sqm	646.00	7325.64
18	17.7 Providing and replacing broken vitreous china water closet squatting pan (Indian type) including removing the broken squatting pan and mortar, cutting and making good the walls and floors wherever required: 17.7.1 White Long pattern W.C. pan of size 580 mm	1				1.00			
	Rajiv Nagar Samudayik Bhawan				Total	1.00	Each	1448.00	1448.00
19	12.9 Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete								
	12.9.2 Size above 300x300mm	1	1.80	2.50		4.50	sqm	728.00	3276.00
20	9.13 Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer								
		1	25.50	25.00		637.00	kg	75.00	47775.00
21	18.77 Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.								
a	18.77.1 Tee/ Tee with door/ Bend 45°/ Bend 90°								
b	18.77.1.1 75 mm	4				4.00	each	113.00	452.00
c	75 mm					1.00	Each	129.00	129.00
d	110 mm					1.00	Each	224.00	224.00
e	18.77.5 "P" trap 110mmx110mm long	1				1.00	each	227.00	227.00
f	18.77.8 Plain reducing Tee 110x75mm	4				4.00	each	129.00	516.00
22	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.								
	9.6.2- In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.								
		2	1.20	1.20	25kg/sqm	72.00			
					TOTAL	72.00	kg	68.00	4896.00

23	14.14 Finishing walls with water proofing cement paint of required shade to give an even shade								
	14.14.2 On old work (one or more coats applied @ 2.20 kg/10 sqm)								
		2	13.00		3.60	93.60			
		2	7.00		3.60	50.40			
		2	4.00		3.60	28.80			
		2	3.50		3.60	25.20			
	deduct opening				(-)	26.00			
					Total	172.00	sqm	25.50	4386.00
24	19.10 Making connection of G.I. distribution branch in G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete: (dia of main line to be measured)								
	19.10.1 25 mm nominal bore	4			4	each	200	800.00	
25	19.13 Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:								
	19.13.1 Bib cock (250 grams)	2			4	each	185	740.00	
26	19.47 Constructing masonry Chamber 30x30x50 cm, inside with modular well burnt clay bricks of 35 kg/ cm ² in cement mortar 1:4 (1 cement : 4 coarse sand) for stop cock, with C. I. surface box 100x100 x75 mm (inside) with hinged cover fixed in cement concrete slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) necessary excavation foundation concrete 1:5:10 (1 cement : 5 fine sand:10 graded stone aggregate 40mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12mm thick finished with a floating coat of neat cement complete as per standard design : each								
		1			1	Each	754	754.00	
27	18.76 Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.								
	18.76.2 110 mm dia pipe.	1	12.00		12.00	metre	267.00	3204.00	
27	18.17 Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :								
	18.17.1 White Size 550x450 mm	1			1.00	each	1430.00	1430.00	

28	14.15 Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:								
	14.15.1 On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)								
		2	13.00		3.60	93.60			
		2	7.00		3.60	50.40			
		2	4.00		3.60	28.80			
		2	3.50		3.60	25.20			
	deduct opening				(-)	26.00			
					Total	172.00	sqm	56.00	9632.00
29	19.6 Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This included jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge								
	19.6.1 15 mm nominal outer dia pipes	1	18		18	metre	91.5	1647.00	
As per SOR Total Estimate Amount Rs.									397689.04
Say Amount Rs.									398000.00


Sub Engineer
Municipal Corporation
Korba (C.G.)


Asst. Engineer
Municipal Corporation
Korba (C.G.)


Executive Engineer
Municipal Corporation
Korba (C.G.)

मातृका

15

पावद
क - 2 माई क - 45