कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. 1519/विद्युत शाखा/2026 कोरबा दिनांक 13.11.2026

सिस्टम टेण्डर नं. 203907

द्वितीय ई–निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग (विद्युत कार्य) में एकीकृत पंजीयन प्रणाली सक्षम श्रेणी **वर्ग डी एवं प्रवर श्रेणी में एवं छत्तीसगढ़ अनुज्ञापन मंड़ल (विद्युत) में उचित श्रेणी में विद्युतीकरण कार्य हेतु पंजीकृत/ए क्लास लाईसेंसी ठेकेदारों से** निम्नलिखित कार्य हेतु पार्ट–ए प्रमुख अभियंता लोक निर्माण विभाग (विद्युत) रायपुर 10.04.2026 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान प्रतिशत् दरों पर ई–प्रोक्यूरमेंट (E- Tendering) के माध्यम से निविदा आमंत्रित की जाती है:–

क.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (DD)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	**गोपालपुर से सिंधिया चौक तक विभिन्न स्थानों पर स्ट्रीट लाईट व्यवस्था कार्य (जि. ख.न्यास मद)**	75.54	56700/–	05 माह	3000/-	वर्ग डी एवं प्रवर श्रेणी	02.12.2026 से .....

शर्तें:–

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
2. जिन ठेकेदारों द्वारा नगर पालिक निगम के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम के हित के विरूद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नही होगी।
3. निविदा प्रपत्र प्राप्त करने हेतु इच्छुंक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र/पेन नम्बर, जी. एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री (विद्युत) नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमाण्ड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा ।
   - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का DD एवं शपथ पत्र (निर्धारित प्रारूप में) की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से निविदा खुलने की तिथि में दोपहर 3.00 बजे तक आयुक्त,नगर पालिक निगम,कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन– 495677 कोरबा को उपलब्ध कराना अनिवार्य होगा।
   - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि निर्धारित प्रारूप में वैध शपथपत्र (राशि रू. 100/– नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा कमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
   - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का DD जो कि आयुक्त, नगर पालिक निगम,कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किए गए कार्यों के प्रत्येक देयको में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष की गारंटी के लिए एवं पृथक से 5 प्रतिशत परफारेमेंस सिक्यूरिटी की गारंटी के रूप में प्रत्येक देयकों में से 03 वर्ष के लिए रोकी जावेगी। जिसे कार्यपूर्णता के 01 वर्ष पश्चात सुरक्षा राशि एवं 03 वर्ष पश्चात परफारमेंस गारंटी की राशि को कार्य के सही स्थिति में होने पर वापस की जावेगी।
5. निविदा उन्ही ठेकेदारों को दिया जावेगा,जिन्हें इस प्रकार के कार्यो का अनुभव होगा।
6. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन (वर्तमान तक वैधता) एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे। कर्मचारी भविष्य निधि संगठन (ई.पी.एफ.) एवं विभिन्न प्रावधानों की धारा 1952 के तहत् निविदाकार का जीवित पंजीयन होना आवश्यक है साथ ही निविदा आमंत्रण दिनांक से विगत 03 माह की अवधि में जमा किये गये TRRN Payment Details चालान की प्रति प्रस्तुत करना तथा ऑनलाईन अपलोड किया जाना अनिवार्य होगा।
7. इंजीनियर के अपॉइंटमेंट लेटर का दस्तावेजी सबूत जिस पर सही तारीख हो और अधिकृत हस्ताक्षरकर्ता द्वारा प्रमाणित हो, साथ ही संबंधित योग्यता प्रमाण पत्र और फोटो सहित परिचय पत्र संलग्न करना होगा।
8. निविदा में सफल निविदकार को ऐसे कार्य जिसकी अनुबंध राशि रू. 10.00 लाख या उससे अधिक है,उनको प्रत्येक कार्यों हेतु पृथक से छ. ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत् पंजीयन कराकर प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा की स्थिथति में देयक भुगतान किया जाना संभव नहीं होगा। तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
9. निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेस गारंटी के रूप में कार्य के अनुबंध संपादन के पूर्व राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होाग। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
10. शासन के विभिन्न विभागों जैसे:– खनिज विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय–समय पर जारी निर्देशो/आदेशों के पालन की समस्त जिम्मेदारी संबधित ठेकेदार की होगी।
11. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबध में प्रावधान के अन्तर्गत कार्यवाही की जावेगी।
12. कार्य प्रारंभ नही करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरूद्ध तत् समय में एमआइसी द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी। जिसकी सम्पूर्ण जवाबदारी ठेकेदार की होगी।
13. कार्य में लगने वाली सामग्रियों की टेस्ट रिपोर्ट देयक भुगतान के पूर्व प्रस्तुत करने के पश्चात ही देयक भुगतान किया जावेगा

कमशः....2

14. भूमिपूजन/लोकार्पण हेत लगने वाले शिलान्यास पत्थर (लिखाई सहित) प्रदाय एवं स्थापना कार्य स्वंय के व्यय से ठेकेदार के द्वारा किया जावेगा।
15. उक्त कार्य में लगे श्रमिको को विद्युत सुरक्षा उपकरण उपलब्ध कराना अनिवार्य होगा, एवं किसी प्रकार से दुर्घटना होने की स्थिति में सम्पूर्ण जिम्मेदारी आपकी होगी।
16. निविदा प्रपत्र फार्म –ए की कंडिका 11 अनुसार एस्कलेशन देय नहीं होगा।
17 ठेकेदार को निर्माण कार्य के दौरान निर्माण एवं अपशिष्ठ प्रबंधन नियम 2016 में किये गये प्रावधानों का पालन करना अनिवार्य होगा।
18. ठेकेदार द्वारा संपादित किये गए कार्यों के देयकों का भुगतान बजट आबंटन और राशि उपलब्ध होने पर किया जावेगा।
19. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नही किया जावेगा।
20. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
21. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
22. उपरोक्त निविदा सूचना की विस्तृत जानकारी नगर पालिक निगम, कोरबा के साकेत भवन स्थित विद्युत शाखा से प्राप्त किये जा सकते है।
23. कोई भी निविदाकार जिसे केंद्र सरकार,राज्य सरकार, पब्लिक सेक्टर अंडरटेकिंग (PSU) अर्बन लोकल बॉडी (ULB) या किसी सरकारी विभाग ने बोली जमा करने की आखरी तारीख तक डिभार (Debarred), ब्लैकलिस्ट, बैन या सस्पेन्ड किया है, वह इस बोली में हिस्सा लेने के लिए योग्य नहीं होगा, मूल्यांकन चरण के दौरान अगर यह पता चलता है कि बिडर ने अपीन योग्यता से जुड़ी जरूरी जानकारी छिपाई है तो फर्म को अयोग्य घोषित कर दिया जावेगा और उनपकी फाइनेंशियल बिड नहीं खोली जाएगी।
24. निविदा जमा करने की समय सीमा से पहले, नगर पालिक निगम कोरबा (छ.ग.) के कमिश्नर संशोधन जारी करने निविदा दस्तावेज में बदलाव कर सकते है इस तरह जारी किया गया कोई भी संशोधन निविदा का हिस्सा होगा और वेबसाईट पर प्रकाशित किया जाएगा।
25. बिल ऑफ क्वांटिटीज (BOQ) में बताई गई दरें CGPWD SOR 2026 पर आण्धारित है, और इनमें गुड्स एण्ड सर्विसेस टैक्स GST शामिल नहीं है, इसलिए बोली लगाने वाले को केवल GST को छोड़कर वित्तीय ऑफर जमा करना होगा। मौजूदों दरों के अनुसार लागू GST का भुगतान रनिंग अकाउंट (R.A.) बिल और फाईनल बिल से अलग से किया जाएगा, बशर्ते वैध GST इनवॉइस जमा किया जाए और GST एक्ट और नियमों के तहत सभी लागू कानूनी प्रावधानों का पालन किया जाए। इस क्लॉज के प्रावधान केवल उपर बताई गई दरों की अनुसूची (Schedule of Rates) पर आधारित कार्यो पर लागू होंगे।

    उपर बताया गया नियम CGPWD SOR 2026 के आधार पर तैयार किये गये अनुमानों पर लागू होगा। हालांकि CGPWD SOR 2026 के आधार पर तैयार किये गये अनुमानों के मामले में दरों में GST और अन्य सभी लागू कर शामिल है। इसलिए ऐसे मामलों में बोली लगाने वाले GST और अन्य सभी लागू करों को मिलाकर अपनी दरें प्रस्तुत करनी होगी।

अधीक्षण अभियंता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

प्रतिलिपि–

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायुपर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		13.11.2026	15.30	13.11.2026	15.30	Release Tender
2		Bid Submission	13.11.2026	15.30	30.11.2026	17.30	
3		Physical Document Submmission	13.11.2026	15.30	02.12.2026	15.00	
4	Tender Open		02.12.2026	16.00	--	--	

SUEPRITENDING ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION KORBA (C.G)

Sub. Street light Arrangement work from Gopalpur to Sindhiya Chouk at Various Location.

ESTIMATE

PWD Electrical SOR 10.04.2026 **Part A**

SN	SOR	ITEM	UNIT	RATE	QTY	AMOUNT
1	19.3	Supply of swaged steel tubular pole as per IS 2713 with base plate of size 300x300x6mm welded at bottom, necessary hole for cable entry and earthing stud welded at specified height including painting with one coat of red oxide zinc chromate primer.				
	19.3.8	Designation 410 SP-23 height 8.50 metre	Each	10032.00	192.00	1926144.00
	19.3.13	Designation 410 SP-38 height 9.50 metre	Each	10840.00	44.00	476960.00
2	19.10	Erection of STEEL TUBULAR or "H" BEAM/ ISMB pole in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation and cement concrete collar of size 0.4 metre dia and 0.50 metre height from ground level including excavation and refilling etc. as per specification of length:				
	19.10.4	7 metre to 10 metre	Each	2303.00	236.00	543508.00
3	14.2	Supplying and laying HDPE pipe of 4kg/Sqcm in ground below road, path etc at a depth not less than 40 cm and upto 90 cm including excavation, dismantling of road if required and refilling the trench with excavated material, ramming and making the surface good etc. as per specification.				
	14.2.1	63 mm outer dia	Metre	110.00	6250.00	687500.00
4	14.5	Supplying and fixing G.I. pipe along with wall or pole/ support with 2 Nos MS clamps for protection of under ground cable in approved manner including bolts and nuts or metal dash fasteners complete as per specification.				
	14.5.2	40 mm dia	Metre	317.00	810.00	256770.00
5	14.3	Supplying and laying following size medium class G.I. pipe in ground below road, path etc at a depth not less than 40 cm and upto 90 cm including excavation, dismantling of road if required and refilling the trench with excavated material, ramming and making the surface good etc. as per specification.				
	14.3.2	80 mm internal dia	Metre	465.00	130.00	60450.00
6	15.3	Supplying and laying following sizes one number FRLS PVC insulated /XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade in existing RCC/ HUME/ STONEWARE/ METAL/ HDPE pipe as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1).				
	15.3.11	3.5 x 25 sq. mm.	Metre	103.00	7190.00	740570.00
7	15.4	Supplying and laying following sizes one number FRLS PVC insulated /XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade in existing masonry open duct as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1).				
	15.4.11	3.5 x 25 sq. mm.	Metre	96.00	1098.00	105408.00
	15.4.12	3.5 x 35 sq. mm.	Metre	111.00	150.00	16650.00
	15.4.13	3.5 x 50 sq. mm.	Metre	146.00	70.00	10220.00
8	19.17	Supplying and fixing PVC water tight terminal box of approved make and brand with detachable gland plate in bottom, hinged front openable cover, rubber gasket, having 1 Nos 4way connector and 1 No SPMCB inside the box for cable connection, fixed to pole with 2 Nos clamp made from 25x3mm GI flat with 2 No GI nuts bolts complete as per specification.				
	19.17.2	300x200x125 mm for 3 phase	Each	872.00	236.00	205792.00

ESTIMATE

) Electrical SOR 10.04.2026 **Part A**

N	SOR	ITEM	UNIT	RATE	QTY	AMOUNT
	15.28	Supplying, fixing and cramping suitable size and all type aluminium ferule/ lugs to following size 1.1 KV grade power cable core / lead, pressed with high pressure cramping tool including connection to switch gear/ MCCB etc as per specification. .				
	15.28.4	25 sq. mm	Each	20.00	1856.00	37120.00
10	19.9	Supply and fixing following street light pole bracket on existing pole made out of 50 mm dia MS "B" class pipe welded to 300 mm long MS pole canopy of suitable dia at a angle of 102.50 including having MS triangular stiffner of size 150 X 50 X 5 mm thick, making arrangement for tightening the bracket with pole by providing suitable size heavy duty nuts and bolts in canopy, painting with one coat of approved steel primer etc. as per specification.				
	19.9.3	Single Over Hang 1.50 metre Long	Each	1087.00	234.00	254358.00
	19.9.7	Double Over Hang 1.50 metre Long	Each	1649.00	2.00	3298.00
11	6.28	Supplying, installation, testing and commissioning of following 230/250 volts LED street light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 15 KV surge protection on pole bracket, including connection, earthing, Separate housing for driver etc complete as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio ≥ 120 lumens /watt.				
	6.28.11	150 watt	Each	8246.00	238.00	1962548.00
12	3.11	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, multi strand wire in the existing surface/ concealed, FRLS PVC conduit / PVC casing caping as per specification and IS: 694 (2010)				
	3.11.2	2 x 1.5 sq. mm	Metre	23.00	2380.00	54740.00
13	12.19	Providing maintenance free earthing with following size GI pipe including making bore pit of minimum 150mm dia, providing and laying approved make Earthing Electrode of Pipe-in-Pipe technology as per IS 3043(R 2016) -1987 made of corrosion free G.I. Pipes having outer pipe of 80mm dia and inner pipe of 50mm dia and filling with specified qty highly conductive compound around pipe and above that with soft soil in bore pit complete and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. as per specification:				
	12.19.2	With 2 metre long GI Pipes and 25 kg back filling compound.	Each	7253.00	9.00	65277.00
14	12.18	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ concealed conduit/ submain wiring/ cable as per specification.	Metre	17.00	160.00	2720.00
15	31.13	Painting of following height steel tubular poles with two coat of copper paint of approved brand including cleaning the surface as per specification:				
	31.13.3	Above 8 metre and upto 10 metre	Each	242.00	236.00	57112.00
16	7.10	Providing and fixing metal clad, TP&N switch fuse unit (re-wirable), 415/500 volts, with porcelain re-wireble fuses including drilling holes on the board, connections, earthing the body etc. as per specification. (Thimbeling shall be paid separately).				
	7.10.3	100 amps	Each	3082.00	5.00	15410.00

ESTIMATE

Electrical SOR 10.04.2026 **Part A**

N	SOR	ITEM	UNIT	RATE	QTY	AMOUNT
	7.19	Fabrication, supply, installation, testing and commissioning of cubicle type compartmentalized wall/ floor mounted power cum control panel board of specified size and following depth made out of not less than 2 mm thick CRCA MS powder coated sheet with suitable size compartments for bus bars, switchgears and necessary cutouts for voltmeters, ammeters etc as per specifications including powder coating painting but without busbars, switchgears and other accessories etc complete as per specification.				
	7.19.1	Upto 300 mm deep	sqm	6014.00	1.80	10825.20
18	10.17	Providing and fixing penal mounting 230 volt LED type indicating lamp in existing cubical panel including, connections, testing and commissioning etc. as per specification.	Each	83.00	1.50	124.50
19	10.22	Providing and fixing following Time switch (timer) in existing panel including connection, testing and commissioning as per specification.				
	10.22.2	Analoge type	Each	2228.00	5.00	11140.00
20	9.16	Supplying and fixing TP&N MCB, 440 volts, 'C' curve, suitable for lighting and other loads in the existing MCB DB complete with connections, testing and commissioning etc. as per specification.				
	9.16.4	50 amps	Each	1161.00	5.00	5805.00
21	10.13	Providing and fixing 3 pole, 415/500 volts following rating (AC-1 Duty) power contactor in existing starter/ cubical panel including, connections, testing and commissioning etc. as per specification.				
	10.13.3	60 amps	Each	2876.00	5.00	14380.00
22	30.3	Earth work in hard rock (without blasting) with all lead and 1.5 metre lift, dressing, stacking excavated strata including refilling with excavated soil in trench / pit to ground level complete as per specification	cum	396.00	15.60	6177.60
23	30.12	Providing and laying Cast-in-situ cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm including mixing with mechanical mixer, compacting with vibrator, finishing and currying etc. complete but excluding form work.	cum	3022.00	7.50	22665.00
					RS.	**7553672.30**
					With 18% GST RS.	**1359661.01**
						8913333.31

Part B Non SOR

1	Item Rate	Charging cost for CSEB including Transformer and connection.	Each		2.00	
					RS.	

Sub Engineer
Municipal Corporation
Korba (C.G.)

Asstt. Engineer
Municipal Corporation
Korba (C.G.)

E. Engineer
Municipal Corporation
Korba (C.G.)