



# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

दर्दी जोन

फा.क्र./726,728,730,731,732,733, 735, 734 /निर्माण (दर्दी जोन)/2025/

कोरबा, दिनांक 09.06.2026

## प्रथम निविदा आमंत्रण की सूचना


लोक निर्माण विभाग में एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित निर्माण कार्य हेतु मैनुवल निविदा वेबसाईड से डाउनलोड कर मुहरबंद लिफाफे में निविदा आमंत्रित की जाती है :-

- निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने की अंतिम तिथि - दिनांक 01.07.2026 सायंकाल 3:00 बजे तक
- निविदा खुलने की अंतिम तिथि - दिनांक 01.07.2026 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1.	वार्ड कं. 48 हसदेव कमांक 01 अंतर्गत मॉ कलमी दाई के पास सार्वजनिक सामुदायिक एवं सांस्कृतिक भवन का संधारण एवं भवन में नयी सुविधा की व्यावस्था। (पार्षद मद)	7,00,000/-	5,300/-	750/-	Form-A	04 माह	सक्षम श्रेणी	01.07.2026
2.	वार्ड कं. 59 फर्टिलाइजर बर पेंड शिव मंदिर के पास अहाता निर्माण एवं अन्य विस्तार कार्य। (विधायक-प्रभारी मंत्री मद वर्ष 2025-26)	3,00,000/-	3,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.07.2026
3.	वार्ड कं. 55 नागिन भांठा सुमेधा में स्वास्थ्य केन्द्र के पास निर्माण। (विधायक-प्रभारी मंत्री मद वर्ष 2025-26)	5,00,000/-	5,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.07.2026
4.	वार्ड कं 54 जमनीपाली स्थित कबार आश्रम में शेड निर्माण कार्य। (विधायक-प्रभारी मंत्री मद वर्ष 2025-26)	5,00,000/-	5,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.07.2026
5.	वार्ड कं. 49 ओडिया बस्ती में मंच के सामने शेड निर्माण कार्य। (विधायक-प्रभारी मंत्री मद वर्ष 2025-26)	5,00,000/-	5,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.07.2026
6.	वार्ड कं. 52 जनकपुरी पाईप लाईन शिव मंदिर के पास मंच निर्माण। (विधायक-प्रभारी मंत्री मद वर्ष 2025-26)	5,00,000/-	5,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.07.2026
7.	वार्ड कं. 58 श्यामनगर साडा कालोनी में जोगी जनरल स्टोर्स के पास का जीर्णोद्धार एवं अन्य विस्तार कार्य। (विधायक-प्रभारी मंत्री मद वर्ष 2025-26)	5,00,000/-	5,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.07.2026
8.	वार्ड कं. 53 जनकपुरी मोहल्ला हनुमान मंदिर पावर सिटी पाईप लाईन के पास मंच निर्माण। (विधायक-प्रभारी मंत्री मद वर्ष 2025-26)	5,00,000/-	5,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.07.2026

उपरोक्त कार्यों की निविदा की सामान्य शर्त, धरोहर निविदा विज्ञप्ति, निविदा दस्तावेज व अन्य जानकारी कार्यालयीन अवधि में कार्यालय से प्राप्त की जा सकती है, साथ ही यह जानकारी विभागीय वेबसाईट Website : [www.korbamunicipal.in](http://www.korbamunicipal.in) एवं [www.uad.cg.gov.in](http://www.uad.cg.gov.in) में देखा एवं डाउनलोड किया जा सकता है।

// स्वच्छ भारत निर्माण में योगदान दें //

  
कार्यपालन अभियंता  
नगर पालिक निगम  
कोरबा (छ.ग.)



**OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)**  
**OF WORK - CONSTRUCTION OF BOUNDARYWALL AND OTHER EXTENTION WORK NEAR**  
**SHIV MANDIR BADD TREE IN FERTILIZER BASTI WN 59**

As per Sor :- Schedule of Rates Public Works Department [ PWD BUILDING 01-01-2015], AMD 08


NO.	ITEM	NO.	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	1.2 Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	1	60	1.5		90.00	SQM	7.20	648.00
	1.1 Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	18	1.2	1.2	1.2	31.104			
2	1.1.1 In all types of soils	1	60	0.4	0.4	9.6			
						40.704	CUM	185	7530.24
	1.18 Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete	18	1.2	1.2	0.1	2.592			
3		1	60	0.4	0.1	2.4			
						4.992	CUM	371	1852.032
	3.1 Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work 3.1.3 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	18	1.2	1.2	0.1	2.592			
4		1	60	0.4	0.1	2.4			
						4.992	CUM	2970	14826.24
	2.1 Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:	72	1		0.26	18.72			
5	2.1.1 Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	36	0.2		0.75	5.4			
		36	0.3		0.75	8.1			
		2	60		0.3	36			
		36	0.2		1.5	10.8			


		36	0.2		1.5	10.8			
		2	60		0.2	24			
						113.82	SQM	139	15820.98
3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.	18	1	1	0.25	4.5			
3.2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 6 graded stone aggregate 20mm nominal size).								
		18	0.2	0.3	0.75	0.81			
		1	60	0.2	0.3	3.6			
		18	0.2	0.2	1.5	1.08			
		1	60	0.2	0.2	2.4			
						12.39	CUM	4163	51579.57
3.4	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:					12.39	CUM	97.5	1208.025
3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:					929.25	KG	54.5	50644.125
8	<del>3.12.1 Thermo-Mechanically treated bars FE 415</del>								
7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:	1	56.4	0.2	1.5	16.92			
7.5.3	Cement Mortar 1:5 (1 cement : 5 coarse sand)								
9		1	56.4	0.3	0.4	6.768			
						23.688	CUM	3350	79354.8
1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	1				18.642	CUM	65	1211.73
10									
1.26	Carriage by mechanical transport upto 5 km lead:	1				22.062	CUM	111	2448.882
11	1.26.1 Earth								

12	18 Providing and fixing broken glass 100 mm thick in spacing not more than 40 mm both ways and laid in 50 mm thick (average) cement mortar 1:4 (1 cement : 4 coarse sand ) over compound walls, parapet walls and the like.	1	60	0.3	18	SQM	268	4824
13	9.16 Providing and fixing M.S. frames of doors, windows, ventilators and cupboards joints mitred and welded with 15x3 mm lugs 10cm long embedded in cement concrete blocks 15x10x10cm of grade M-10 or with wooden plugs and screws or with dash fastener or rawl plugs and screws or with fixing clips or with bolts and nuts as required including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer. 9.16.2 Angle-iron frames 50X50X5MM	1			50	KG	73.5	3675
14	9.6 Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. 9.6.2 In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	1			200	KG	68	13600
17	11.3 Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: 11.3.3 In Cement Mortar 1:5 (1 cement : 5 fine sand)	1	60	2.3	138	SQM	113	15594
18	11.2 Providing and making 12mm thick cement plaster of mix: 11.2.3 In Cement Mortar 1:5 (1 cement : 5 fine sand)	1	60	1.5	90	SQM	96.5	8685
19	14.59 Providing and applying Polymaric cement primer on all surface applied @ 0.80 litres/10 sqm as per relevant I.S. code 15489:1974 (product such as Birla white primacoat/activcoat, Asian Trucare, Dulux interior cement primer, Opus Calista / 110) with all tool tackles and labour etc. complete for the work.	1			228	SQM	29	6612

<p>20 Providing and applying on exterior surface REMIUM Exterior emulsion paint of required shade to give protective and water proof finish minimum 3 coats applied @ 1.40 lit / 10Sqm up to final finish as per relevant I.S. Code 15489:2013_Type -2 ClassD, C (Glossy /Semi Glossy finish ) (Product such as Asian Apex ,Dulux Weather Shield Prima E900, Berger Weathercoat Antidust Nerolac Everlas Excel, Nippon Sumo Etra, Opus True flex) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackles and labour etc. complete for the work.(With 3 Year Warranty.)</p>	1				228	SQM	84	19152
<p>21 14.71 Providing and applying satin/matt finish Enamel paint minimum 2 coats in all surface applying @ 0.75 lit/ 10 Sqm up to required finish as per relevent I.S. code 2932: 2013 of (Product such as Asian satin Enamel, Dulux Promise Premium Enamel, Nerolac Synthatic Enamel, Opus Prime enamel) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackle and labour etc. complete for the work.</p>	2	3	2		12	SQM	133	1596
								300862.62

SAY AS 3.00 LACS RUPEES ONLY

  
 Sub Engineer  
 Municipal Corporation  
 Korba (C.G.)

  
 Asst. Engineer  
 Municipal Corporation  
 Korba (C.G.)