



# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. पौक, कोरबा (छ.ग.)

टी.पी. नगर जोन

फा.क्र./8372/8536/टी.पी. नगर जोन/2020

कोरबा, दिनांक 11.02.2020

## निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित **PWD Building SOR 01.01.2015** से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :-

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 03.03.2020 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 03.03.2020 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र. 02 अंतर्गत तुलसी नगर (साकेत नगर) स्थित सामुदायिक भवन का मरम्मत एवं नवीनीकरण कार्य। द्वितीय निविदा (मरम्मत संधारण मद)	4,00,000/-	4,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	03.03.2020
2	वार्ड क्र. 02 अंतर्गत बंगाली चाल में बाउन्ड्रीवाल एवं मंच का मरम्मत कार्य। (मरम्मत संधारण मद)	3,83,000/-	3,830/-	750/-	Form-A	03 माह	सक्षम श्रेणी	03.03.2020

### निविदा की शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज हाथो-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. कॉलोनी रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट [www.korbamunicipal.in/uad.cg.gov.in](http://www.korbamunicipal.in/uad.cg.gov.in) डाउनलोड किया जाकर नवीन निविदा प्रपत्र **Form - A/B/ABC** (जारी दिनों तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
4. निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-  
(अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।  
(ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।  
(स) तृतीय लिफाफा में उपरोक्त दोनों लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
6. निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम



- रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
- कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
  - निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लेवें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
  - निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
  - निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
  - ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
  - शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
  - ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
  - कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
  - सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
  - सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष के लिये तथा मरम्मत संधारण के कार्यों को छोड़कर शेष कार्यों के लिये 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्यूरिटी के रूप में रोकी जावेगी।
  - निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
  - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र कंडिका क. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
  - ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
  - निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
  - निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
  - निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
  - निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट:-

- अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
- उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

(ठेकेदार के हस्ताक्षर)

नाम .....

पूर्ण पता .....

मोबाईल नं.- .....

कार्यपालन अभियंता  
नगर पालिक निगम  
कोरबा (छ.ग.)



**OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)**  
**ABSTRACT**


Name of Work **MAINTENANCE AND RENOVATION OF TULSINAGAR SAMUDAYIK BHAWAN AT WARD NO 02 SAKET NAGAR**  
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]


S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	3.14	Providing and mixing water proofing material in PCC/ RCC work in the proportion recommended by the manufacturer.	kg	25	43.50	1,087.50
2	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.3	Cement Mortar 1:5 (1 cement : 5 coarse sand)	cum	6.30	3350.00	21,105.00
3	9.2	Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.	Kg	175.00	66.00	11,550.00
4	17.1	Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :				
	1.1	Thickness upto 15mm	sqm	262.50	132.00	34,650.00
5	17.7	Providing and replacing broken vitreous china water closet squatting pan (Indian type) including removing the broken squatting pan and mortar, cutting and making good the walls and floors wherever required:				
	7.3	White Orissa pattern W.C. pan of size 580x440 mm	each	2.00	1888.00	3,776.00
6	16.42	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	cum	4.50	768.00	3,456.00
7	14.10	Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.				
	10.1	On new work (two or more coats)	sqm	240.50	44.50	10,702.25
8	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	485.25	94.50	45,856.12
9	14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:				
	15.1	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	sqm	228.80	56.00	12,812.80
10	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	5.03	4073.00	20,487.19
11	10.63	Providing and fixing 97mm thick Gypsum board partition upto ceiling height consisting of frame work "W" / "U" / "L" sections made of G.I. sheet with zinc coating of grade 120, consisting of floor and ceiling channel 50mm wide having equal flanges of 32mm and 0.55mm thick fixed to the floor and ceiling at the spacing of 610mm centre to centre with	sqm	105.00	758.00	79,590.00



REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	dash fastener of 12.5mm diameter 40mm length and the studs 48mm wide having one flange of 34mm and other flange 36mm and 0.55mm thick fixed vertically within flanges of floor and ceiling channel and placed at a spacing of 610mm centre to centre by 6mm dia bolts and nuts at both ends of partition fixed flush to wall with rawl plugs at spacing of 450mm centre to centre and fixing of boards to either side of frame work by 25mm dry wall screws on studs, floor and ceiling channels at the spacing of 300mm centre to center and 97mm thick Gypsum board which includes one layer of tapered edge 12.5mm thick Gypsum plaster board (conforming I.S. 2095-1982) screw fixed with 25mm screws at 300mm centre to centre to either side, including jointing and finishing to a flush finish with recommended jointing compound, jointing tape, joint finisher and two coats of primer suitable for board as per manufacture's specification and Direction of Engineer-in-charge all complete.				
12	17.2	Providing and replacing broken floor tile with ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including removing the broken tile and mortar, pointing the joints with white cement mixed with matching pigment etc., complete.			
	2.1	Size 300x300mm	sqm	25.00	1151.00
13	19.4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. INTERNAL WORK - EXPOSED ON WALL			
	4.1	15 mm nominal outer dia .Pipes.	metre	18.00	110.00
	4.3	25 mm nominal outer dia .Pipes.	metre	25.00	199.00
	4.4	32 mm nominal outer dia .Pipes.	metre	22.00	271.00

As per Estimate Amount Rs. 286764.86

  
Sub Engineer  
Nagar Palik Nigam  
Korba(C.G.)

  
Asst. Engineer  
Nagar palik Nigam  
korba(C.G.)



**OFFICE OF THE NAGAR PALIK NIGAM, KORBA ( C.G.)**  
**ABSTRACT**

Name of Work Internal Electrification of Tulsinagar samudayik bhawan at ward no 02 Saket nagar  
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD ELECTRICAL-01-08-2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	3.1	Wiring for light/ fan/ exhaust fan / call bell point with 1.5 sqmm FR PVC insulated stranded copper conductor single core cable in concealed PVC conduit, with 5 amp piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with same size cable etc as required.				
	1	Short Point	Point	30.00	236.00	7,080.00
	2	Medium Point	Point	20.00	388.00	7,760.00
	3	Long Point	Point	10.00	553.00	5,530.00
2	3.13	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FR PVC insulated copper conductor, single core cable in concealed PVC conduit as required.				
	11	6 X 2.5 sq. mm in 25mm conduit	Metre	90.00	172.00	15,480.00
	6	3 X 4 sq. mm in 25mm conduit	Metre	60.00	141.00	8,460.00
	7	3 X 6 sq. mm in 25mm conduit	Metre	30.00	183.00	5,490.00
3	6.1	Supplying and fixing metal box of following sizes (nominal size) in recess with suitable size phenolic laminated sheet cover in front including painting etc as required.				
	1	75 mm X 75 mm X 60 mm deep	Each	6.00	77.50	465.00
	2	100 mm X 100 mm X 60 mm deep	Each	8.00	93.50	748.00
	4	150 mm X 150 mm X 60 mm deep	Each	8.00	133.00	1,064.00
	5	180 mm X 100 mm X 60 mm deep	Each	4.00	121.00	484.00
	6	200 mm X 125 mm X 60 mm deep	Each	6.00	147.00	882.00
	8	200 mm X 250 mm X 60 mm deep	Each	6.00	216.00	1,296.00
4	6.3	Supplying and fixing of following sizes PVC switch box suitable for modular switches with modular base and cover plates on surface complete as required				
	1	94 mm X 94 mm (1/2 Module)	Each	10.00	111.00	1,110.00
	2	118mmX94mm (3 Module)	Each	20.00	123.00	2,460.00
	3	150mmX94mm (4 Module)	Each	25.00	133.00	3,325.00
	4	205mmX94mm (6 Module)	Each	15.00	163.00	2,445.00
5	7.1	Supplying and fixing following piano type switch, socket, other accessories on the existing switch box/ cover including connections etc. as required.				
	12	Fan regulator Electronic, step type moving all round	Each	8.00	178.00	1,424.00
	13	Ceiling rose 3 pin 5 amps	Each	18.00	28.00	504.00
	14	Pendent holder	Each	5.00	38.00	190.00
	15	Batten/ angle holder	Each	6.00	37.50	225.00
6	8.1	Supplying, installation, testing and commissioning of following sizes ceiling fan including wiring the down rods of standard length up to 30 cm with 1.5 sq. mm FR PVC insulated, copper conductor, single core cable, earthing etc. complete as required.				
	3	1400 mm sweep	Each	8.00	1637.00	13,096.00
7	8.20	Supplying, installation, testing and commissioning of following LED fitting (luminaries) down lighters in round/ square shape complete with electronic				



REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	driver heat sink capacitor and all other accessories on surface/ in false ceiling etc. as required and furnishing 2 Yrs Guarantee certificate from manufacturer.				
2	9 Watt	Each	5.00	1989.00	9,945.00
3	12 Watt	Each	5.00	2436.00	12,180.00
4	15/16 Watt	Each	4.00	2615.00	10,460.00

As per Estimate Amount Rs. **112103.00**



Sub Engineer  
Nagar Palik Nigam  
Korba(C.G.)



Asst. Engineer  
Nagar palik Nigam  
korba(C.G.)