



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

फा.क्र./880/निर्माण/2023/

कोरबा, दिनांक 29.03.2023

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :-

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 21.04.2023 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 21.04.2023 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	घरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	केन्द्रीय भण्डार गृह के शटर, कार्यालय कक्ष, शौचालय एवं बाथरूम का मरम्मत एवं संधारण कार्य। (मरम्मत एवं संधारण मद)	3,92,000/-	4,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	21.04.2023

निविदा की शर्तें:-

1. निविदा दरें प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज हाथो-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं. -495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनोंक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
4. निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-
 - (अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी (निविदा आमंत्रण पत्र जारी दिनांक के पश्चात् का मान्य) एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
 - (ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
 - (स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
6. निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर चुकता प्रमाण पत्र, पेन नम्बर, शपथ पत्र, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कडिका क्र. 04 के लिफाफा (अ) के अनुरूप प्रस्तुत करना अनिवार्य होगा।

क्रमशः.....02

- कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना कर्मोंक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
 9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
 10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
 11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
 12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
 13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
 14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
 15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
 16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत की दर से सुरक्षा राशि चल देयकों से 01 वर्ष की अवधि हेतु सिक्क्यूरिटी के रूप में रोकी जावेगी।
 17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
 18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथ पत्र कंडिका क्र. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
 19. ईट से संबंधित निर्माण कार्यों में फ्लाइ एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
 20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
 21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
 22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
 23. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

(ठेकेदार के हस्ताक्षर)

नाम

पूर्ण पता

.....

मोबाईल नं.-


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

प्रतिलिपि :- प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नया रायपुर (छ.ग.) को Uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT

NAME OF WORK - Maintenance & Renovation Work of Central Store Shutter, Office Room, Toilet And WashRoom Under Nigam Area

As per Sor :- Schedule of Rates Public Works Department [PWD BUILDING 01-01-2015]

S.NO.	Item Work	No.	L	B	H	Qty	Unit	Rate	Amount
1	Removing dry or oil bound distemper by scraping sand papering and preparing the surfaces smooth including necessary repair to scratches etc. complete.					379.36	SQM	5.20	1972.672
2	17.1 Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :					65.84	Sqm	132.00	8690.88
3	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.					379.36	Sqm	94.50	35849.52
5	14.11 Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade. 14.11.1 On New Work (two or more coats)					299.68	Sqm	32.00	9589.44
6	14.16 Painting exterior surface with PREMIUM ACRYLIC SMOOTH exteri or paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with 14.16.1 On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)					189.68	Sqm	74.50	14131.16
	14.23 Painting on old work (one or more coats) to give an even shade with: Satin synthetic enamel paint					39.00	Sqm	35.00	1365.00
	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).					1.60	cum	4073.00	6516.80
	16.31 Dismantling steel work in built-up section in angles channels, flats I-section and T-section including all gusset plates, bolts, nuts, cutting rivets, welding etc., including dismembering and stacking within 50 metres lead.					1800.00	kg	1.00	1800.00

Supplying and fixing rolling shutter of approved makes made M.S. laths interlocked together through their entire length and joined together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and out side locking with push and pull arrangement complete but excluding the cost of top cover and spring.

80x1.25mm M.S. Laths							
				97.60	Sqm	1691.00	165041.60
Providing and fixing 27.5cm long wire spring for rolling shutters.							
				20	each	362.00	7240.00
9.29 Providing and fixing M.S. sheet top cover for rolling shutter							
1.20mm thick							
				32.00	Sqm	530.00	16960.00
Providing and fixing ball bearing for rolling shutters							
				40	each	423.00	16920.00
14.22 Painting on new work (two or more coats) to give an even shade with.							
Satin synthetic enamel paint							
				217.60	sqm	55.00	11968.00
4.13 Grading roof for water proofing treatment with:							
4.13.1 Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)							
				4.72	cum	3817.00	18028.45
4.22 Providing Water proofing treatment over Roof, Wall, Chhajjas, Balcony with Diamond Shield and Sealer coat or equivalent at leakage/ seepage area consisting of the operation: (i) Surface preparation roughening of surface, opening of cracks in 'V' groove in size of 5mm x 10m (WxD), filling of cracks with putty of Diamond shield with laying fiber glass mesh, Cleaning of surface by scrubbing with steel wire/ Nylon brush. Removing all dust particles and washing with adequate water to clean completely. (ii) Providing and applying 1st coat of diamond shield or equivalent compound (having two component dry powder 80% Chemical 20% (chemical having 30% solid contents) making flexible waterproof and protective modified mortar with minimum thickness 70-80 micron after proper mixing of both the parts of compound along with laying of fiber glass mesh (of weaving size of 10x10 yarn/inch duly coated with alkaline resistant polymer). Allow the coating to set in natural air for minimum 2 Hrs. After 1st coat apply 2nd coat with minimum thickness 100 micron of the same compound. Allow the 2nd coat to set in natural air for minimum 4 Hrs. Total consumption of the diamond shield or equivalent in both coat should be @ 17.90 kg for 10sqm area (iii) Over the above layers providing and applying 1st coat of sealer compound (Single component High Build elastomeric, flexible, pure acrylic waterproofing membranes having solid content of 65%) minimum 50-60 micron and allow it to set in natural air for minimum 2 Hrs. After 1st coat apply 2nd and final coat 120-140 micron of sealer compound and allow it to set in natural air for minimum 4 Hrs. Consumption of Sealer compound should be @ 5.40 kg per 10 sqm area. The final area appearance of the coating will be milky white. (iv) The treated area should be cure with water for 48 hrs by flooding the surface. All above operations to be done in order.							
				70.40	sqm	421.00	29638.40

lettering with black Japan paint, per cm height.								
				986.00	per letter	0.70		690.20
12.9 Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc. complete								
Size 300x300mm				16.00	sqm	692.00		11072.00
12.7 Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.								
Size upto 200x300mm				24.60	sqm	587.00		14440.20
Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :								
White Size 550x450 mm				1.00	each	1430.00		1430.00
18.13 Providing and fixing white vitreous china urinal basin with waste fitting as per IS : 2556, and other couplings in C.P. brass complete.								
Flat back half stall urinal of size 460x380x250mm				2				
				2	each	1776.00		3552.00
Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.								
110 mm dia pipe.				16.00	metre	267.00		4272.00
Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion								
Tee/ Tee w/ th door/ Bend 45°/ Bend 90°								
110 mm				2.00	each	154.00		308.00
Vent cover								
110 mm				2.00	each	44.00		88.00
Access door cap								
110 mm				2.00	each	59.00		118.00
"P" trap 110mmx110mm long				2.00	each	227.00		454.00

Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, providing thermal stability for hot & cold water supply including CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. CONCEALED WORK including cutting chases and making good the walls etc.							
15 mm nominal outer dia Pipes				20.00	metre	133.00	2660.00
32 mm nominal outer dia Pipes				15.00	metre	284.00	4260.00
Providing and fixing 15 mm nominal bore Brass bib/stop cock of							
Bib cock (250 grams)				7.00	each	185.00	1295.00
Stop cock (350 grams)				5.00	each	237.00	1185.00
						Total	391905.09
							391905.09
						Say as. Rs	392000.00


 Sub. Engineer,
 Municipal Corporation
 Korba (C.G.)


 Asstt. Engineer,
 Municipal Corporation
 Korba (C.G.)