



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क्र./1220,1221/जल प्रदाय/2021

कोरबा, दिनांक 17.03.2021

द्वितीय निविदा आमंत्रण सूचना


नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग, से एकीकृत पंजीयन अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु कार्य क्र.01 पार्ट ए प्रमुख अभियंता लोक स्वास्थ्य यांत्रिकी विभाग रायपुर द्वारा दिनांक 07.02.2013 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान प्रतिशत दरों पर तथा पार्ट बी शेड्यूल अनुसार आयटम दरों पर फार्म "ए एवं बी" एवं कार्य क्र. 02 प्रमुख अभियंता लोक निर्माण विभाग (भवन एवं विद्युत) रायपुर द्वारा दिनांक 01.01.2015 एवं 01.07.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान प्रतिशत दरों पर मैन्युअल निविदा फार्म "ए" वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति के माध्यम से मुहरबंद निविदाएं आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि	धरोहर राशि	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1.	बांकीमोहरा जोन अंतर्गत एवं नगर निगम स्टाफ क्वार्टर में वॉटर स्टोरेज टैंक बदलने एवं पी.व्ही.सी. पाईप लाईन का मरम्मत एवं संधारण कार्य। (मरम्मत/संधारण मद)	3,55,700/-	3,600/-	750/-	02 माह	सक्षम श्रेणी	06.04.2021
2	निगम क्षेत्रांतर्गत 11 नग उच्च जलागारों में स्वीच रूम का निर्माण कार्य। (यूआईडीएसएसएमटी योजना)	13,72,100/-	10,300/-	750/-	04 माह	सक्षम श्रेणी	06.04.2021

निविदा की शर्तें

- कार्य क्र.01 पार्ट "ए" निविदा दरे प्रचलित एस.ओ. आर. से कम या अधिक प्रतिशत दरों पर दिया जावे एस. ओ. आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों एवं पार्ट "बी" निविदा दरे आयटम दर पर ही भरी जावे, अन्यथा निविदा निरस्त मानी जावेगी।
- कार्य क्र. 02 निविदा दरे प्रचलित एस.ओ. आर. से कम या अधिक प्रतिशत दरों पर दिया जावे एस. ओ. आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों एवं निविदा दरे आयटम दर पर ही भरी जावे, अन्यथा निविदा निरस्त मानी जावेगी।
- निविदा प्रपत्र नगर पालिक निगम कोरबा के वेबसाइट : www.korbamunicipal.in एवं www.uad.cg.gov.in से डाउनलोड किया जाकर नवीन निविदा प्रपत्र फार्म ए/बी/ए.बी.सी.(जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डी.डी. के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
- निविदा प्रपत्र स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किए जावेगे। निर्धारित तिथि को 3.00 बजे के पश्चात प्राप्त निविदाएं स्वीकार नहीं की जावेंगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य ना किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर चुकता प्रमाण पत्र/पैन नम्बर पत्र एवं जी.एस.टी. का पंजीयन प्रमाण पत्र प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र एवं धरोहर राशि प्रस्तुत करना होगा।
- निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा। प्रथम लिफाफे में वांछित दस्तावेज, अमानत राशि का टी.डी.आर./एफ.डी.आर एवं निविदा प्रपत्र के शुल्क का डी.डी. जो कि आयुक्त नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा,। द्वितीय लिफाफे में ठेकेदार द्वारा भरा निविदा प्रपत्र होगा। तृतीय लिफाफा में उपरोक्त दोनों लिफाफे होगी तथा आवश्यकता पडने पर मूल अभिलेख प्रस्तुत करना होगा।
- निविदा प्रपत्र उन्ही ठेकेदारों को दिया जायेगा जिन्हे इस प्रकार के कार्यों का अनुभव हो।
- पूर्ण रूप से भरी निविदा प्रपत्र उपरोक्त तिथि को 3.00 बजे तक प्राप्त की जा सकती है और उसी दिन 4.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहे तो उनके समक्ष खोले जावेंगे।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ठेके से संबंधित निविदा प्रपत्र उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं राज्य कर्मचारी बीमा निगम रायपुर से पंजीयन कराकर कोड प्राप्त कर प्रमाण पत्र प्रस्तुत करना होगा। अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
- सम्पूर्ण किए गए कार्यों के लिए प्रत्येक चल देयको में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए रोकी जावेगी।
- सम्पूर्ण किए गए कार्यों के लिए प्रत्येक चल देयको में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 05 प्रतिशत परफार्मस सिक्यूरिटी की गारंटी के रूप में प्रत्येक चल देयको में से 03 वर्ष रोकी जावेगी।

13. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में शपथ पत्र प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
14. सफल निविदादाता से अनुबंध के पूर्व अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जब कि निविदा की दरों में कौफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमनित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
15. शासन के विभिन्न विभागों जैसे—खनिज विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
16. निर्धारित निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाये जाने पर ही निविदा दर संबंधित लिफाफा खोला जावेगा, अन्यथा निविदा निरस्त मानी जावेगी।
17. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएं स्वयमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
18. कार्य हेतु लिफाफे पर कार्य का नाम, निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
19. ठेकेदारों को उपरोक्त कार्य हेतु लगे श्रमिकों का भुगतान बैंक के माध्यम से किया जाना अनिवार्य होगा।
20. निविदा प्रपत्र अहस्तांतरणीय होगा। एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- नोट:— 1. धरोहर राशि के रूप में एफ.डी.आर./टी.डी.आर. पृथक से लिफाफे में स्वीकार किए जावेंगे, जो आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में कोई तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।


 कार्यपालन अभियन्ता
 नगर पालिक निगम
 कोरबा (छत्तीसगढ़)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ESTIMATE

Work Name :- Construction of Switch Room (11 Nos) at OHT sites.


As per SOR: Schedule of rates [PWD Building SOR 01.01.2015]

S.N.	Item No.	ITEM DESCRIPTION	N	QTY	UNIT	RATE	AMOUNT
PATE - A							
1	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work					
		3.2.1 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	11	2.85	Cum	4163.00	130510.05
2	3.4	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	11	2.81	Cum	97.50	3013.73
3	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:					
		Beams, lintels, cantilevers & walls	11	7.20	Sqm	202.00	15998.40
		Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	11	17.00	Sqm	235.00	43945.00
4	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in.					
		Cement Mortar 1:4 (1 cement : 4 coarse sand)	11	12.13	Cum	3452.00	460600.36
5	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	11	12.09	Cum	121.00	16091.79
6	9.6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.					
		In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	11	141.05	Cum	68.00	105505.40
7	13.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:					
		Thermo-Mechanically treated bars FE 415	11	344.75	kg	54.50	206677.63
8	11.2	Providing and making 12mm thick cement plaster of mix:					
		In Cement Mortar 1:5 (1 cement : 5 fine sand)	11	76.46	Sqm	96.50	81162.29
9	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix					0.00
		In Cement Mortar 1:4 (1 cement : 4 fine sand)	11	63.70	Sqm	120.00	84084.00


10	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	11	76.46	Sqm	94.50	79480.17
11	14.5	White washing with lime to give an even shade.					
		On new work (Three or more coats)	11	63.70	Sqm	9.40	6586.58
12	14.7	Colour washing such as green, blue or buff with lime to give an even shade.					
		On new work (two or more coats) including a base coat of white washing	11	63.70	Sqm	12.00	8408.40
13	8.99	Providing and fixing M.S. bright finished or black enameled sliding door bolts with bolts, nuts and necessary iron screws:					
		250 x 16 mm	11	4.00	Each	72.50	3190.00
14	8.103	Providing and fixing M.S. bright finished or black enameled handles with necessary iron screws:					
		125 mm	11	1.00	Each	51.00	561.00
		100 mm	11	1.00	Each	45.00	495.00
15	14.22	Painting on new work (two or more coats) to give an even shade with:					
		Premium synthetic enamel paint	11	3.54	Sqm	47.00	1830.18
						Total	1248139.97
PATE - B							
[Electrification SOR 01.07.2015]							
1	3.1	Wiring for light/ fan/ exhaust fan / call bell point with 1.5 sqmm FR PVC insulated stranded copper conductor single core cable in concealed PVC conduit, with 5 amp piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with same size cable etc as required.					
		Short Point	11	1.00	Point	236.00	2596.00
		Medium Point	11	1.00	Point	388.00	4268.00
		Long Point	11	1.00	Point	553.00	6083.00
2	3.11	Wiring for power plug point with 2x4 sq mm FR PVC insulated stranded copper conductor cable in concealed PVC conduit along with modular type 16 Amp switch and 6 pin 16 amps socket outlet with modular base and cover plate, suitable size G.I. box, earthing the switch box and socket outlet with same size cable etc. as required.					
		Medium Point	11	2.00	Point	934.00	20548.00
3	3.3	Extra for providing and fixing light plug point on board in concealed PVC conduit point wiring with piano type 3 pin 5 amp socket outlet and 5 amp switch including cost of phenolic laminated sheet and M.S. box etc. as required.etc. as required.	11	2.00	Point	95.00	2090.00
4	3.13	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FR PVC insulated copper conductor, single core cable in concealed PVC					
		3 X 2.5 sq. mm in 20mm conduit	11	5.00	Metre	104.00	5720.00

		6 X 2.5 sq. mm in 25mm conduit	11	5.00	Metre	172.00	9460.00
		9 X 2.5 sq. mm in 32mm conduit	11	5.00	Metre	249.00	13695.00
5	7.5	Providing and fixing 16/32 amp DP surface switch with neon on suitable size wooden box including connection, testing etc. complete.	11	1.00	Each	139.00	1529.00
6	7.1	Supplying and fixing following piano type switch, socket, other accessories on the existing switch box/ cover including connections etc. as required.					
		Ceiling rose 3 pin 5 amps	11	1.00	Each	28.00	308.00
		Pendent holder	11	4.00	Each	38.00	1672.00
7	9.9	Providing and fixing metal clad, SP&N switch fuse unit (re-wirable), 230/250 volts, with porcelain re-wirable fuses including drilling holes on the board, connections, earthing the body etc. as required. (Thimbeling shall be paid separately).					
		32 amps	11	1.00	Each	931.00	10241.00
8	11.3	Supplying and fixing on surface/ recess following way, 240 volts SP&N MCB distribution board consumer unit of sheet steel phosphatized and powder painted, complete with tinned copper busbar, neutral busbar, earth bar, din bar, detachable gland plate, including interconnections, earthing etc. as required. (But without MCB/RCCB/Isolator)					
		2 + 4 way	11	1.00	Each	661.00	7271.00
9	11.10	Supplying and fixing SP MCB, 240 volts, 'B' curve, suitable for lighting and other loads in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
		6 amps to 32 amps	11	1.00	Each	154.00	1694.00
10	8.9	Supplying, installation, testing and commissioning of following surface/ concealed type fluorescent fitting (luminaries) complete with electronic ballast/ copper ballast glow type starter but without fluorescent lamp, on ceiling/ wall surface, earthing the fitting etc. as required.					
		4' x 40 W single patti type	11	1.00	Each	272.00	2992.00
11	8.19	Supplying, fixing, testing and commissioning of following CFL without ballast in existing CFL lighting luminaries as required.					
		18 W CFL (without choke)	11	2.00	Each	165.00	3630.00
12	8.12	Supplying, fixing, testing and commissioning of following 230/250 volts fluorescent lamp (tube) in existing lighting luminaries as required.					
		4' x 36/40 watt	11	1.00	Each	51.00	561.00
13	23.1	Providing and fixing for house service connection G.I. pipe 50mm dia 3.2 metre long with 2 Nos 50x50x6mm angle iron bracket on wall and 75x90mm shackle insulator with straps including accessories complete	11	1.00	Set	1601.00	17611.00


14	23.2	Supplying and installing (overhead) service main with following size PVC insulated PVC sheathed aluminium conductor cables suspended with bobbin insulator on existing bearer wire in an approved manner and as per specification etc. or drawn in existing G.I. pipe bracket or conduit pipe wherever required, including connection, testing etc.					
		2 x 6 sq. mm	11	20.00	Mtr	54.50	11990.00
Total							123959.00
PART -A + PART -B Total Rs.							1372098.97
Say Rs.							1372100.00



Sub Engineer
Municipal Corporation
Korba (C.G.)



Asstt. Engineer
Municipal Corporation
Korba (C.G.)



Executive Engineer
Municipal Corporation
Korba (C.G.)