

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. 1490 / 2026

सिस्टम टेंडर नं. 184787

कोरबा दिनांक 02.02.2026

ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता PHE-USOR 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र फार्म A में निविदा आमंत्रित की जाती है :-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि — 26.02.2026 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि — 26.02.2026 सायंकाल 4.00 बजे से

क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (DD)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	निगम एरिया में लोकेज की समस्या के कारण अलग-अलग ओवर हेड टैंक के 450 एम.एम. डायामीटर के स्लुइस वाल्व की मरम्मत एवं रिप्लेसमेंट कार्य (ग्री.पे.सं.नि. मद)	39.40	29600/-	03 माह	1500/-	वर्ग डी एवं प्रवर श्रेणी	26.02.2026 से

शर्त:-

1. निविदा दरे एस.ओ.आर. को कम या अधिक प्रतिशत दरों पर दिया जावे एवं आयटमों पर पृथक से आयटम दरों का उल्लेख किया जावे।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र/पैन नम्बर, वैध जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमाण्ड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का DD एवं शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट /रजिस्टर्ड डाक के माध्यम से निविदा खुलने की तिथि में दोपहर 3.00 बजे तक आयुक्त,नगर पालिक निगम,कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा को उपलब्ध कराना अनिवार्य होगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का DD जो कि आयुक्त, नगर पालिक निगम,कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन(वर्तमान तक वैधता)एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे एवं कर्मचारी भविष्य निधि संगठन(ई.पी.एफ.) एवं विभिन्न प्रावधानों को धारा 1952 के तहत निविदाकार का जीवित पंजीयन होना आवश्यक है साथ ही निविदा आमंत्रण दिनांक से विगत तीन माह की अवधि में जमा किये गये TRRN Payment Detail चालान की प्रति प्रस्तुत करना तथा ऑनलाईन अपलोड किया जाना अनिवार्य होगा।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
10. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. निविदा प्रपत्र फार्म -ए की कंडिका 11 अनुसार एस्कलेशन देय नहीं होगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान बजट आबंटन और राशि उपलब्ध होने पर किया जाएगा।
16. ठेकेदारों को निर्माण कार्य के दौरान निर्माण एवं अपशिष्ट प्रबंधन नियम 2016 में किये गये प्रावधानों का पालन करना होगा।
17. कार्य कियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
18. सफल निविदाकार को कार्य संपादन के दौरान पाईप बिछाये जाने के पूर्व पाईप एवं फिटिंग इत्यादि का CIPET से अभिप्रेमाणित जांच प्रमाण पत्र सहित SGS/RITES आदि संस्था के माध्यम से Thirt party inspection report प्रस्तुत करना अनिवार्य होगा। संबंधित दस्तावेज की अनुपलब्धता पर देयक भुगतान की कार्यवाही नहीं की जाएगी।

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Executive Engineer,
Municipal Corporation,
KORBA (Chhattisgarh)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		02.02.2026	15.30	02.02.2026	15.30	Release Tender
2		Bid Submission	02.02.2026	15.30	24.02.2026	17.30	
3		Physical Document Submission	02.02.2026	15.30	26.02.2026	15.00	
4	Tender Open		26.02.2026	16.00	--	--	


EXECUTIVE ENGINEER,
KORBA (CG)
 For, Commissioner Korba (C.G.)
KORBA (Chhattisgarh)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ESTIMATE

Work Name :- Repairing & Replacement of 450 MM Dia to 150 MM Dia Sluice Valves of Various Over Head Tank Due to Leakage Problem at Nigam Area.

(CG PHE SOR Amendment No 7/ 2022-23;

S.N.	ITEM DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	4.41 Providing & fixing of following Ductile iron double flanged sluice valves as per IS 14846:2000 fitted with cap including jointing & testing with cost of jointing material such as bolts, nuts, rubber insertions etc. all complete CLASS PN- 16				
	150 mm dia	2.00	Each	15200.00	30400.00
	200 mm dia	4.00	Each	27850.00	111400.00
	250 mm dia	2.00	Each	52154.00	104308.00
	300 mm dia	4.00	Each	68739.00	274956.00
	350 mm dia	3.00	Each	107902.00	323706.00
	400 mm dia	3.00	Each	136247.00	408741.00
	450 mm dia	3.00	Each	191693.00	575079.00
2	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 m lead as per direction of engineer-in-charge				
	Dismantling of Cement Concrete Pavment by mechanical means using pneumatic tools, cutter breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials up to a lead of 1000 metres, stacking serviceable and unserviceable materials separatel	60.00	Cum	1227.00	73620.00
3	Earth work in excavation for pipe trench in ordinary soil areas including dressing, watering, ramming and disposal of excavated earth lead up to 50m and lift up to 1.5m, disposal earth to be levelled, neatly dressed	363.00	Cum	201.00	72963.00
4	Providing and laying mechanically mixed cement concrete with crushed stone aggregate excluding centering and shuttering (with 40mm nominal size graded stone aggregate)				
	1:2:4 (M-15)	5.00	Cum	5910.00	29550.00
5	Providing & laying mechanically mixed cement concrete 20mm nominal size graded crushed stone excluding cost of centering & shuttering.				
	1:31/2:3 (M-20)	20.00	Cum	6545.00	130900.00
6	Providing and Laying including testing Ductile iron Mechanical joint collar with follower glands conforming to IS: 9523/2000 having dimension as per table 24 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen and internal cement mortar lining				
	150 mm dia	3.00	Each	3896.00	11688.00
	200 mm dia	6.00	Each	5035.00	30210.00

	300 mm dia	4.00	Each	7592.00	30368.00
	400 mm dia	5.00	Each	8901.00	44505.00
	350 mm dia	8.00	Each	14142.00	113136.00
	400 mm dia	4.00	Each	17309.00	69236.00
	450 mm dia	6.00	Each	19791.00	118746.00
7	Providing and Laying including testing ductile PN 16 type iron flanged spigot conforming to IS: 9523/2000 having dimensionas per table 24 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining with finishing as per clause 13 of IS: 9523/2000				
	150 mm dia	4.00	Each	2291.00	9164.00
	200 mm dia	8.00	Each	3294.00	26352.00
	250 mm dia	4.00	Each	4582.00	18328.00
	300 mm dia	6.00	Each	6015.00	36090.00
	350 mm dia	8.00	Each	9611.00	76888.00
	400 mm dia	4.00	Each	12014.00	48056.00
	450 mm dia	4.00	Each	15104.00	60416.00
8	Providing and Laying including testing ductile iron PN 16 type flanged sockets conforming to IS: 9523/2000 having dimension as per table 23 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining with finishing as per clause 13 of IS:9523/2000				
	150 mm dia	3.00	Each	2005.00	6015.00
	200 mm dia	6.00	Each	3007.00	18042.00
	250 mm dia	3.00	Each	4010.00	12030.00
	300 mm dia	5.00	Each	5298.00	26490.00
	350 mm dia	7.00	Each	8239.00	57673.00
	400 mm dia	3.00	Each	10470.00	31410.00
	450 mm dia	4.00	Each	13044.00	52176.00
9	Supply & Filling moorum/river sand for pipe bedding or over the pipe (including supply	30.00	Cum	864.00	25920.00
10	Filling available excavated earth in trenches, plinth sides of foundation in layers not exceeding 20cm. in depth including consolidation of each layer by ramming watering, lead up to 50m and lift up to 1.5m in all kinds of soils	660.00	Cum	82.00	54120.00
11	Construction of Rcc valve chamber with Rcc precast covers for valves. (100mm to 600mm dia.)				
	(cost as per rate analysis enclosed)	10.00	job	74641.40	746414.00

only for cutting following Ductile Iron pipes of any e and class. (CG PHED SOR Amendment 07/2022-23, It.No.19.4, Pg.No.60)				
200 mm	8.00	Per Cut	180.00	1440.00
250 mm	4.00	Per Cut	224.00	896.00
300 mm	8.00	Per Cut	269.00	2152.00
350 mm	6.00	Per Cut	312.00	1872.00
400 mm	6.00	Per Cut	357.00	2142.00
450 mm	8.00	Per Cut	400.00	3200.00
Chamfering of CI/DI pipes of all type sand classes to make suitable for tyton joints. (CG PHED SOR Amendment 07/2022-23, It.No.19.6, Pg.No.61)				
Up to 150 mm dia.	8.00	Each	1079.00	8632.00
200 mm dia.	4.00	Each	1343.00	5372.00
250 mm dia.	8.00	Each	1480.00	11840.00
300 mm dia.	8.00	Each	1681.00	13448.00
400 mm dia.	6.00	Each	2018.00	12108.00
450 mm dia.	8.00	Each	2194.00	17552.00
Rs.				3939750.00
Say Rs.				3939750.00


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asstt. Engineer
 Municipal Corporation
 Korba (C.G.)


**CONSTRUCTION OF RCC VALVE CHAMBERS WITH RCC PRECAST
COVERS FOR VALVES
(SIZE 2.2 M. X 2.2 M. X 2.3 M.)**

S. No.	Particulars	Qty.	Unit	Rate	Amount
1	Earth work in excavation for pipe trench in all kinds of soil and WBM in areas including dressing, watering and ramming and disposal of excavated earth lead up to 1.5 m. disposal earth to be leveled, neatly dressed. Chhattisgarh PHED USOR Amendment No.07/2022-23; Item No.18.15, Pg. No.51 2.4 x 2.4 x 1.0	7.08	Cum.	201.00	1424.04
2	Earth work in excavation for pipe trench in all kinds of rocks in areas including' dressing, stacking of useful material and disposal of unserviceable on up to 50 m. lead and lift up to 1.5 m. Chhattisgarh PHED USOR Amendment No.07 /2022-23; Item No.18.19, 18.19.3 & 18.19.7; Pg. No.51 & 52 a) Soft rock with or without blasting or bituminous pavement/cement concrete road. 2.4 x 2.4 x 1.0	6.16	Cum.	465.00	2865.89
3	Earth work in excavation for pipe trench in all kinds of rocks in areas including' dressing, stacking of useful material and disposal of unserviceable on up to 50 m. lead and lift up to 1.5 m. c) Hard rock requiring chiseling/where blasting is prohibited. Chhattisgarh PHED USOR Amendment No.07 /2022-23; Item No.18.19.3 & 18.19.7; Pg. No.51 & 52 2.4 x 2.4 x 0.3	1.73	Cum.	664.00	1147.39
4	Providing and laying mechanically mixed cement concrete 20mm nominal size graded crushed stone e/x cost of centring & shuttering. In Plinth & foundation M-10 (1:3:6) PCC of valve chambers Chhattisgarh PHED USOR Amendment No.07 /2022-23; Item No.18.41.1.1 ; Pg. No.54	0.58	Cum.	5216.00	3004.42
5	Providing and fixing formwork including centering shuttering, strutting, staging, propping bracing etc. complete & including removal of form work. i) Foundations, footing, base of columns and plinth beam in any shape and size up to plinth level. Floor or valve chambers walls of any thickness. ii) walls of any thickness included attached buttresses.	1.60 15.84	Sqm. Sqm.	231.00 402.00	369.60 6367.68
	Chhattisgarh PHED USOR Amendment No.07 /2022-23; Item No.18.64.1 ; Pg. No.56				
6	Providing & laying mechanically mixed R.C.C. excluding cantering & shuttering and reinforcement in foundation/plinth (20mm graded metal) M-20				

Chhattisgarh PHED USOR Amendment No- 07 2022-
Item No. 18.42.1 ; Pg. No.54

7	Providing and placing in position cold twisted steel and hot rolled deformed steel reinforcement for R.C.C. work i/c cutting, Bending, binding etc. complete i/c cost of binding wire and wastage. Qty = 100 kg/ m ³ of item no. 6 Chhattisgarh PHED USOR Amendment No- 07 2022-23, Item No. 18.44 ; Pg. No.54	4.57	Cum.	6025.00	27505.63
		456.53	Kg.	70.00	31956.75

Total = 74641.40


Sub Engineer
Municipal Corporation
Korba (C.G.)


Assistant Engineer
Municipal Corporation
Korba (C.G.)