कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क. **/ 729 / विद्युत / 2018**

सिस्टम टेंडर क. 50131 ई- प्रोक्यूरमेंट निविदा आमंत्रण सूचना

कोरबा, दिनांक 28.02.2019

नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विमाग, छ.रा.वि.मडल, एवं छत्तीसगढ़ अनुज्ञापन मंड़ल (विद्युत) में उचित श्रेणी में विद्युतीकरण कार्य हेतु पंजीकृत/लाईसेंसी ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियंता, लोक निर्माण विमाग (विद्युत) रायपुर द्वारा दिनांक 01.07.2015 से प्रमावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साध) कम अधिक या समान प्रतिशत दरों पर ई—प्रोक्यूरमेंट (E-Tendering) के माध्यम से निविदा आमंत्रित की जाती है :--

क	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रू में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड कं 56 घुड़देवा 03 नं. माइंस से भैरोताल रेल्वे लाईन तक प्रकाश व्यवस्था कार्य।	9,18,100 /-	7,000/-	03 माह	वर्ग अ— श्रेणी	23.03.2019 से

शर्ते :--

- निविदा दरे प्रचलित एस.ओ. आर. से कम या अधिक प्रतिशत दरों पर दिया जावे एस. ओ. आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- 2. निविदा ई-प्रोक्यूरमेंट (E-Tendering) के माध्यम से ही स्वीकार किए जावेगे। निर्धारित तिथि को 3.00 बजे के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं की जावेंगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य ना किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- 4. निविदा हेतु इच्छुक ठेकेदारों को ऊचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर चुकता प्रमाण पत्र /पेन नम्बर एवं जी.एस.टी. का पंजीयन प्रमाण पत्र, कर्मचारी भविष्य निधि एवं कर्मचारी राज्य बीमा निगम सबंधी प्रमाण पत्र, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र एवं धरोहर राशि को स्केन कापी ऑनलाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
- निविदा उन्ही ठेकेदारों को दिया जायेगा जिन्हे इस प्रकार के कार्यों का अनुभव हो।
- 6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सिन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत् पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ठेके से संबंधित निविदा उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन रायपुर एवं कर्मचारी राज्य बीमा निगम से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विमागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मुलप्रति में वैध शपथपत्र देना अनिवार्य होगा।
- 9. सम्पूर्ण किए गए कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 05 प्रतिशत परफार्मेस सिक्यूरिटी की गारंटी के रूप में प्रत्येक चल देयकों में से 03 वर्ष रोकी जावेगी।
- 10. निविदा दरों असामान्य कभी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बुँक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयाविध में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- ठेकेदारों को उपरोक्त कार्य हेतू लगे विद्युत श्रिमिकों का भुगतान बैंक के माध्यम से किया जाना अनिवार्य होगा।
- 12. निविदा प्रपन्न अहस्तांतरणीय होगा। एवं संशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त निर्णय अंतिम एवं सर्वमान्य होगा।
- 14. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- 15. उपरोक्त निवैदा सुचना की विस्तृत प्रति नगर पालिक निगम ,कोरबा के साकेत भवन स्थित विद्युत शाखा से प्राप्त किये जा सकते है

कार्यपालन अभियन्ता युक्त प्रात्निक निगम कीरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks	
	reagar reigani otage	Continuotor Garge	Date	Time	Date	Time		
1	Release Tender		28.02.19	18.00	28.02.19	18.00	Release Tender	
2		Bid Submission	28.02.19	18.00	22.03.19	17.30		
3	Tender Open		23.03.19	10.30				

EXECUTIVE ENGINEER

KORBA (CG)

For, Commissioner Korba (C.G.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.) ABSTRACT

Name of Work SUPPLY AND FIXING OF STREET LIGHT AT GHUDAVA 3 NO MINE TO RAILWAY LINE BHAROTAL W. NO. 56
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD ELECTRICAL-01-07-2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	21.7	Supply of hot dipped galvanized (in single dip to average 65 micron)			T	
		octoganal pole made of 3mm thick steel sheet having window and flush				
		cover with locking arrangement at suitable height from base for cable		100		
	93	termination block, pole suitably reinforced with welded steel section at				
		window cut section to make the strength of pole unaffected, with following				
		minimum specifications including 3mm thick anchor plate, 4 nos 20mm dia				
		foundation bolts of EN8 grade. (designed for wind speed upto 150km/hr)				
	2	7 metre high, dia 130mm at bottom and 70mm at top, base plate size	Each	28.00	10273.00	287,644.00
		220x220x12mm, foundation bolts 700mm long	Laon	20.00	10270.00	201,011.00
2	21.9	Supply and fixing following street light pole bracket on existing pole made out				
		of 50 mm dia MS "B" class pipe welded to 300 mm long MS pole canopy of				
		suitable dia at a angle of 102.50 including having MS triangular stiffner of				
		size 150 X 50 X 5 mm thick, making arrangement for tightening the bracket				
		with pole by providing suitable size heavy duty nuts and bolts in canopy,				
		painting with one coat of approved steel primer etc. as required.				
	1	Single Over Hang 0.75 metre Long	Each	28.00	949.00	26,572.00
3	21.11	Erection of GI octogonal/ tubular pole on existing cement concrete foundation	Lacin	20.00	540.00	20,072.00
		having grouted bolts and nuts, aligning in true vertical position as required.				
	5	7 metre high	Each	28.00	756.00	21,168.00
4	21.12	Designing and providing suitable RCC foundation in Cement Concrete 1:2:4	cum	6.72	4906.00	32,968.32
		(1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) for	ouiii	0.72	1000.00	02,000.02
		3 mere to 12 metre high GI octagonal pole including steel reinforcement				
		(minimum 90kg per cum), form work, embeding 2 nos 50mm dia PVC pipe				
		for cable entry in each foundation, excavation disposal of surplus soil and				
		curing etc. as required.				
5	5.11	Supplying and drawing following sizes of FR PVC insulated copper				
	0.11	conductor, single core cable in the existing surface/ concealed, steel/ PVC				
		conduit/ PVC casing caping as required.				
	2	2 x 1.5 sq. mm	Metre	224.00	33.00	7,392.00
6	11.10	Supplying and fixing SP MCB, 240 volts, 'B' curve, suitable for lighting and	Moto	221100	00.00	.,,
		other loads in the existing MCB DB complete with connections, testing and				
		commissioning etc. as required.				
	1	6 amps to 32 amps	Each	28.00	154.00	4,312.00
7	9.19	Fabrication, supply, installation, testing and commissioning of cubicle type				
	0.10	compartmentalized wall/ floor mounted power cum control panel board of				
		specified size and following depth made out of not less than 2 mm thick				
		CRCA MS sheet with suitable size compartments for bus bars, switchgears				
		and necessary cutouts for voltmeters, ammeters etc as per specifications				
		including powder coating painting but without busbars, switchgears and other				
		accessories etc complete as required.				
	4	(Only face area is to be measured)				
	1	Upto 300 mm deep	sqm	1.20	6492.00	7,790.40

			UNIT	QTY	RATE	AMOUNT
RE	EF	TEM DESCRIPTION Supplying and fixing DP MCB, 240 volts, 'C' curve, suitable for lighting and				
10	2	Supplying and fixing DP MCB, 240 Volts, O curve, sensetions, testing and	107			
	1	other loads in the existing MCB DB complete with connections, testing and				
		commissioning etc. as required.	Each	2.00	684.00	1,368.00
	5	63 amps BVC insulated/ XLPE, PVC				
17	7.1	Supplying and laying following sizes one number PVC insulated/ XLPE, PVC				
		sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade				
		direct in ground including excavation, sand cushioning, protective covering				
		and refilling the trench etc as required.	Metre	800.00	269.00	215,200.00
	4	2 x 16 sq. mm				
1	7.8	2 x 16 sq. mm Supplying and laying following sizes one number PVC insulated/ XLPE, PVC				
		supplying and laying following states of the supplying and laying states of the supplying states of				
		surface/ existing cable tray with 1 mm thick GI saddle as required.	Metre	30.00	88.00	2,640.00
+	3	0.40 - 4. mm	INICEO			
1 17	7.28	O salving fixing and cramping suitable size and all type aluminium teruler				
1		to following gize 1.1 KV grade power cable core / lead, pressed with				
		high pressure cramping tool including connection to switch gear/ MCCB etc				
		as required.	Each	120.00	13.00	1,560.00
+	3		Eduli	120.00		
2	9.9	Building and fixing metal clad. SP&N switch fuse unit (re-wirable), 250/250				
2	9.9	the with percelain re-wireble fuses including drilling noies on the board,				
		connections, earthing the body etc. as required. (Thimbeling shall be paid				
		separately).		1.00	1676.00	1,676.00
		00	Each	75.00	20.50	1,537.50
		Providing and fiving 6 SWG dia G.I. wire on surface or in recess to loop	Metre	/5.00	20.00	
13	14.19	earthing along with existing surface/ concealed conduit/ submain wiring/				
				400.00	130.00	15,600.00
		cable as required.	Metre	120.00	130.00	
	2	- in tellation, tasting and commissioning of following 250/250 volla				
14	8.30	Supplying, installation, testing and commerce of the LED street light fitting with all accessories like driver, heat sink made of die				
		cast aluminium with IP 66 protection and 5 KV surge protection on pole				
		bracket complete as required and furnishing 2 Yrs Guarantee certificate from				
					10115.00	283,220.00
		manufacturer.	Each	The second secon	10115.00	178.00
		3 60 watt 7 Providing and fixing penal mounting 230 volt LED type indicating lamp in	Each	2.00	89.00	110.00
15	12.1	Providing and fixing penal mounting 250 Volt EED type materials existing cubical panel including, connections, testing and commissioning etc.				
		as required.				
16	12.2	as required. 2 Providing and fixing following Time switch (timer) in existing panel including				2,070.0
		connection, testing and commissioning as required.	Eac	h 1.00	2070.00	2,070.0
		1 Digital type				1
1	7 12.	Digital type Providing and fixing 2 pole, 230/250 volts following rating power contactor in				
		existing starter/ cubical panel including, connections, testing and				4.000
		commissioning etc. as required.	Eac	ch 2.0	The second secon	
-				et 1.0	0 2472.00	2,472.
1	18 1	in C.L. and pine 4.5 metre long, 40 mm dia including				
1	10	I manufaling maconny enclosure with cover plate have	d			
		accessories, and providing masonly crisises at locking arrangement and watering pipe etc. (but without charcoal or coke an	IU			
		no constant	The second secon	ich 28.	00 9.5	0 266
		salt) as required. Numbering of ceiling fan/ exhaust fan/ fluorescent fittings as required.	Ea	20.		