

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क्र. 502/2026

सिस्टम टेंडर नं. 187353

कोरबा दिनांक 18.03.2026

ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015, विद्युत हेतु दिनांक 01.08.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र Form-A में निविदा आमंत्रित की जाती है:-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि - 10.04.2026 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 10.04.2026 सायंकाल 4.00 बजे से

| क्र. | कार्य का नाम | प्राक्कलन राशि (लाख में) | धरोहर राशि (FDR/TDR) | कार्यावधि | निविदा प्रतिभागी शुल्क (डिमांड ड्राफ्ट) | ठेकेदार का वर्ग | निविदा खुलने की तिथि |
|------|--|--------------------------|----------------------|-----------|---|--------------------------|----------------------|
| 1 | वार्ड क्र. 03 अंतर्गत न्यू टी.पी.नगर जोन ऑफिस का निर्माण कार्य (निगम मद) | 99.78 | 75000/- | 10 माह | 3000/- | वर्म डी एवं प्रवर श्रेणी | 10.04.2026 से |

शर्तें:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र, पेन नम्बर, वैध जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमाण्ड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं निर्धारित प्रारूप में शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा के पते पर भेजना होगा। निर्धारित तिथि को सायं 03:00 बजे के पश्चात् फिजिकल सबमिशन लिफाफा स्वीकार नहीं किया जायेगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निर्धारित प्रारूप में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात् का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन (वर्तमान तक वैधता) एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे एवं कर्मचारी भविष्य निधि संगठन (ई.पी.एफ.) एवं विभिन्न प्रावधानों को धारा 1952 के तहत निविदाकार का जीवित पंजीयन होना आवश्यक है साथ ही निविदा आमंत्रण दिनांक से विगत तीन माह की अवधि में जमा किये गये TRRN Payment Detail चालान की प्रति प्रस्तुत करना तथा ऑनलाईन अपलोड किया जाना अनिवार्य होगा।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ईट से संबंधित निर्माण कार्यों में फ्लाइंग एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
10. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. निविदा प्रपत्र फार्म -ए की कंडिका 11 Price Adjustment (एस्कलेशन) देय नहीं होगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान कार्य विशेष हेतु बजट आबंटन एवं राशि उपलब्ध होने पर किया जाएगा।
16. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
17. कार्य कियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
18. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।



अधीक्षक अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

| Seq. No. | Nagar Nigam Stage | Contractor Stage | Start | | Expiry | | Remarks |
|----------|-------------------|------------------------------|------------|-------|------------|-------|----------------|
| | | | Date | Time | Date | Time | |
| 1 | Release Tender | | 18.03.2026 | 15.30 | 18.03.2026 | 15.30 | Release Tender |
| 2 | | Bid Submission | 18.03.2026 | 15.30 | 08.04.2026 | 17.30 | |
| 3 | | Physical Document Submission | 18.03.2026 | 15.30 | 10.04.2026 | 15.00 | |
| 4 | Tender Open | | 10.04.2026 | 16.00 | -- | -- | |



**SUPERITENDING ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)**

OFFICE OF THE MUNICIPAL CORPORATION KORBA

ABSTRACT

NEW TP NAGAR ZONBE OFFICE

Ground Floor

SUB STRUCTURE

| S.NO. | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|-------|--|------|--------|---------|-----------|
| 1 | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits | | | | |
| A | 1.1.1 In all types of soil | CUM | 595.56 | 185.00 | 110178.60 |
| B | Extra for every additional lift of 1.5 m or part thereof. 1.6.1 All types of soils | CUM | 169.89 | 33.00 | 5606.37 |
| C | 1.1.2 In ordinary rocks. | CUM | 0.00 | 367.00 | 0.00 |
| 2 | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc complete 1.18 | CUM | 28.38 | 371.00 | 10528.24 |
| 3 | Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 3.1.3 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size) | CUM | 25.58 | 2970.00 | 75966.66 |
| 4 | Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels. for: | | | | |
| A | Foundations, footings, base of columns and plinth beam in any shape and size. 2.1.1 | Sqm | 176.00 | 139.00 | 24464.00 |
| B | 2.1.5 Columns, Pillars, Piers and likes- rectangular or square in shape | Sqm | 156.60 | 297.00 | 46510.20 |
| C | 2.1.8 Beams, lintels, cantilevers & walls | Sqm | 176.00 | 202.00 | 35552.00 |
| D | 2.1.7 Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ) | Sqm | 18.00 | 235.00 | 4230.00 |
| F | 2.1.2 Wall of any thickness including attached pilasters, buttresses etc. in super structure. | Sqm | 126.00 | 228.00 | 28728.00 |
| 5 | 3.2 Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.. 1:1 1/2:3 (1 cement : 1 1/2 coarse sand : 3 graded stone aggregate 20mm nominal size) 3.2.1 | CUM | 183.42 | 4163.00 | 763585.79 |

| S.NO. | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|--------------------|---|------|----------|----------------|-------------------|
| 6 | 3.12 Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: 3.12.2 Thermo-Mechanically treated bars FE 500D | Kgs | 20176.42 | 54.50 | 1099614.89 |
| 7 | 7.5 Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: :7.5.3 Cement Mortar 1:5 (1 cement : 5 coarse sand) | CUM | 16.26 | 3350.00 | 54468.99 |
| 9 | Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M. 1.17 | CUM | 989.18 | 65.00 | 64296.38 |
| 14 | 1.26 Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth | Cum | 393.62 | 111.00 | 43691.27 |
| | | | | Total:- | 2367421.37 |
| upper floor | | | | | |
| 1 | Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels. for: | | | | |
| A | 2.1.7 Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ) | Sqm | 463.39 | 235.00 | 108896.65 |
| B | 2.1.15 Stair cases of all types excluding spiral and folded plate type, including risers and landings | Sqm | 31.68 | 230.00 | 7286.40 |
| C | 2.1.8 Beams, lintels, cantilevers & walls | Sqm | 536.00 | 202.00 | 108272.00 |
| D | 2.1.5 Columns, Pillars, Piers and likes-rectangular or square in shape | Sqm | 727.20 | 297.00 | 215978.40 |
| E | 2.1.2 Wall of any thickness including attached pilasters, buttresses etc. in super structure. | Sqm | 19.20 | 228.00 | 4377.60 |
| 2 | 3.2 Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.. 1:1 1/2:3 (1 cement : 1 1/2 coarse sand : 3 graded stone aggregate 20mm nominal size). (3.2.1) & 3.4 Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and | CUM | 113.67 | 4260.50 | 484288.90 |

| S.NO. | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|-------|---|------|----------|---------|-----------|
| 3 | 3.12 Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: 3.12.2 Thermo-Mechanically treated bars EE 500D | Kgs | 12503.65 | 54.50 | 681448.65 |
| 4 | Brick work with modular fly-ash lime bricks (FALG Bricks) conforming to IS:12894-2002 of class designation 40 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) & extra for brick work in superstructure: Above plinth and upto floor five level.7.5.4 & 7.6 | CUM | 275.80 | 3471.00 | 957284.45 |
| 5 | Providing and fixing aluminium work for doors, windows, ventilators and partitions made out of extruded aluminium standard sections (main section with minimum 1.5mm thickness) conforming to IS: 733, IS: 1285 mitred and jointed mechanically including aluminium cleats, neoprene weather stripping gasket beveled edge beading, screws duly fixed in wall/ floor with fixing clips or hold fasteners or bolts and nuts as required aluminium sections shall be anodized transparent or dyed to approved shade according to IS: 1868, minimum anodic coating shall be of grade AC-15. (Glazing and panelling to be paid for separately For shutter of doors, windows & ventilators including providing and making provision for fixing of fitting wherever required including the cost of PVC/ neoprene gasket required (Fittings shall be paid for separately).9.47 | | | | |
| A | 9.47.1 For fixed portion | kgs | 137.40 | 331.00 | 45479.40 |
| B | 9.47.2 For shutter of doors, windows & ventilators including providing and making provision for fixing of fitting wherever required including the cost of PVC/ neoprene gasket required (Fittings shall be paid for separately). | kgs | 137.40 | 338.00 | 46441.20 |
| 6 | Glazing Work | | | | |
| A | Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete. (Cost of aluminium snap beading shall be paid in basic item): 9.51.2 With float glass panes of 5 mm thickness With float glass panes of 5 mm thickness | sqm | 57.80 | 804.00 | 46471.20 |
| B | 9.56 Extra for providing and fixing reflective glass panes in aluminium door, window, ventilator shutters and partitions instead of float glass. 9.59.2 5 mm thickness | sqm | 57.80 | 292.00 | 16877.60 |
| 7 | 6mm thick cement plaster of mix:11.1.2 In Cement mortar 1:4 (1 cement : 4 fine sand) | Sqm | 1758.27 | 87.00 | 152969.49 |

| S.NO. | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|-------|--|-------|---------|---------|-----------|
| 8 | 12mm thick cement plaster of mix:11.2.3 In Cement Mortar 1:5 (1 cement : 5 fine sand) | Sqm | 1449.63 | 96.50 | 139889.05 |
| 9 | 15mm thick cement plaster on the rough side of single or half brick wall of mix:11.3.3 In Cement Mortar 1:5 (1 cement : 6 fine sand) | Sqm | 1341.63 | 113.00 | 151603.91 |
| 10 | 12.13 Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete | | | | |
| | 12.13.1 Size 600x600mm | Sqm | 807.37 | 1151.00 | 929282.87 |
| 11 | Granite Work | | | | |
| A | 12.46 15 mm thick Table rubbed polished Granite stone slab in risers and treads of steps skirting dado and pillars laid on 12mm (average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry including rubbing and polishing etc. complete (single stone is to be used for risers and treads of steps and width of stone for skirting and dado shall be equal to the height of skirting & dado and length of 1.0 m). | | | | |
| | 12.46.2 Granite stone black | sqm | 15.84 | 2719.00 | 43068.96 |
| | 12.46.3 Granite stone lakha red/ shahi red | sqm | 15.84 | 4273.00 | 67684.32 |
| B | 13.6 15mm thick Granite work (machine cut, table rubbed & mirror polished) for kitchen platform, vanity counters, window sills and similar locations of required size laid over 20mm thick base cement mortar 1:4 (1 cement : 4 coarse sand) including joints treated with white cement mixed with matching pigment including rubbing and polishing to edge moulding to give high gloss finish. 13.6.2 Granite stone black | Sqm | 7.25 | 3279.00 | 23779.31 |
| C | 13.17 Providing and fixing 15mm thick Granite (machine cut, table rubbed & mirror polished on both sides) for partition curtain in toilets or similar locations of required size in wall with cement mortar 1:4 (1 cement : 4 coarse sand) including cutting chase in wall and joint with wall treated with white cement mixed with matching pigment including rubbing and polishing to edge moulding to give high gloss finish. 13.17.2 Granite stone black | sqm | 7.20 | 2924.00 | 21052.80 |
| D | 13.20 Extra for fixing marble /granite stone in facia and drops of width upto 150 mm with epoxy resin based adhesive instead of cement mortar including cleaning etc. complete. | Meter | 12.76 | 257.00 | 3279.32 |

| S.NO. | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|-------|---|------|---------|--------|-----------|
| E | 13.21 Extra for making opening of required size & shape for wash basins/ kitchen sink in kitchen platform, vanity counters and similar location in marble/Granite/stone work including making necessary holes for pillar taps etc. including rubbing and polishing of cut edges etc. complete. | Each | 8.00 | 253.00 | 2024.00 |
| 11 | Distempering with acrylic washable distemper to give an even shade.14.9.1 On new work (Two or more coats) | Sqm | 3099.90 | 38.00 | 117796.11 |
| 12 | Finishing walls with water proofing cement paint of required shade to give an even shade. 14.14.1 On new work (Two or more coats applied @ 3.84 kg/10 sqm) | Sqm | 1449.63 | 41.00 | 59434.73 |
| 13 | Painting on new work (two or more coats) to give an even shade with: 14.22.2 Premium synthetic enamel paint (2nd top most approved branded quality) to give an even shade. | Sqm | 179.69 | 47.00 | 8445.43 |
| 14 | Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI,Nerolac, J.K. wall putty) on walls to make the surface smooth and even 14.13 | Sqm | 4549.53 | 94.50 | 429930.11 |
| 15 | Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat of red oxide zinc chromate primer.. 9.15 | Kgs | 833.75 | 67.50 | 56278.13 |
| 15 | Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. 12.7& 12.7.2 Size above 200x300mm | Sqm | 330.12 | 646.00 | 213257.52 |

| S.NO. | DESCRIPTION | | | | |
|-------|--|-----|--------|---------|-----------|
| 16 | Providing and fixing flush door shutters, interior grade, commercial type, core of block board construction with frame of first class hard wood and well matched commercial ply veneering with vertical grains, cross bands and face veneers on both faces of shutters excluding hinges | | | | |
| A | 8.13.2 35 mm. thick (single leaf) | Sqm | 27.83 | 1370.00 | 38120.25 |
| B | 8.15 Extra for double leaf shutter instead of single leaf. | | | | |
| 17 | Providing and fixing bright finished brass sliding door bolt with nuts and brass polished MS screws complete 8.60.1 300x16mm | Nos | 30.00 | 475.00 | 14250.00 |
| 18 | Providing and fixing bright finished brass tower bolts (barrel type) with brass polished MS screws complete:8.62.1 250x10mm | Nos | 15.00 | 276.00 | 4140.00 |
| 19 | Providing and fixing bright finished brass door handles with brass polished MS screws complete: 8.65.1 125 mm | Nos | 30.00 | 55.50 | 1665.00 |
| 20 | Providing and fixing bright finished brass butt hinges with brass polished MS screws complete: 8.58.1 125x85x5.50 mm (Heavy Type) | Nos | 90.00 | 245.00 | 22050.00 |
| 21 | granite Stone Flooring | | | | |
| A | 12.45 15 mm thick Table rubbed polished Granite stone slab flooring laid over 20mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry including rubbing and polishing etc. complete. (Area of slab should be 0.50 sqm and above) | | | | |
| | 12.45.2 Granite stone black | Sqm | 80.00 | 2646.00 | 211680.00 |
| | 12.45.3 Granite stone lakha red/ shahi red | Sqm | 80.00 | 4200.00 | 336000.00 |
| B | 12.46 15 mm thick Table rubbed polished Granite stone slab in risers and treads of steps skirting dado and pillars laid on 12mm (Average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry including rubbing and polishing etc. complete (single stone is to be used for risers and treads of steps and width of stone for skirting and dado shall be equal to the height of skirting & dado and length of 1.0 | Sqm | 10.80 | 2719.00 | 29365.20 |
| 22 | 9.48 Extra for powder coated (minimum 50 micron) aluminium sections instead of anodized. | kgs | 161.40 | 27.00 | 4357.80 |

| S.NO. | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|-------|-------------|------|-----|------|--------|
|-------|-------------|------|-----|------|--------|

| | | | | | |
|--|---|----|--|------------|--|
| | SUB Structure | RS | | 2367421.37 | |
| | Super Structure | RS | | 6309455.36 | |
| | | | | 8676876.74 | |
| | Add extra for Water Supply sanitary & Electrification @ 15% of Civil work | RS | | 1301531.51 | |
| | Total | RS | | 9978408.25 | |



महापालिका कार्यपालिका,
 कान्छा बाजार, काठमाडौं,
 नेपाल (२०७३)



Executive Engineer
 Municipal Corporation
 KORBA (C. G.)