



# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क./771,780,781/विद्युत/2019

कोरबा, दिनांक 11.07.2019

## निविदा आमंत्रण सूचना

नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग, छ.रा.वि.मंडल, एवं छत्तीसगढ़ अनुज्ञापन मंडल (विद्युत) में उचित श्रेणी में विद्युतीकरण कार्य हेतु पंजीकृत/लाईसेंसी ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियंता लोक निर्माण विभाग (विद्युत) रायपुर द्वारा दिनांक 01.07.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान प्रतिशत दरों पर मुहरबंद निविदाएं आमंत्रित की जाती है :-

	कार्य का नाम (निगम मद)	प्राक्कलन राशि	घरोहर राशि	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने हेतु आवेदन प्रस्तुत करने की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1	वार्ड कं. 30 अंतर्गत मानिकपुर में जूनो लाईट प्रदाय एवं स्थापना कार्य।	3,03,472/-	3,100/-	750/-	02 माह	वर्ग अ श्रेणी	24.07.2019	27.07.2019	02.08.2019
2	वार्ड कं. 25 एस.ई.सी.एल.कालीबाडी मंदिर के सामने मैदान के पास हाईमास्ट लाईट प्रदाय एवं स्थापना कार्य।	4,39,120/-	4,400/-	750/-	02 माह	वर्ग अ श्रेणी	24.07.2019	27.07.2019	02.08.2019
3	वार्ड कं.07 अंतर्गत वृद्ध आश्रम में आंतरिक विद्युतीकरण कार्य।	2,62,095/-	2,700/-	750/-	02 माह	वर्ग ब श्रेणी	24.07.2019	27.07.2019	02.08.2019

शर्तें :-

- निविदा दरे प्रचलित एस.ओ. आर. से कम या अधिक प्रतिशत दरों पर दिया जावे एस. ओ. आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा प्रपत्र की प्रतियाँ नगर पालिक निगम, साकेत भवन रामपुर, कोरबा कार्यालय से उपरोक्त कार्य हेतु नाम के सम्मुख अंकित राशि नगद जमा कर उपरलिखित तिथि तक सायं 5.00 बजे तक अवकाश के दिनों को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा मांगा हो तो रु. 50/- अधिक भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की जिम्मेदारी इस कार्यालय की नहीं होगी।
- निविदा प्रपत्र स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किए जावेंगे। निर्धारित तिथि को 3.00 बजे के पश्चात प्राप्त निविदाएँ स्वीकार नहीं की जावेंगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य ना किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर चुकता प्रमाण पत्र/पैन नम्बर पत्र एवं जी.एस.टी. का पंजीयन प्रमाण पत्र प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र एवं घरोहर राशि प्रस्तुत करना होगा।
- निविदा प्रपत्र उन्ही ठेकेदारों को दिया जायेगा जिन्हें इस प्रकार के कार्यों का अनुभव हो।
- पूर्ण रूप से भरी निविदा प्रपत्र उपरोक्त तिथि को 15.00 बजे तक प्राप्त की जा सकती है और उसी दिन 16.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहें तो उनके समक्ष खोले जावेंगे।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन ) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ठेके से संबंधित निविदा प्रपत्र उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं राज्य कर्मचारी बीमा निगम रायपुर से पंजीयन करार कोड प्राप्त कर प्रमाण पत्र प्रस्तुत करना होगा। अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
- सम्पूर्ण किए गए कार्यों के लिए प्रत्येक चल देयको में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 05 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में प्रत्येक चल देयको में से 03 वर्ष रोकी जावेगी।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में शपथ पत्र देना अनिवार्य होगा।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- ठेकेदारों को उपरोक्त कार्य हेतु लगे विद्युत श्रमिकों का भुगतान बैंक के माध्यम से किया जाना अनिवार्य होगा।
- निविदा प्रपत्र अहस्तांतरणीय होगा। एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।

नोट:-

- घरोहर राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद स्वीकार किए जावेंगे जो आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
- उपरोक्त तिथियों में कोई तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

कार्यपालन अभियंता  
नगर पालिक निगम  
कोरबा (छत्तीसगढ़)



# OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

## DETAILED ESTIMATE

Name of work-

*Internal Electricals Brihda Ashram.*  
*Vol. No - 07*

As per SOR: Schedule of rates public works department [PWD Electrical -01-04-2015]


S.N.	SOR	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	4.7	Wiring for light/ fan/ exhaust fan / call bell point with 1.5 sqmm FR PVC insulated stranded copper conductor single core cable in surface PVC conduit, with 5 amp modular switch, modular base and cover plate, suitable size G.I. box and earthing the point with same size cable as required.				
	4.7.1	Short Point	Point	18.00	252.00	4536.00
	4.7.2	Medium Point	Point	10.00	394.00	3940.00
	4.7.3	Long Point	Point	150.00	518.00	77700.00
2	4.9	Extra for providing and fixing light plug point on board in surface PVC conduit point wiring with modular type 3 pin 5 amp socket outlet and 5 amp switch including cost of base and cover plate and G. I. box etc. as required.	Point	18.00	240.00	4320.00
3	4.10	Wiring for light plug point with 2x2.5 sq mm FR PVC insulated stranded copper conductor cable in surface PVC conduit along with modular type 6 Amp switch and 3 pin 6 amps socket outlet with modular base and cover plate, suitable size G.I. box, earthing the switch box and socket outlet with same size cable etc. as required.				
	4.10.5	Extra Long Point II	Point	9.00	1645.00	14805.00
4	4.13	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FR PVC insulated copper conductor, single core cable in surface PVC conduit etc as required.				
	4.13.2	3 X 2.5 sq. mm in 20mm conduit	Metre	320.00	95.00	30400.00
	4.13.6	3 X 4 sq. mm in 25mm conduit	Metre	110.00	130.00	14300.00
5	7.1	Supplying and fixing following piano type switch, socket, other accessories on the existing switch box/ cover including connections etc. as required.				
	7.1.13	Ceiling rose 3 pin 5 amps	Each	172.00	28.00	4816.00
		Batten/ angle holder	Each	6.00	37.50	225.00
6	9.1	Supplying and fixing wall/ floor mounted metal board of welded construction, fabricated with minimum 50mmX 50mm X 6mm angle iron frame work, with horizontal and vertical intermediate members of suitable angle/flat iron for mounting of switch gears including painting etc. as required.	sqm	0.50	2878.00	1439.00
7	9.5	Supplying and fixing metal clad busbar chamber made of 1.6 mm thick CRCA sheet with 2 strip aluminium alloy or wrought aluminium busbars of following capacity and length, complete with all accessories, including earthing the body etc. as required.				





	9.5.2	100 amps x 450mm long	Each	1.00	1232.00	1232.00
8	9.10	Providing and fixing metal clad, TP&N switch fuse unit (re-wirable), 415/500 volts, with porcelain re-wireable fuses including drilling holes on the board, connections, earthing the body etc. as required. (Thimbeling shall be paid separately).				
	9.10.2	63 amps	Each	1.00	1821.00	1821.00
9	11.2	Supplying and fixing on surface/ recess following way, 240 volts SP&N MCB distribution board of sheet steel phosphatized and powder painted complete with tinned copper busbar, neutral busbar, earth bar, din bar, detachable gland plate, including interconnections, earthing etc. as required. (But without MCB/RCCB/Isolator)				
	11.2.6	8 way, Double door	Each	4.00	986.00	3944.00
10	11.10	Supplying and fixing SP MCB, 240 volts, 'B' curve, suitable for lighting and other loads in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
	11.10.1	6 amps to 32 amps	Each	16.00	154.00	2464.00
11	11.12	Supplying and fixing DP MCB, 240 volts, 'C' curve, suitable for lighting and other loads in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
	11.12.2	6 amps to 32 amps	Each	4.00	428.00	1712.00
12	8.1	Supplying, installation, testing and commissioning of following sizes ceiling fan including wiring the down rods of standard length up to 30 cm with 1.5 sq. mm FR PVC insulated, copper conductor, single core cable, earthing etc. complete as required.				
	8.1.1	1050 mm sweep	Each	34.00	1503.00	51102.00
13	8.11	Supplying, installation, testing and commissioning of following T-5 fluorescent fitting (luminaries) complete with electronic ballast but without fluorescent lamp, on ceiling/ wall surface, earthing the fitting etc. as required.				
	8.11.1	Single box type with decorative end caps	Each	40.00	635.00	25400.00
14	8.12	Supplying, fixing, testing and commissioning of following 230/250 volts fluorescent lamp (tube) in existing lighting luminaries as required.				
	8.12.2	4' x 28 watt (T-5)	Each	40.00	143.00	5720.00
15	7.4	Supplying and fixing following modular switch, socket, other accessories on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
	7.4.8	Fan regulator (two module size) electronic stepped type moving all rounds	Each	34.00	203.00	6902.00
	7.4.20	Blanking plate	Each	20.00	24.00	480.00



16	17.8	Supplying and laying following sizes one number PVC insulated/ XLPE, PVC sheathed, unarmoured, aluminium conductor power cable of 1.1 KV grade on surface/ existing cable tray with 1 mm thick GI saddle as required.				
	17.8.13	4 x 10 sq. mm.	Metre	20.00	108.00	2160.00
17	14.1	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. (but without charcoal or coke and salt) as required.	Set	1.00	2472.00	2472.00
18	14.19	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ concealed conduit/ submain wiring/ cable as required.	Metre	10.00	20.50	205.00
<b>TOTAL =</b>						<b>262095.00</b>

  
 Sub Engineer  
 Municipal Corporation  
 Korba (C.G.)

  
 Asstt. Engineer  
 Municipal Corporation  
 Korba (C.G.)

  
 Executive Engineer  
 Municipal Corporation  
 Korba (C.G.)