

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

454/

फा.क./निर्माण /2018

सिस्टम टेन्डर नं. 47826

कोरबा, दिनांक 04/01/2019


ई-निविदा आमंत्रण सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई-निविदा आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क 17 में नाली निर्माण एवं कांकीट पेविंग का निर्माण कार्य।	3539841.00	27000/-	04 माह	वर्ग डी एवं प्रवर श्रेणी	29.01.2019 से

शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पेन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. निविदा उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रदाय नहीं किया जावेगा।
6. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निविदा जारी तिथि से 10 दिवस पूर्व का नोटरी सत्यापित शपथपत्र देना अनिवार्य होगा।
7. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
8. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
9. कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेंट की खरीदी ठेकेदारों को स्वयं करनी होगी।
10. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
11. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
12. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
13. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
14. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
15. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।


कार्यपाल अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		04.01.19	10.30	04.01.19	10.30	Release Tender
2		Bid Submission	04.01.19	10.30	28.01.19	17.30	
3	Tender Open		29.01.19	10.30	--	--	



**EXECUTIVE ENGINEER
KORBA (CG)**

2/ **For, Commissioner Korba (C.G.)**

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

Name of : CONSTRUCTION OF RCC DRAIN & C.C. ROAD AT NEAR RATHORE MOHALLA, OF WARD NO. 17
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1.1	In all types of soils.								
			1	40.00	1.00	1.00	40.00			
			1	160.00	1.20	1.20	230.40			
			2	50.00	1.00	1.00	100.00			
			1	200.00	1.00	1.00	200.00			
						Total	570.40	cum	185.00	105524.00
						Total	60.00	cum	263.00	15780.00
2	16.3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.								
	3.3	In cement mortar.								
			1X2	20.00	0.20	0.90	7.20			
						Total	7.20	cum	263.00	1893.60
3	16.43	Demolishing cement concrete including disposal of material within 50 metre lead.								
	43.2	1:3:6 or richer mix								
		-RAMESWAR RATHORE HOUSE TO NEAR SHIV RATHORE HOUSE	1	40.00	1.00	0.15	6.00			
		-GARIB DAS HOUSE TO SHIV KUMAR RATHORE HOUSE	1	160.00	1.20	0.15	28.80			
			2	50.00	1.00	0.15	15.00			
			1	200.00	1.00	0.15	30.00			
						Total	79.80	cum	549.00	43810.20
4	1.26	Carriage by mechanical								



SN	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
	HOUSE TO BACK SIDE OF NAYAK HOUSE								
	-KOLLYA SARTHI HOUSE TO CHANDRA KUMAR GAVEL	1	50.00	1.00	0.15	7.50			
		2	50.00	0.15	0.60	9.00			
	-TAMBOLI HOUSE TO MANIRAM HOUSE	1	200.00	1.00	0.15	30.00			
		2	200.00	0.15	0.60	36.00			
	-GUPTA HOUSE TO SHERSINGH HOUSE	1	50.00	1.00	0.15	7.50			
		2	50.00	0.15	0.60	9.00			
		300	1.00	0.80	0.10	24.00			
					Total	268.31	cum	4163.00	1116974.53
7	3.9 Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.								
		40	1.00	0.80	0.10	3.20			
		160X2	0.50	1.20	0.15	28.80			
		15X2	0.50	1.25	0.10	1.87			
		300	1.00	0.80	0.10	24.00			
					Total	57.87	cum	469.00	27141.03
8	3.12 Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:								
	12.1 Thermo-Mechanically treated bars FE 415								
		268.31	60.00			16098.60			
					Total	16098.60	kg	54.50	877373.70
9	2.1 Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at								

REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1.1	all levels, for: foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	2	40.00		0.15	12.00			
		4	40.00		0.60	96.00			
		2	3.50		0.20	1.40			
		4	3.50		0.60	8.40			
		2	160.00		0.20	64.00			
		4	160.00		0.90	576.00			
					Total	757.80	sqm	139.00	105334.20
1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	1	3.50	0.60		2.10			
		1	8.20		0.20	1.64			
					Total	3.74	sqm	235.00	878.90
10 6.6	(PWD ROAD-01.01.2015-6)Provid and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads)								
(iv)	P.C.C. M-30	1	170.00	2.80	0.10	47.60			
	-VIP ROAD TO SHIV RATHORE	1	90.00	2.80	0.10	25.20			
	-VIP ROAD TO GARIB DAS HOUSE	1	200.00	2.80	0.10	56.00			
	-NEAR G.P. KHUTE TO NAYAK	1	85.00	2.80	0.10	23.80			
	-NEAR I.D. VAISHNAO HOUSE TO	1	50.00	2.80	0.10	14.00			
	-KOUSHIYA SARTHI TO CHANDRA	1	200.00	2.80	0.10	56.00			
	-TAMBOLI HOUSE TO MANIRAM	1	50.00	2.80	0.10	14.00			
	-GUPTA HOUSE TO SHERSINGH HOUSE	1	52.00	1.50	0.15	11.70			
	-NEAR KAMLA RATHIA HOUSE TO				Total	248.30	Cum	4350.00	1080105
									353984

As per Estimate Amount Rs.
Say Rs.

Powered By : Estimate Maker Software Pg.

REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
-----	------------------	---	---	---	-----	-----	------	------	--------



Sub Engineer
Nagar Palik Nigam
korba (C.G.)



Asst. Engineer
Nagar Palik Nigam
korba (C.G.)