



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

दर्दी जोन

फा.क्र./687, 686, 688, 685, 697, 690/निर्माण (दर्दी जोन/2025/

कोरबा, दिनांक 09.12.2025

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर शेड्यूल अनुसार एवं आयटम दरों पर मैनुअल निविदा वेबसाईट से डाउनलोड कर मुहर बंद लिफाफे में निविदा आमंत्रित की जाती है :-

- निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने की अंतिम तिथि - दिनांक 30.12.2025 सायंकाल 3:00 बजे तक
- निविदा खुलने की अंतिम तिथि - दिनांक 30.12.2025 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	घरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1.	वार्ड क्र. 48 श्याम नगर दर्दी में नाली का मरम्मत एवं संचारण कार्य भाग-1 (मरम्मत एवं संचारण मद, प्रथम निविदा)	3,98,000/-	4,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	30.12.2025
2.	वार्ड क्र. 60 में नाली का मरम्मत एवं संचारण कार्य (शशि साहू घर से इंदुपाल घर तक) (मरम्मत एवं संचारण मद, प्रथम निविदा)	3,96,520/-	4,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	30.12.2025
3.	वार्ड क्र. 54 अंतर्गत लारी पारा प्राथमिक शाला स्कूल से घमरमुड़ा तालाब तक सी.सी. रोड का मरम्मत कार्य (मरम्मत एवं संचारण मद, प्रथम निविदा)	3,96,000/-	4,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	30.12.2025
4.	वार्ड क्र. 48 श्याम नगर दर्दी में नाली का मरम्मत एवं संचारण कार्य पार्ट-2 (शैना साहू से शिव मिस्त्री एवं सीता सोनी से शिल्पी के घर तक) (मरम्मत एवं संचारण मद, प्रथम निविदा)	3,98,000/-	4,000/-	750/-	Form-A	06 माह	सक्षम श्रेणी	30.12.2025
5.	वार्ड क्र. 59 में सी.सी. रोड के साथ आर.सी.सी. नाली एवं सांस्कृतिक मंच के पास अतिरिक्त सुविधाओं का विस्तार कार्य (पार्श्व मद 2025-26, प्रथम निविदा)	7,00,000/-	5,300/-	750/-	Form-A	04 माह	सक्षम श्रेणी	30.12.2025
6.	वार्ड क्र. 60 दर्दीखार-02 अंतर्गत प्रगति नगर में नाली एवं आर.सी. रोड का निर्माण कार्य (पार्श्व मद 2025-26, प्रथम निविदा)	7,00,000/-	5,300/-	750/-	Form-A	04 माह	सक्षम श्रेणी	30.12.2025

निविदा की शर्तें:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा के दस्तावेज हाथों-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. कॉलोनी रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
- निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाईट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनांक तक समस्त संशोधनों के साथ) आयुक्त नगर पालिक निगम कोरबा के नाम पर देय निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
- निविदा प्रपत्र मुहर बंद लिफाफे में मान्य किया जावेगा जो निम्नानुसार होगा:-
 - प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित निविदा प्रपत्र शुल्क का डीडी, निविदाओं में निविदाकार को फिजिकल दस्तोवज के साथ निविदा सूचना प्रसारित होने के पश्चात् राशि रूपये 100/- के रटाम्प पेपर पर निष्पादित शपथ पत्र जिसमें संबंधित कार्य का नाम एवं कार्य के निविदा क्रमांक अंकित हो प्रेषित करना अनिवार्य होगा एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
 - द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
 - तृतीय लिफाफा में उपरोक्त दोनों लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
- जिन ठेकेदारों द्वारा नगर पालिक निगम के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अगले की जानकारी पिछले 03 वित्तीय वर्षों का आयकर चुकता प्रमाण पत्र, पेन नम्बर, वैध जी.एस.टी. (जीवित) पंजीयन प्रमाण पत्र एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी गवियथ निधि संगठन वर्तमान तक वैधता एवं कर्मचारी राज्य बीमा निगम रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया गया हो वे निविदाकार ही निविदा हेतु पात्र होंगे एवं विस्तृत निविदा आमंत्रण सूचना ठेकेदार के हस्ताक्षर सहित निविदा दस्तावेजों के साथ प्रस्तुत करना अनिवार्य होगा। कर्मचारी गवियथनिधि संगठन ई.पी.एफ.) एवं विभिन्न प्राक्धानों की धारा 1952 के तहत निविदाकार का जीवित पंजीयन प्रमाण पत्र होना आवश्यक है साथ ही निविदा आमंत्रण दिनांक से विगत 03 माह की अवधि में जमा किये गये TRRN Payment Details चालान की प्रति प्रस्तुत करना तथा ऑन लाईन अपरोड करना अनिवार्य होगा।
- कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।


क्रमशः.....02

- निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लेवें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
 10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दरतावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
 11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
 12. शासन के विभिन्न विभागों जैसे- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
 13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
 14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध निविदा शर्तानुसार एवं मेयर इन काउंसिल के निर्णयों के अनुरूप कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
 15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
 16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष हेतु साथ ही मरम्मत एवं संधारण प्रकृति के कार्यों को छोड़कर शेष कार्यों के देयकों से 5 प्रतिशत दर से पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्कुरिटी के रूप में रोकी जावेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापिसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जावेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के सन्तुष्टि के आधार पर भुगतान किया जावेगा।
 17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
 18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि रु. 100/- नान् ज्यूडिशियल स्टॉम्प पेपर पर निष्पादित शपथ पत्र निविदा दरतावेजों के साथ संलग्न करना अनिवार्य होगा।
 19. ईंट से संबंधित निर्माण कार्यों में फ्लाइ ईश ब्रिक्स का उपयोग किया जाना अनिवार्य होगा।
 20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
 21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त, नगर पालिक निगम कोरबा का निर्णय अंतिम एवं सर्वमान्य होगा।
 22. निविदा प्रपत्र From-A के क्लाज नंबर-11 अनुसार एस्केलेशन देय नहीं होगा।
 23. निविदा में सफल निविदाकारों को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मकार मण्डल का पंजीयन का प्रमाण प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
 24. कार्य क्रियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
 25. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गये प्रावधानों का पालन करना अनिवार्य होगा।
 26. ठेकेदार द्वारा संपादित किये गये कार्यों के देयकों का भुगतान बजट आबंटन और राशि उपलब्ध होने पर किया जावेगा।
 27. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
 28. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

प्रतिलिपि :-

1. प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, मंत्रालय अटल नगर नया रायपुर (छ.ग.) को uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।

हस्ताक्षर —
फर्म का नाम —
पता —
मोबाई नंबर —


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

NAME OF WARD- WARD 48

NAME OF WORK - CONSTRUCTION OF RCC DRAIN WITH CC ROAD AND EXPANTION WORK
OF NEW FACILIES NEAR CULTURAL MUNCH WN 59

As per Sor :- Schedule of Rates Public Works Department [PWD BUILDING 01-01-2015], AMD 08

SN	ITEM	No	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	1.2 Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	1	6.1	5.7		34.77			
		1	4.5	2.7		12.15			
						46.92	SQM	7.2	337.824
2	1.1 Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. 1.1.1 In all types of soils.	12	1.2	1.2	1.2	20.74			
		1	24	0.4	0.4	3.78			
		1	14	0.4	0.4	2.30			
		1	50	0.4	0.4	8.00			
						34.82	CUM	185	6440.96
3	1.17 Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.					34.82	CUM	65	2263.04
4	1.18 Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	12	1.2	1.2	0.1	1.73			
		1	30	0.4	0.1	1.18			
		1	14	0.4	0.1	0.58			
		1	6.1	5.7	0.1	3.48			
		1	4.5	2.7	0.1	1.22			
		1	50	2	0.1	10.00			
						18.18	CUM	371	6744.78

	ITEM	No	L	B	H/D	QTY	UNIT	RATE	AMOUNT
	2.1.1 Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	48	1		0.3	14.40			
		24	0.2		0.7	3.36			
		24	0.3		0.7	5.04			
		2	30		0.2	11.84			
		2	14		0.2	5.76			
		2	50		0.1	10.00			
						50.40	SQM	139	7005.6
9	2.1.5 Columns, Pillars, Piers and likes-rectangular or square in shape	24	0.2		2.85	13.68			
		24	0.3		2.85	20.52			
						34.20	SQM	297	10157.4
10	2.1.8 Beams, lintels, cantilevers & walls	2	30		0.2	11.84			
		2	14		0.2	5.76			
		2	41		0.2	16.56			
		2	14		0.2	5.76			
						39.92	SQM	202	8063.84
11	2.1.7 Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	1	6.9	6		41.10			
		1	4.5	3.4		15.30			
						56.40	SQM	235	13254
12	2.1.13 Weather shade, chhajja, Cornices and mouldings	7	1.7	0.7		8.33	SQM	294	2449.02
13	3.4 Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:					19.83	cum	97.5	1933.425
14	7.5 Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: 7.5.4 Cement Mortar 1:6 (1 cement : 6 coarse sand)								
		1	28	0.2	0.5	2.84			
		1	14	0.2	0.5	1.36			
		1	28	0.2	2.85	16.19			
		1	14	0.2	2.85	7.75			
	DEDUCT	2	1.2	0.2	2.1	1.01			
		5	1.2	0.2	1.2	1.44			
		6	0.6	0.2	0.3	0.22			
						25.48	cum	3263	83128.188

ITEM		No	L	B	H/D	QTY	UNIT	RATE	AMOUNT
	6 Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:					21.28	CUM	121	2574.396
16	9.13 Providing and fixing steel door/window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	2	1.2		2.1	5.04			
		5	1.2		1.2	7.20			
						12.24			
						97.92	kg	75	7344
17	9.15 Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.					244.80	kg	67.5	16524
18	9.16 Providing and fixing M.S. frames of doors, windows, ventilators and cupboards joints mitred and welded with 15x3 mm lugs 10cm long embedded in cement concrete blocks 15x10x10cm of grade M-10 or with wooden plugs and screws or with dash fastener or rawl plugs and screws or with fixing clips or with bolts and nuts as required including					288	kg	73.5	21168
19	11.3 Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: 11.3.1 In cement Mortar 1:3 (1 cement : 3 fine sand	1	28		3.9	110.76			
		1	14		3.9	53.04			
	DEDUCT	1				12.24			
						151.56	sqm	113	17126.28
20	11.2 Providing and making 12mm thick cement plaster of mix: 11.2.3 In Cement Mortar 1:5 (1 cement : 5 fine sand)	1	28		3.3	93.72	sqm	96.5	8829.75

ITEM		No	L	B	H/D	QTY	UNIT	RATE	AMOUNT
	DEDUCT	1	14		3.3	91.50			
						12.24			
						172.98			
21	14.41 Lettering with black Japan paint, per cm height.	1				500.00	per letter	0.7	350
22	12.13 Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete. 12.13.1 Size 600x600mm	1	5.7	5.3		30.21			
		1	4.1	2.3		9.43			
						39.64	SQM	1151	45625.64
23	14.56 Providing and applying 2mm thick white cement based Sqm 86.00polymeric Exterior grade Putty_ with minimum 3 coats applied @ 5.4 kg/ 10Sqm as per relevant IS code17545:2021 (Product such as Birla wall care, Asiantrucare,JK wall putty, Berger Bison wall putty) to make the surface					380.94	SQM	86	32760.84
24	14.59 Providing and applying_Polymeric cement primer_on allsurface applied @ 0.80 litres/10 sqm as per relevant I.S. code 15489:1974 (product such as Birla white primacoat/activcoat, Asian Trucare, Dulux interior cement primer, Opus Calista / 110) with all tool tackles and labour etc. complete for the work.					380.94	SQM	29	11047.26

	ITEM	No	L	B	H/D	QTY	UNIT	RATE	AMOUNT
25	14.64 Providing and applying_Premium plastic emulsion paint with roller application minimum three coats applied @ 0.75 lit / 10Sqm up to final finish as per relevant I.S. Code 15489:2013 Type -1 Class D & C (Glossy and Semi Glossy Finish) of required shade (Product such as Asian Apcolite Premium, Dulux Super Cover, Berger Easy Clean ,Nippon Breezee Metex Gold, Opus I-50 / Calista)inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackles and labour etc. complete for the work.(with 3 year Warranty)					212.62	SQM	84	17860.08
26	14.68 Providing and applying on exterior surface with PREMIUM Exterior emulsion paint of required shade to give protective and water proof finish minimum 3 coats applied @ 1.40 lit / 10Sqm up to final finish as per relevant_I.S. Code 15489:2013_Type - 2 ClassD, C (Glossy /Semi Glossy finish) (Product such as Asian Apex ,Dulux Weather Shield Prima E900, Berger Weathercoat Antidust Nerolac Everlas Excel, Nippon Sumo Etra, Opus True flex) inclusive of providing abro tape on edges and articleand cleaning of door, windows, floor and surface as required with all tools tackles and labour etc. complete for the work.(With 3 Year Warranty.)					168.32	SQM	84	14138.88
27	14.71 Providing and applying satin/matt finish Enamel paint mimimum 2 coats in all surface applying @ 0.75 lit/ 10 Sqm up to required finish as per relevent I.S. code 2932: 2013 of (Product such as Asian satin Enamel, Dulux Promise Premium Enamel, Nerolac Synthatic Enamel, Opus Prime enamel) inclusive of providing abro tape on edges and article and cleaning of door, windows,floor and surface as required with all tools tackle and labour etc. complete for the work.					24.48	SQM	133	3255.84

वर्क-आवृत्त
ITEM

श्री वी.आर.उस्ताव कार्यालय अथि


	No	L	B	H/D	QTY	UNIT	RATE	AMOUNT
8 16.3 Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. 16.3.3 In cement mortar	1	14	0.2	2.1	6.048	cum	263	1590.624
30 3.1 Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 3.1.5 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1	54	1.5	0.13	10.125	CUM	4073	41239.125
A								633292.82


RCC DRAIN

SN	ITEM	No	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	1.1 Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	1	48	0.6	0.8	23.04	CUM	185	4262.4
2	1.18 Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	1	48	0.6	0.1	2.88	CUM	371	1068.48
3	3.1 Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 3.1.2 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	1	48	0.6	0.1	2.88	CUM	2659	7657.92
4	3.2 Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 3.2.1 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1	48	0.4	0.1	1.92			
		2	48	0.1	0.4	3.84			
		33	1	0.6	0.05	0.99			
						6.75	CUM	4163	28100.25

ITEM		No	L	B	H/D	QTY	UNIT	RATE	AMOUNT
5	3.1.2 Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: 3.12.1 Thermo-Mechanically treated bars FE 415	27				270.00	kg	54.5	14715
6	2.1 Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	2.1.1 Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	4	48		0.4	76.80			
		33	1.2		0.8	31.68			
						108.48	SQM	139	15078.72
									66620.37
									699913.19
TOTAL A+B									

SAY AS 7.00 LACS RUPEES ONLY


Sub Engineer
Municipal Corporation
Korba (C.G.)


Asst. Engineer
Municipal Corporation
Korba (C.G.)