कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

पं.रविशंकर शुक्ल नगर जोन

फा.क्र./55/निर्माण (पं.रविशंकर शुक्ल नगर जोन)/2022/ कोरबा, दिनांक 12.05.2022

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित **PWD Building SOR 01.01.2015 & PWD Electrical SOR 01.06.2020** से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्युल अनुसार आयटम दरों पर निविदा प्रपत्र **Form-A** में तथा नॉन एस.ओ.आर. दर के शेड्यूल अनुसार ऑयटम दरों पर निविदा प्रपत्र **Form-B** में निम्नलिखित निर्माण कार्य हेतु मैन्युअल निविदा वेबसाईट से डाउनलोड कर त्रि–लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :–

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि – 02.06.2022 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि – 02.06.2022 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रू में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	पं. रविशंकर शुक्ल नगर जोन ऑफिस का मरम्मत एवं नवीनीकरण कार्य। **(मरम्मत एवं संधारण मद)**	**3,98,600/-**	**5,200 /-**	**750/-**	**Form-A & Form-B**	03 माह	सक्षम श्रेणी	**02.06.2022**

निविदा की शर्तेः–

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत् दरों पर दिया जावे सी.एस.आर. के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. नॉन एस.ओ.आर. ऑयटम हेतु निविदा प्रपत्र **Form-B** के अंतर्गत **Annexure-E Schedule of Items** में निर्धारित स्थान पर पृथक–पृथक ऑयटम हेतु दर अंकित करने पर निविदा मान्य होगी।
3. न्यूनतम निविदा राशि का निर्धारण निविदा प्रपत्र **"Form-A"** प्रतिशत् दर पर एवं निविदा प्रपत्र **"Form-B"** आयटम दर प्राप्त निविदा राशियों के योग से प्राप्त न्यूनतम राशि के आधार पर किया जायेगा।
4. निविदा के दस्तावेज हाथो–हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा **आयुक्त, नगर पालिक निगम, आई.टी.आई. चौक साकेत भवन, जिला–कोरबा (छ.ग.) पिन नं.–495677** के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
5. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाईट **www.korbamunicipal.in/uad.cg.gov.in** डाउनलोड किया जाकर नवीन निविदा प्रपत्र **Form - A/B/ABC** (जारी दिनॉक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
6. निविदा प्रपत्र त्रि–लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगाः–
   (अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी (निविदा आमंत्रण पत्र जारी दिनांक के पश्चात् का मान्य) एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
   (ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
   (स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
6. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरूद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नही होगी।
7. निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकरी पिछले वित्तीय वर्ष का **आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन,कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन** एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क्र. 04 के अनुरूप लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
8. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमॉक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।

निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लेवें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।

निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।

11. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
12. ठेकेदार को अपनी दरें शब्दों एवं अंको में लिखना अनिवार्य होगा।
13. शासन के विभिन्न विभागों जैसेः– खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय–समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
14. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
15. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरूद्ध तत् समय में एम.आई. सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
16. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से **15 दिवस** के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
17. सम्पूर्ण किये गये कार्यो के लिये **5 प्रतिशत की दर से सुरक्षा निधि मद में राशि रनिंग देयकों** से 01 वर्ष की अविध हेतु सिक्यूरिटी के रूप में रोकी जावेगी।
18. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत् पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का **1 प्रतिशत उपकर** के रूप में प्रत्येक देयक से कटौती की जावेगी।
19. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यो का विवरण राशि सहित मूल प्रति में वैध शपथ पत्र कंडिका क्र. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
20. ईंट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
21. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नही किया जावेगा।
22. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
23. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
24. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोटः–

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

प्रतिलिपि :– **प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नया रायपुर (छ.ग.) को Uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।**

(ठेकेदार के हस्ताक्षर)

नाम .....

पूर्ण पता .....

.....

मोबाईल नं.– .....

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

Executive Engineer,
Municipal Corporation,
KORBA (Chhattisgarh)

FICE OF THE MUNCIPAL CORPORATION, KORBA (C.G.)

ABSTRACT

NAME OF WORK - Maintenance & Renovation Work of R.S.S. Nagar Zone Office

Part-A

S.N.	Item Work	No.	L	B	H	Qty	Unit	Rate	Amount
1	Removing dry or oil bound distemper by scraping sand papering and preparing the surfaces smooth including necessary repair to scratches etc. complete.								
						2515.82	SQM	5.20	13082.264
2	17.1 Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :								
						127.96	Sqm	132.00	16890.72
3	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.								
						882.71	Sqm	94.50	83415.72
4	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete								
	On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)								
						1633.11	Sqm	37.00	60425.22
5	14.11 Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade.								
	14.11.1 On new work (two or more coats)								
						882.71	Sqm	52.50	46342.07
6	9.13 Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer								
						160.00	kg	75.00	12000.00

	Item Work	No.	L	B	H	Qty	Unit	Rate	Amount
	viding and fixing flush door shutters, ming to IS : 2202 (Part-I), decorative type of block board construction with frame of t class hard wood and well matched teak ply vering with vertical grains or cross bands and face veneers on both faces of shutters excluding hinges.								
	35 mm thick (single leaf)								
						10.08	sqm	2005.00	20210.40
8	8.77 Providing and fixing antique/ SS finished brass butt hinges with antique/ SS polished MS screw complete:								
	100x85x5.50 mm (Heavy Type)								
						48	each	205.00	9840.00
9	8.79 Providing and fixing antique/ SS finished brass sliding door bolt with necessary bolts, nuts and antique/ SS polished MS screw complete:								
	300x16mm								
						20.00	each	496.00	9920.00
10	8.81 Providing and fixing antique/ SS finished brass tower bolts (Barrel type) with antique/ SS polished MS screw complete:								
	250 x10 mm								
						5.00	each	297.00	1485.00
11	Providing and fixing antique/ SS finished brass hanging door stopper with necessary antique/ SS finished MS steel screws complete.								
						5.00	each	49.50	247.50
12	Providing and fixing powder coated M.S. handles with necessary iron screws:								
	125 mm								
						20.00	each	61.50	1230.00
13	14.22 Painting on new work (two or more coats) to give an even shade with:								
	Satin synthetic enamel paint								
						80.00	sqm	55.00	4400.00
14	18.4 Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required :								
	White pedestal type					1.00	each	2882.00	2882.00

	Item Work	No.	L	B	H	Qty	Unit	Rate	Amount
	...iding and fixing vitreous china wash ...sin with C.I. brackets, 32 mm C.P. brass ...waste of standard pattern, including ...ainting of brackets, cutting and making ...good the walls wherever required :								
	White Size 550x450 mm					2.00	each	1430.00	2860.00
16	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.								
	110 mm dia pipe.					30.00	metre	267.00	8010.00
17	Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.								
	Tee/ Tee with door/ Bend 45°/ Bend 90°								
	110 mm					5.00	each	154.00	770.00
	Vent covel								
	110 mm					2.00	each	44.00	88.00
	Access door cap								
	110 mm					2.00	each	59.00	118.00
	"P" trap 110mmx110mm long					2.00	each	227.00	454.00
18	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. CONCEALED WORK including cutting chases and making good the walls etc.,								
	15 mm nominal outer dia .Pipes.					20.00	metre	133.00	2660.00
	32 mm nominal outer dia .Pipes.					15.00	metre	284.00	4260.00
19	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:								
	Bib cock (250 grams)					5.00	each	185.00	925.00
	Stop cock (350 grams)					3.00	each	237.00	711.00
20	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end):								
	32 mm nominal bore.					1.00	each	510.00	510.00
21	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank					1000.00	litre	7.30	7300.00

	Item Work	No.	L	B	H	Qty	Unit	Rate	Amount
22	Constructing brick masonry manhole with well burnt modular clay bricks crushing strength not less than 35kg/cm2 in cement mortar 1:4 (1 cement : 4 coarse sand), R.C.C. top slab with 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), foundation in cement concrete 1:4:8 mix (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) inside plastering 12mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) finished with a floating coat of neat cement complete as per standard design :								
23	Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg)					1.00	each	6703.00	6703.00
								Total	317739.88
		Add For Electrification Work							22241.79
									339981.68
		Part - B							58560.00
								Grand Total	398541.68
								Say as. Rs	398600.00

Sub Engineer
Municipal Corporation
Korba (C.G.)

Asst. Engineer
Municipal Corporation
Korba (C.G.)

OFFICE OF THE MUNCIPAL CORPORATION, KORBA (C.G.)

Detail Estimate

NAME OF WORK - Maintenance & Renovation of Furniture For Zone Office

Part-B

S.N.	Item Work	No.	L	B	H	Qty	Unit	Rate	Amount
1	Supply of Office Table With locker Draw System,Top of Table PlyWood and Finishing With Sunmikea of Best Quality As Per Direction of Engineer in Charge								
	Minimun Size of Table 1500*750*750mm								
		2	1			2	Each		
2	**Supply of Office Chair of Best Quality of Suitable Material With Foam OR Such As Material like As REX Chair As Per Direction of Engineer in Charge**								
		12	1			12	Each		
3	**Supply of Revolving Executive Chair of Best Quality As Per Direction Engineer in Charge**								
		2	1			2	Each		

Sub. Engineer,
Muncipal Corporation
Korba (C.G.)

Asstt. Engineer,
Muncipal Corporation
Korba (C.G.)