



# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

सर्वमंगला नगर जोन

फा.क्र. / 905 से 909 / निर्माण (सर्वमंगला नगर जोन) / 2026 /

कोरबा दिनांक 25.03.2026

## निविदा आमंत्रण सूचना

नगर पालिक निगम कोरबा द्वारा लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्यों हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर मुहरबंद-लिफाफा पद्धति के माध्यम से निविदा आमंत्रित की जाती है :-

- निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 16.04.2026 सायंकाल 3:00 बजे तक
- निविदा खुलने की तिथि से..... - 16.04.2026 सायंकाल 4:30 बजे से

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की तिथि से....
✓	वार्ड क. 63 कुसमुण्डा प्रोजेक्ट एम.एस. में बालक शौचालय का निर्माण कार्य। (समग्र शिक्षा कोरबा)	1,81,000/-	2,000/-	750/-	Form-A	02 माह	सक्षम श्रेणी	16.04.2026
2	वार्ड क. 63 कुसमुण्डा प्रोजेक्ट पी.एस. बालवाड़ी में अतिरिक्त कक्ष का निर्माण कार्य। (पी.एम.श्री योजना)	7,84,266/-	6,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	16.04.2026
3	वार्ड क. 65 आनंद नगर नक्का पंडाल के पास मंच व शेड निर्माण कार्य। (विधायक मद 2025-26)	8,00,000/-	6,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	16.04.2026
4	वार्ड क. 64 इमलीछापर परसामांठा में अमरसाय घर के पास मंच निर्माण कार्य। (विधायक मद 2025-26)	5,00,000/-	3,800/-	750/-	Form-A	02 माह	सक्षम श्रेणी	16.04.2026
5	वार्ड क. 61 खम्हरिया में सतलाल घर के पास सांस्कृतिक मंच निर्माण कार्य। (विधायक मद 2025-26)	5,00,000/-	3,800/-	750/-	Form-A	02 माह	सक्षम श्रेणी	16.04.2026

### निविदा की शर्तें:-

- निविदा दरें प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा के दस्तावेज हाथों-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. कॉलोनी रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेगे।
- निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट [www.korbamunicipal.in/uad.cg.gov.in](http://www.korbamunicipal.in/uad.cg.gov.in) डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
- निविदा प्रपत्र मुहरबंद-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-

(अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निविदा सूचना जारी होने के पश्चात् दिनांक का निर्धारित निविदा प्रपत्र शुल्क का डीडी, शपथ पत्र राशि रु. 100/- के नान ज्युडिशियल स्टाम्प पेपर पर जिसमें संबंधित कार्य का नाम एवं कार्य की निविदा क. अंकित हो निविदाओं में निविदाकार को फिजिकल दस्तावेज के साथ प्रेषित करना अनिवार्य होगा एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. नगद निगम कोष में जमा कर जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।

(ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।

कमशः ....02

- (स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
  6. निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन, शपथ पत्र (मूल प्रति) एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, (प्रपत्र 5-ए) कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क्र. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
  7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
  8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
  9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वयं लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
  10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
  11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
  12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
  13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है, तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
  14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
  15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ. डी.आर./टी.डी.आर. ऑफिस टाईम डिपॉजिट अथवा एन.एस.सी.जो कि आयुक्त नगर पालिक निगम कोरवा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
  16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयकों के साथ 01 वर्ष हेतु साथ ही मरम्मत एवं संधारण प्रवृत्ति के कार्यों को छोड़कर शेष कार्यों से 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्क्यूरिटी के रूप में रोकी जावेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्यपूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने की तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
  17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
  18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित राशि रु. 100/- के नॉन ज्यूडिशियल स्टाम्प पेपर पर निष्पादित शपथ पत्र निविदा दस्तावेजों के साथ संलग्न करना अनिवार्य होगा।
  19. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
  20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
  21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
  22. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि रु. 10.00 लाख या उससे अधिक है उनको प्रत्येक कार्य हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मकार मंडल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक का भुगतान किया जाना संभव नहीं होगा।
  23. कार्य क्रियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
  24. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किए गए प्रावधानों का पालन करना अनिवार्य होगा।
  25. निविदा प्रपत्र Form-I के क्लॉज नम्बर - 11 अनुसार एस्केलेशन देय नहीं होगा।
  26. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
  27. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।
  28. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान वजट आबंटन और राशि उपलब्ध होने पर किया जावेगा।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेगे आयुक्त, नगर पालिक निगम, कोरवा के नाम पर देय हो।

2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।


प्रतिलिपि :- प्रोग्रामर संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नवा रायपुर छ.ग. को [www.uad.cg.gov.in](http://www.uad.cg.gov.in) में अपलोड किये जाने हेतु प्रेषित।

(ठेकेदार के हस्ताक्षर)

नाम .....

पूर्ण पता .....

मोबाईल नं.- .....

  
कार्यपालक अभियंता  
नगर पालिक निगम  
कोरबा (छ.ग.)

# OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

## DETAILED ESTIMATE

Work Name: Construction of trench and fin grade for rawdha paridai anand Nagar bhaktal at ward 65

As per SOR Schedule of rates public works department (P.W.D. BUILDING-01-01-2015)

S. N.	ITEM DESCRIPTION	M	L	B	H/D	QTY	UNIT	RATE	AMOUNT	
1	1.2 Surface dressing of the ground including removing vegetation and making irregularities and inequalities not exceeding 15 cms in depth/height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).									
		1	10.00	9.00				90.00		
	code	30	0.50	0.50	0.50			3.75		
								93.75	1sqm	675.00
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling in all types of soil									
	col	6	1.50	1.50	1.50			20.25		
	wall long	1	24.00	0.50	0.50			6.00		
	step	1	3.00	1.50	0.40			1.80		
	code	30	0.50	0.50	0.50			3.75		
								31.80	Cum	185.00
3	Providing and filling in plinth with sand/ Crusher dust and hard medium under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.									
	col	6	1.50	1.50	0.10			1.35		
	long	1	24.00	0.50	0.10			1.20		
		1	3.00	1.50	0.10			0.45		
	code	30	0.50	0.50	0.10			0.75		
								3.75	Cum	371.00
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.									
	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).									
	col	6	1.50	1.50	0.10			1.35		
		1	24.00	0.40	0.10			0.96		
		1	3.00	1.50	0.10			0.45		
		1	7.00	5.00	0.10			3.50		
	code	30	0.50	0.50	0.10			0.75		
							7.01	Cum	2659.00	18639.59
5	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.									

S. N.	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
	raft								
	below pb	6	1.50	1.50	0.40	5.40			
	col.	6	0.20	0.40	1.10	0.53			
	pb	6	0.20	0.40	3.10	1.49			
	lb	1	24.00	0.20	0.50	2.40			
	sb	1	19.00	0.20	0.20	0.76			
	front both side cant beam	2	24.00	0.20	0.50	4.80			
	latkan b	2	0.50	0.20	0.50	0.10			
	slab	1	5.00	0.20	0.50	0.50			
	chajja	1	7.50	5.50	0.12	4.95			
	flooring	2	4.00	0.50	0.10	0.40			
	pole	1	7.00	5.00	0.10	3.50			
		30	0.50	0.50	0.50	3.75			
						28.58	cum	4163.00	118961.89
6	3.1 Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	3.1.5 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
	plinth prot.	1	7.00	5.00	0.10	3.50			
		1	10.00	5.00	0.15	7.50			
						11.00	cum	4073.00	44803.00
	9.2 Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.								
						800.00	kg	66.00	52800.00
	9.4 Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer.								
	9.3.1 Electric resistance or induction butt welded tubes Grade-250								
	pipe 4 inch					200.00			
						200.00	kg	88.50	17700.00
	10.10 Extra for providing and fixing wind ties of 40x6mm flat iron section.								
	wind tie	40			5.00	200.00			
						200.00	metre	118.00	23600.00


S. N.	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
	10.12 Supply and fixing of polymer pre-coated galvalume profile sheets (PPGL) of approved size, shape and pitch of corrugation, total coated thickness (TCT) 0.60 mm +/- 5%, epoxy primer on both side of the sheet and colour polyester top coat 18-20 microns and 6-7 microns on bottom. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed								
		3	14.00		5.00	210.00			
						210.00	sqm	693.00	145530.00
7	Brick work with modular well burnt (open bhatta) clay bricks of crushing strength not less than 20 kg/sqcm and water absorption not more than 25% in foundation and plinth in:								
	7.5.3 Cement Mortar 1:5 (1 cement : 5 coarse sand)								
	below pb	1	24.00	0.40	0.40	3.84			
	step	1	2.00	1.50	0.40	1.20			
		1	2.00	1.00	0.20	0.40			
		1	2.00	0.50	0.20	0.20			
	above pb	1	19.00	0.20	3.10	11.78			
	parapet wall	1	24.00	0.20	0.30	1.44			
	deduction	2	2.00	0.20	1.20	-0.96			
						17.90	cum	3350.00	59965.00
8	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:								
	Thermo-Mechanically treated bars FE 415								
						2090.00			
						400.00			
						2490.00	kg	54.50	135705.00
9	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.								
	6x4	24	1.50		0.40	14.40			
		6	1.20		1.10	7.92			
	pb	2	24.00		0.50	24.00			
						46.32	sqm	139.00	6438.48
10	Columns, Pillars, Piers and likes- rectangular or square in shape								
	6 above pb	6	1.20		3.10	22.32			
						22.32	sqm	297.00	6629.04

S. N.	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
11	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.								
						22.26			
						22.26	Cum	65.00	1446.90
12	1.19 Providing filling and compacting local earth (from approved source pit) in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
		1	7.00	5.00	0.40	14.00			
						14.00	cum	242.00	3388.00
13	Beams, lintels, cantilevers & walls								
	lb	2	19.00		0.20	7.60			
	s b	2	24.00		0.50	24.00			
	latkan b	1	5.00		0.50	2.50			
						34.10	sqm	202.00	6888.20
14	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in slab								
	lb	1	7.50	5.50		41.25			
	l b	1	19.00	0.20		3.80			
	s b	1	24.00	0.20		4.80			
	latkan beam	1	5.00	0.20		1.00			
						50.85	Sqm	235.00	11949.75
15	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and col.								
	s beam	6	0.20	0.40	3.10	1.49			
	l beam	1	24.00	0.20	0.30	1.44			
	l beam	1	19.00	0.20	0.20	0.76			
	l beam	1	5.00	0.20	0.50	0.50			
	slab	1	7.50	5.50	0.12	4.95			
						9.14	cum	97.50	890.96
16	7.6 Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:								
	parapet wall	1	19.00	0.20	3.10	11.78			
	deduction	1	24.00	0.20	0.40	1.92			
		2	4.00	0.20	1.20	-1.92			
						11.78	cum	121.00	1425.38
17	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)								
	col. Jodna	6	0.60		2.50	9.00			
	beam	2	24.00		0.35	16.80			
	beam	2	19.00		0.20	7.60			
	beam	2	5.00		0.35	3.50			
	slab	1	7.00	5.00		35.00			
		2	7.00		0.50	7.00			
	chajja	2	4.00		0.10	0.80			
						79.70	sqm	87.00	6933.90

S. N.	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
18	Providing and making 12mm thick cement plaster of mix:								
	In Cement mortar 1:5 (1 cement : 5 fine sand)								
		1	19.00	0.20	3.10	11.78			
	deduction	1	24.00	0.20	0.40	1.92			
		2	4.00	0.20	1.20	-1.92			
						11.78	sqm	96.50	1136.77
19	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:								
	In Cement mortar 1:5 (1 cement : 5 fine sand)								
		1	19.00	0.20	3.10	11.78			
	deduction	1	24.00	0.20	0.40	1.92			
		2	4.00	0.20	1.20	-1.92			
						11.78	sqm	113.00	1331.14
20	14.13 Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.								
	6 mm					79.70			
	12 mm					11.78			
	15 mm					11.78			
						103.26	sqm	94.50	9758.07
21	12.13 Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc.								
	12.13.1 Size 600x600mm	1	7.00	5.00		35.00			
	stair	1	2.00	1.50		3.00			
		1	2.00	0.70		1.40			
		1	2.00	0.40		0.80			
		1	24.00	0.10		2.40			
						42.60	sqm	1151.00	49032.60
22	3.13 Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including form work.								
		1	24.00	0.20	0.05	0.24			
						0.24	cum	4237.00	1016.88
23	3.16 Making 50mm thick plinth protection of plain cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded crushed stone aggregate 20mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with sand including finishing the top smooth.								
		1	24.00	1.00		24.00			
						24.00	sqm	273.00	6552.00

S. N.	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
24	2.1.4 Edge of slab, breaks in floor and walls upto 200mm.								
		1	24.00			24.00			
						24.00	mtr	34.00	818.00
	19.44 Cutting holes upto 15x15 cm in R.C.C. floors and roofs for passing drain pipe etc. and repairing the hole after insertion of drain pipe etc. with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including finishing complete so as to make it leak proof.								
						6.00	each	94.50	567.00
25	14.10 Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.								
	14.10.1 On new work (two or more coats)								
						103.26			
						103.26	sqm	44.50	4595.07
27	9.6 Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.								
	9.6.2 In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.								
						180.00			
						180.00	kg	68.00	12240.00
28	14.15 Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:								
	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm) sqm								
						103.26			
						103.26	sqm	56.00	5782.56
29	14.23 Painting on old work (one or more coats) to give an even shade with:								
	14.23.1 Satin synthetic enamel paint								
		4	4.00		1.20	19.20			
						19.20	sqm	55.00	1056.00
30	9.15 Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.								
						190.00			
						190.00	kg	67.50	12825.00
31	Supplying, installation, testing and commissioning of following sizes ceiling fan including wiring the down rods of standard length up to 30 cm with 1.5 sq. mm FR PVC insulated, copper conductor, single core cable, earthing etc. complete as required.								
						4.00			
	1200 mm sweep					4.00	each	1697	6788

S. N.	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
32	Providing and fixing round /hexagonal fan box with 12 mm dia steel bar hook					1.00	each	42	42
33	providing and fixing phenolic laminated sheet cover 180 mmdia 3 mm thick on the fan box etc					1.00	each	56	56.00
34	supplying, installation, testing and commissioning of following sleek LED panel down lighters								
	36 watt size 600x600 mm					2.00	each	2342	4684
35	supplying, installation, testing and commissioning of following sleek LED fitting square shape								
	18/20 watt					4.00	each	868	3472
36	Wiring for light/ fan/ exhaust fan / call bell point with 1.5 sqmm FR PVC insulated stranded copper conductor single core cable in concealed steel conduit, with 5 amp piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with same size cable etc as required.								
	Medium Point					2.00	point	424	848.00
	Long Point					2.00	point	588	1176.00
37	Wiring for light plug point with 3x1.5 sq mm FRLS PVC insulated copper conductor wire in phase neutral and earth in concealed								
	Short Point					1.00	point	442	442
	Medium Point					1.00	point	659	659
38	Wiring for power plug point with 3x1.5 sq mm FRLS PVC insulated copper conductor wire for phase neutral and earth in concealed								
	Medium Point					1.00	point	1171	1171.00
	Long Point					1.00	point	1705	1705.00
39	supplying and drawing UTP 4 pair can 6 LAN wire in existing surface								
						3.00	metre	19.00	57.00
40	Supplying and fixing SP MCB 240 volts C curve suitable for inductive load in the existing MCB DB complete with connection								
	6 amp to 32 amp					3.00	each	148.00	444.00
<b>TOTAL =</b>									<b>799897.42</b>
<b>Say Rs.</b>									<b>800000.00</b>



Sub Engineer  
Municipal Corporation  
Korba (C.G.)



Asstt. Engineer  
Municipal Corporation  
Korba (C.G.)