



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय = साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

मु.का. दूरभाष : 221288, 222672, फ़ैक्स : 07759-221929, पो. बॉक्स नं.-12 पिन कोड - 495677

फ़ाइल/8372/टी.पी. नगर जोन/ 2019/

कोरबा, दिनांक 11.09.2019

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल/ऑनलाईन निविदा वेबसाइट से डाउनलोड कर आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने आवेदन की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र. 02 अंतर्गत तुलसी नगर (साकेत नगर) स्थित सामुदायिक भवन का मरम्मत एवं नवीनीकरण कार्य। (मरम्मत संधारण मद)	4,00,000/-	4,000/-	750/-	03 माह	सक्षम श्रेणी	20.09.2019	24.09.2019	01.10.2019

शर्त:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा प्रपत्र की प्रतियाँ नगर पालिक निगम, साकेत भवन रामपुर, कोरबा कार्यालय से उपरोक्त कार्य हेतु नाम के सममुख अंकित राशि नगद जमा कर उपर लिखित तिथि तक सायं 5:00 बजे तक अवकाश के दिनों को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा मंगाना हो तो रु. 50/- अधिक भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की जिम्मेदारी इस कार्यालय की नहीं होगी।
- निविदा प्रपत्र स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किए जावेगे। निर्धारित तिथि को 3.00 बजे के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं की जावेंगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड)की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय प्रमाण पत्र/पैन नम्बर पत्र एवं जी.एस.टी. पंजीयन प्रमाण पत्र प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र एवं धरोहर राशि सहित निविदा प्रपत्र प्राप्त करने के अंतिम तिथि को 5.30 बजे सायं तक आवेदन प्रस्तुत करना अनिवार्य होगा।
- पूर्ण रूप से भरी निविदा प्रपत्र उपरोक्त तिथि को 15.00 बजे तक प्राप्त की जा सकती है और उसी दिन 16.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहें तो उनके सम्मुख खोले जावेगे।
- सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि देयको से 01 वर्ष की गारंटी के लिये रोकी जावेगी।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ठेके से संबंधित निविदा प्रपत्र उन्हें ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में शपथ पत्र देना अनिवार्य होगा।
- ईट से संबंधित निर्माण कार्यों में फ्लाई ऐश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेंट की खरीदी ठेकेदारों को स्वयं करनी होगी।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधिनस्त अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा प्रपत्र कय कर अथवा वेबसाइट से सीधे डाउनलोड कर निविदा प्रपत्र हेतु निर्धारित राशि की अतिरिक्त डिमांड ड्राफ्ट सहित अपनी भरी हुई निविदा नगर पालिक निगम में रजिस्टर्ड/स्पीड पोस्ट द्वारा अमानत राशि के साथ प्रस्तुत करें।

नोट:- 1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।

2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

कार्यालय अभियन्ता
नगर पालिक निगम
कोरबा (छ.ग.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)

ABSTRACT

Name of Work MAINTENANCE AND RENOVATION OF TULSINAGAR SAMUDAYIK BHAWAN AT WARD NO 02 SAKET NAGAR
As per SOR :SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	3.14	Providing and mixing water proofing material in PCC/ RCC work in the proportion recommended by the manufacturer.	kg	25	43.50	1,087.50
2	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.3	Cement Mortar 1:5 (1 cement : 5 coarse sand)	cum	6.30	3350.00	21,105.00
3	9.2	Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.	Kg	175.00	66.00	11,550.00
4	17.1	Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :				
	1.1	Thickness upto 15mm	sqm	262.50	132.00	34,650.00
5	17.7	Providing and replacing broken vitreous china water closet squatting pan (Indian type) including removing the broken squatting pan and mortar, cutting and making good the walls and floors wherever required:				
	7.3	White Orissa pattern W.C. pan of size 580x440 mm	each	2.00	1888.00	3,776.00
6	16.42	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	cum	4.50	768.00	3,456.00
7	14.10	Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.				
	10.1	On new work (two or more coats)	sqm	240.50	44.50	10,702.25
8	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	485.25	94.50	45,856.12
9	14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:				
	15.1	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	sqm	228.80	56.00	12,812.80
10	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	5.03	4073.00	20,487.19
11	10.63	Providing and fixing 97mm thick Gypsum board partition upto ceiling height consisting of frame work "W" / "U" / "L" sections made of G.I. sheet with zinc coating of grade 120, consisting of floor and ceiling channel 50mm wide having equal flanges of 32mm and 0.55mm thick fixed to the floor and ceiling at the spacing of 610mm centre to centre with	sqm	105.00	758.00	79,590.00

REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	dash fastener of 12.5mm diameter 40mm length and the studs 48mm wide having one flange of 34mm and other flange 36mm and 0.55mm thick fixed vertically within flanges of floor and ceiling channel and placed at a spacing of 610mm centre to centre by 6mm dia bolts and nuts at both ends of partition fixed flush to wall with rawl plugs at spacing of 450mm centre to centre and fixing of boards to either side of frame work by 25mm dry wall screws on studs, floor and ceiling channels at the spacing of 300mm centre to center and 97mm thick Gypsum board which includes one layer of tapered edge 12.5mm thick Gypsum plaster board (conforming I.S. 2095-1982) screw fixed with 25mm screws at 300mm centre to centre to either side, including jointing and finishing to a flush finish with recommended jointing compound, jointing tape, joint finisher and two coats of primer suitable for board as per manufacture's specification and Direction of Engineer-in-charge all complete.				
12	17.2	Providing and replacing broken floor tile with ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including removing the broken tile and mortar, pointing the joints with white cement mixed with matching pigment etc., complete.			
	2.1	Size 300x300mm	sqm	25.00	1151.00
13	19.4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. INTERNAL WORK - EXPOSED ON WALL			
	4.1	15 mm nominal outer dia .Pipes.	metre	18.00	110.00
	4.3	25 mm nominal outer dia .Pipes.	metre	25.00	199.00
	4.4	32 mm nominal outer dia .Pipes.	metre	22.00	271.00

As per Estimate Amount Rs. 286764.86



Sub Engineer
Nagar Palik Nigam
Korba(C.G.)



Asst. Engineer
Nagar palik Nigam
korba(C.G.)