



कायालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

दर्री जोन

फा.क्र./649, 651, 652,656 एवं 659/निर्माण (दर्री जोन)/2025/

कोरबा, दिनांक 16.07.2025

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 & PWD Electrical SOR 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर बंद लिफाफा के माध्यम से आमंत्रित की जाती है :-

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने की अंतिम तिथि - 05.08.2025 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 05.08.2025 सायंकाल 4:30 बजे

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
01	वार्ड क्र. 48 अंतर्गत मेन रोड दर्री सामुदायिक भवन में संधारण एवं नयी सुविधाओं का विस्तार कार्य। (पार्षद निधि, वर्ष 2024-25) (प्रथम निविदा)	7,00,000/-	5,300 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	05.08.2025
02	वार्ड क्र. 55 मिडिल स्कूल सुमेधा में मंच मरम्मत एवं विस्तार कार्य। (पार्षद निधि, वर्ष 2024-25) (प्रथम निविदा)	7,00,000/-	5,300 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	05.08.2025
03	वार्ड क्र. 59 दर्रीखार क्र. 01 के फर्टीलाइजर बस्ती में सामुदायिक भवन एवं मंच का मरम्मत कार्य। (पार्षद मद, वर्ष 2024-25) (प्रथम निविदा)	7,00,000/-	5,300 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	05.08.2025
04	वार्ड क्र. 54 में स्थित स्वामी आत्मानंद स्कूल गोपालपुर में किचन शेड निर्माण व अन्य विस्तार कार्य। (जिला खनिज संस्थान न्यास, वर्ष 2025) (प्रथम निविदा)	5,00,000/-	5,000 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	05.08.2025
05	वार्ड क्र. 58 अंतर्गत सरदार वल्लभ भाई पटेल नगर स्थित सार्वजनिक भवन में मरम्मत एवं संधारण एवं नई व्यवस्था का कार्य। (पार्षद मद, वर्ष 2024-25) (प्रथम निविदा)	7,00,000/-	5,300 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	05.08.2025

निविदा की शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से भेजना होगा अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, आई.टी.आई. चौक साकेत भवन, जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि

क्रमशः.....02

को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।

3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनोंक तक समस्त संशोधनों के साथ) आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
4. निविदा मुहरबंद लिफाफा में मान्य किया जावेगा जो निम्नानुसार होगा:-
 - (अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित निविदा प्रपत्र शुल्क का डीडी, निविदाओं में निविदाकार को फिजिकल दस्तावेज के साथ निविदा सूचना प्रसारित होने के पश्चात् राशि रु. 100/- के स्टॉम्प पर निष्पादित शपथ पत्र जिसमें संबंधित कार्य का नाम एवं कार्य की निविदा क्रमांक अंकित हो प्रेषित करना अनिवार्य होगा एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
 - (ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
 - (स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफे होंगे तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम, कोरबा के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम, कोरबा के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
6. निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी पिछले 03 वित्तीय वर्षों का आय चुकता प्रमाण पत्र, पेन नम्बर, वैद्य जी.एस.टी. (जीवित) पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन अंतर्गत (वर्तमान तक वैद्यता/Form 5A), कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना ठेकेदार के हस्ताक्षर सहित निविदा दस्तावेजों के साथ प्रस्तुत करना अनिवार्य होगा।
7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिका स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध निविदा शर्तानुसार एवं मेयर इन काउंसिल के निर्णयों के अनुरूप कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत की दर से सुरक्षा राशि रनिंग देयकों के साथ 01 वर्ष हेतु साथ ही मरम्मत एवं संधारण प्रकृति के कार्यों को छोड़कर शेष कार्यों के देयकों से 5 प्रतिशत की दर से पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्क्यूरिटी के रूप में रोकी जायेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के

संतुष्टि के आधार पर भुगतान किया जायेगा।

17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित राशि रु. 100/- नॉन ज्यूडिशियल स्टॉम्प पेपर पर निष्पादित शपथ पत्र निविदा दस्तावेजों के साथ संलग्न करना अनिवार्य होगा।
19. ईट से संबंधित निर्माण कार्यों में प्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त, नगर पालिक निगम कोरबा का निर्णय अंतिम एवं सर्वमान्य होगा।
22. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
23. कार्य क्रियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
24. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।
25. ठेकेदार द्वारा संपादित किये गए कार्यों के देयको का भुगतान बजट आबंटन और राशि उपलब्ध होने पर किया जाएगा।
26. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
27. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

प्रतिलिपि :- प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नया रायपुर (छ.ग.) को Uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।

(ठेकेदार के हस्ताक्षर)

नाम

पूर्ण पता

.....

मोबाईल नं.-


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

NAME OF WARD- WARD 43

NAME OF WORK - MAINTENANCE & EXTENSION WORK OF NEW FACILITIES IN NEAR
CULTURAL BUILDING MAIN ROAD DARRI WARD 48

As per Sor :- Schedule of Rates Public Works Department [PWD BUILDING 01-01-2015]

s per Sor :- Schedule of Rates ELECTRICAL Works Department [PWD ELECTRICAL 01-06-2021]

SN	ITEM	No	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	1.2 Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	1	5	3.1		15.50			
		1	4	4		16.00			
						31.50	SQM	7.2	226.8
2	1.1 Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. 1.1.1 In all types of soils.	1	2.5	2.5	2.5	15.63			
		6	1.2	1.2	1.2	10.37			
		1	15.4	0.6	0.6	5.54			
						31.54	CUM	185	5834.345
3	1.17 Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.					22.08	CUM	65	1434.957
4	1.18 Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
		1	2.5	2.5	0.1	0.63			
		6	1.2	1.2	0.1	0.86			
		1	15.4	0.6	0.1	0.92			
		1	5	3.1	0.3	4.65			
						7.06	CUM	371	26

5	3.1 Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 3.1.2 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).								
		1	2.5	2.5	0.1	0.63			
		6	1.2	1.2	0.1	0.86			
		1	15.4	0.6	0.1	0.92			
		1	5	3.1	0.1	1.55			
		1	10.8	0.6	0.1	0.65			
						4.61	CUM	2659	12260.649
6	3.1 Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work 3.1.5 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
		1	2.5	2.5	0.1	0.63			
		1	12	1	0.1	1.20			
		1	10	2	0.1	2.00			
						3.83	CUM	4073	15579.225
	2.1 Providing and fixing form work including centring, shuttering, strutting, staging, prepping bracing etc. complete and including its removal at all levels, for:								
7	2.1.1 Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	24	1		0.3	7.20			
		24	0.2		0.7	3.36			
		2	15.4		0.3	9.24			
						19.80	SQM	139	2752.2
8	2.1.5 Columns, Pillars, Piers and likes-rectangular or square in shape	24	0.2		3.2	15.36	SQM	297	4561.92
9	2.1.8 Beams, lintels, cantilevers & walls	4	15.4		0.2	12.32			
		2	10.8		0.2	4.32			
						16.64	SQM	202	3361.28
10	platform, balconies (plain surfaces) and shelves (cast in situ)	1	5.3	3.4		18.02			
		1	3.1	3.1		9.61			
						27.63	SQM	235	6493.05

11	3.2 Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 3.2.1 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).							
		6	1	1	0.3	1.80		
		6	0.2	0.2	0.7	0.17		
		1	15.4	0.2	0.3	0.92		
		6	0.2	0.2	0.6	0.14		
		1	6.2	3.1	0.1	1.92		
		6	0.2	0.2	2.6	0.62		
		2	15.4	0.2	0.2	1.23		
		1	10.8	0.2	0.2	0.43		
		2	5.3	3.4	0.15	5.41		
		1	3.1	3.1	0.15	1.44		
						14.09	CUM	4163 58671.241
12	3.4 Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:					12.13	cum	97.5 1182.2363
13	3.12 Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: 3.12.1 Thermo-Mechanically treated bars FE 415					1409.35	kg	54.5 76809.575
14	7.5 Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: 7.5.4 Cement Mortar 1:6 (1 cement : 6 coarse sand)							
		1	10.8	0.2	3.1	6.70		
		1	2.5	0.2	3.1	1.55		
		1	25.9	0.2	0.6	3.11		
		1	25.9	0.2	0.6	3.11		
		1	25.9	0.2	2.7	13.99		
		6	5	0.3	0.2	1.80		
	deduct	4	0.8	0.2	2.1	1.34		
		2	1.2	0.2	2.1	1.01		
		6	0.6	0.2	0.3	0.22		
						27.68	cum	3263 90319.84

15	7.6 Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:					18.89	CUM	121	2286.174
16	9.13 Providing and fixing steel door/window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	4	0.8		2.1	6.72			
		2	1.2		2.1	5.04			
						11.76			
						411.60	kg	75	30870
17	approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.					120.00	kg	67.5	8100
18	11.3 Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: 11.3.1 In cement Mortar 1:3 (1 cement : 3 fine sand	2	30.5		3.6	219.60	sqm	113	24814.8
19	11.2 Providing and making 12mm thick cement plaster of mix: 11.2.3 In Cement Mortar 1:5 (1 cement : 5 fine sand)	1	30.5		3	91.50	sqm	96.5	8829.75
20	12.7 Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. 12.7.1 Size upto 200x300mm	1	22		2	44.00	SQM	587	25828

21	12.9 Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. 12.9.1 Size 300x300mm	1	5		3.1	15.50	SQM	692	10726
22	12.57 25mm thick Local RAJIM/ Red Flag stone slab in riser of steps, skirting, dado and pillars laid on 12mm (Average) thick cement mortar 1:4 (1 cement : 4 coarse sand) and joint with grey cement slurry mixed with pigments to match the shade of the slab i/c grinding, rubbing and polishing.	1				35.00	SQM	595	20825
23	14.13 Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	1				300.00	SQM	94.5	28350
24	14.14 Finishing walls with water proofing cement paint of required shade to give an even shade. 14.14.1 On new work (Two or more coats applied @ 3.84 kg/10 sqm)	1				1760.00	SQM	41	72160
25	14.11 Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade. 14.11.1 On new work (two or more coats)	1				1760.00	SQM	52.5	92400
26	14.22 Painting on new work (two or more coats) to give an even shade with: 14.22.1 Satin synthetic enamel paint	1				300.00	SQM	55	16500
27	14.41 Lettering with black Japan paint, per cm height.	1				500.00	per letter	0.7	350
28	14.45 Removing dry or oil bound distemper by scraping sand papering and preparing the surfaces smooth including necessary repair to scratches etc. complete.	1				1000.00	SQM	5.2	5200


29	area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :	1				50.00	SQM	132	6600
30	18.1 Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required : 18.1.2 Coloured Long pattern W.C. pan of size 580 mm					2.00	each	2913	5826
31	18.13 Providing and fixing white vitreous china urinal basin with waste fitting as per IS : 2556, and other couplings in C.P. brass complete:								
	18.13.3 Wall corner type urinal of sizes 340x410x265mm					2.00	each	1659	3318
32	china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required : 18.17.1 White Size 550x450 mm					2.00	each	1430	2860
33	18.29 Providing and fixing 600x450 mm beveled edge 4mm mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.					2.00	each	599	1198
34	18.76 Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete. 18.76.2 110 mm dia pipe.					70.00	m	267	18690


35	18.77 Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 8.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.								
	18.77.1 Tee/ Tee with door/ Bend 45°/ Bend 90° 18.77.1.2 110 mm					6.00	each	154	924
	18.77.2 Double "Y" with or without door 18.77.2.2 110 mm					4.00	each	224	896
	18.77.3 Vent cover 18.77.3.2 110 mm					5.00	each	44	220
	18.77.4 Access door cap 18.77.4.2 110					10.00	each	59	590
	18.77.5 "P" trap 110mmx110mm long					2.00	each	227	454
	18.77.6 Nahani trap 110x75mm					6.00	each	90.5	543
	18.77.8 Plain reducing Tee 110x75mm					4.00	each	129	516
36	19.6 Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This included jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. EXTERNAL WORK								
	19.6.1 15 mm nominal outer dia pipes					60.00	m	91.5	5490
37	nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required								
	19.14.3 Long body bib cock (500 grams)					6.00	each	426	2556
	19.14.7 Angle valve for basin mixer and geyser points (450 grams)					4.00	each	382	1528
	19.14.14 Soap dish plate					6.00	each	163	978
	19.14.16 Towel rail (600mm long x 20mm dia)					6.00	each	338	2028
38	19.42 Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank					1000.00	litter	7.3	7300

39	19.44 Cutting holes upto 15x15 cm in R.C.C. floors and roofs for passing drain pipe etc. and repairing the hole after insertion of drain pipe etc. with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including finishing complete so as to make it leak proof.					2.00	each	94	188
40	Supplying, installation, testing and commissioning of following LED tube light fitting including batten with Electronic Driver Heat sink Capacitor complete with all other accessories on surface/ in false ceiling, including connection, earthing etc complete as per specification and IP20, P.F. should be greater than 0.9. LED chip efficacy ratio ≥ 100 lumens /watt. 6.19.3 18/20 watt {4 feet}					6.00	each	443	2658
41	1.10 Wiring for light plug point with 3x2.5 sq mm FRLS PVC insulated stranded copper conductor wire for phase, neutral and earth in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) along with modular type 6 Amp switch and 3 pin 6 amps socket outlet with modular base and cover plate, suitable size G.I. box, earthing the switch box and socket outlet with same size wire etc. as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)								
	1.10.1 Short Point					2.00	point	442	884
	1.10.2 Medium Point					1.00	point	659	659
	1.10.3 Long Point					1.00	point	922	922
42	1.13 Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, wire in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)								
	1.13.1 3 X 1.5 sq. mm in 20mm conduit					10.00	m	92	920
	1.13.2 3 X 2.5 sq. mm in 20mm conduit					10.00	m	111	1110

5.1 Supplying and fixing following piano type switch, socket, other accessories on the existing switch box/ cover including connections etc. as per specification.								
5.1.15 Batten/ angle holder					10.00	each	38	380
								699583.39

say as rupes 700000.00


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asst. Engineer
 Municipal Corporation
 Korba (C.G.)