

कोरबा दिनांक 02.05.2025

ई-निविदा आमंत्रण सूचना

प्रपत्र Form-A में निविदा आमंत्रित की जाती है:-					
1.	फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि	—	27.05.2025	सायंकाल से 3.00 बजे तक	
2.	निविदा खुलने की अंतिम तिथि	—	27.05.2025	सायंकाल 4.00 बजे से	

क्र.	निविदा खुलने की अंतिम तिथि कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यवाधि	निविदा प्रतिभागी शुल्क (डिमांड ड्राफ्ट)	टेकेदार का वर्ग	निविदा खुलने की तिथि
1	नगर निगम कोरबा अंतर्गत बोरवेल हेतु आर.सी.सी. चैम्बर के साथ नॉन इलेक्ट्रीकल्स क्लोरिनेशन यूनिट का प्रदाय एवं स्थापना कार्य (ग्री.पे.सं.नि.मद)	99.94	75000/-	05 माह	3000/-	वर्ग डी एवं प्रवर श्रेणी	27.05.2025 से

- नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
- जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में पलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
- निविदा दरों अस्मान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा प्रपत्र फार्म —ए की कंडिका 11 Price Adjustment (एस्कलेशन) देय नहीं होगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
- उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
- ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान कार्य विशेष हेतु बजट आबंटन एवं राशि उपलब्ध होने पर किया जाएगा।
- निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
- कार्य क्रियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
- ठेकेदार को निर्माण कार्य के दौरान “निर्माण एवं अपशिष्ट प्रबंधन नियम 2016” में किये गए प्रावधानों का पालन करना अनिवार्य होगा।



- Attested copy of valid GST Registration certificate in state of Chhattisgarh/valid Commercial Tax/ GST clearance certificate.
23. Annexure-13 Affidavit. (Hard and Soft copy)
24. PAN CARD.
25. Valid Bank Solvency (15% of Tender Value).
26. Experience (As per mentioned in serial no. 22 & 23) upto the tendered category of work and amount. Failing of required Document/Certificate as mentioned in this section can be '**Liabe to Rejection**' and no further financial bid will be opened.
27. Technical Person Detail
28. Tools & Machinery
29. Earth work will be paid by taking initial and final levels by an auto level. The Contractor must have an auto level.
30. Neither any material advance nor mobilization advance will be given to the contractor.
31. No escalation will be paid to the contractor, the work must be completed within the given time.
32. PWD Manual will be followed.
33. The right to approve or reject the tender at any stage of tender processing shall vest to the CMO Nagar Panchayat Sitapur.
34. All the clause of **Tender form "A"** attached with the tender will be followed.
35. **If there is any amendment in the tender it will be published online only.**
36. If any document as required will not received as per desired then tenderer will be treated not qualified and tender will not be opened further.
37. **Documentary evidence for NSF chemicals and approved technology from appropriate Government should be submitted at the time of tender submission.**
38. **Bidder or manufacturer must have experience in supplying and installation of a minimum 10 Nos of Non-Electric Online Chlorination System in Borewell/Handpump in last 03 year. Documentary evidence for that such as purchase order copies, Work Experience Certificate or manufacturer undertakings must be submitted at the time of bid submission.**


अधीक्षण अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

प्रतिलिपि—

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		02.05.2025	15.30	02.05.2025	15.30	Release Tender
2		Bid Submission	02.05.2025	15.30	26.05.2025	17.30	
3		Physical Document Submission	02.05.2025	15.30	27.05.2025	15.00	
4	Tender Open		27.05.2025	16.00	--	--	


20/5/25
SUPERINTENDING ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION KORBA (C.G)


ESTIMATE


Sub. - Installataion of NON Electrical Chlorination unit on Borewell with R.C.C. Chamber Work at Nagar Nigam Area

ESTIMATE HAS BEEN PREPARED AS PER SOR PWD (BUILDING WORKS) W.E.F. 01.01.2015 & PHED SOR amendment 07-2022-2023

Sno	Code	Particulars	No	L	B	H/D	Qty	Unit	Rate	Amount
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1.1.1	In all types of soil								
		Footing	100	1.30	1.30	1.00	169.00			
						Total	169.00	cum	185.00	31265.0
3	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
		In Footing								
		Footing	100	1.20	1.20	0.10	14.40			
						Total	14.40	cum	371.00	5342.0
4	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	3.1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).								
		Below Column Footing								
			100	1.20	1.20	0.10	14.40			
						Total	14.40	cum	2970.00	42768.0
5		Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:								
		bottom mesh cum wall bars	100	16	2.63	0.62	2608.96			
		slab bars mb and db	100	16	1.308	0.62	1297.536			
						Total	3906.50	kg	54.50	212904.0

8		Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	2.1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.								
		wall	400	0.92		0.90	331.20			
						Total	331.20	sqm	139.00	46037.0
7	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	3.2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
		bottom raft	100	1.1	1.1	0.1	12.1			
		wall								
			400	0.80	0.80	0.15	38.40			
		top slab	200	0.50	0.50	0.20	10.00			
						Total	60.50	cum	4163.00	251862
8	26.18	Supply and installation of cartridge based non-electric, online, automatic water chlorination system for piped water supply scheme, using solid chlorination agent, and should be safe and simple to handle.online chlorination unit-2500000 lit water chlorination capacity of single cartridge at 1 ppm dosing price including transpotation upto site with installation (as per phed sor usor amendment 07-2022-2023)					100.00	unit	68964.00	6896400
	26.19	Supply and installation online chlorination cartridge (as per sor phed usor amendment 07-2022-2023)					387.00	unit	6479.00	2507373
Total										9993950.53
Say Rs.										9994000.00


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asstt. Engineer
 Municipal Corporation
 Korba (C.G.)


 Executive Engineer
 Municipal Corporation
 Korba (C.G.)