

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क्र./निर्माण /2018/427

सिस्टम टेन्डर नं. 48906

कोरबा, दिनांक 25/01/2019


चतुर्थ ई-निविदा आमंत्रण सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई-निविदा आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क 05 में शेड का निर्माण एवं आंगनबाड़ी का मरम्मत, सीमेंट कांक्रिट सड़क एवं नाली का मरम्मत कार्य।	700000.00	5500/-	03 माह	वर्ग डी एवं प्रवर श्रेणी	13.02.2019 से

शर्त:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पैन नम्बर, **जी.एस.टी.** पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का **स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।**
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- निविदा उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रदाय नहीं किया जावेगा।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में **निविदा जारी तिथि से 10 दिवस पूर्व का नोटरी सत्यापित** शपथपत्र देना अनिवार्य होगा।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का **1 प्रतिशत उपकर** के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेंट की खरीदी ठेकेदारों को स्वयं करनी होगी।
- प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से **15 दिवस** के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।


कार्यपालन अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		25.01.19	12.00	25.01.19	12.00	Release Tender
2		Bid Submission	25.01.19	12.00	12.02.19	17.30	
3	Tender Open		13.02.19	10.30	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
 For, Commissioner Korba (C.G.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)

DETAILED ESTIMATE

Name of Work : CONSTRUCTION OF SHADE & MAINTANCE OF AGAN BADI CEMENT CONCRETE ROAD & DRAIN AT WARD NO 05 (PARASAD NIDHI)

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1.1	In all types of soils.								
		-COLUMN	6	1.50	1.50	1.50	20.25			
			4	2.55	0.60	0.60	3.67			
			2	3.40	0.60	0.60	2.44			
		-DRAIN	1	30.00	1.00	0.60	18.00			
						Total	44.36	cum	185.00	8206.60
2	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
		-COLUMN	6	1.50	1.50	0.10	1.35			
		-UNDER PLINTH	4	2.55	0.60	0.10	0.61			
			2	3.40	0.60	0.10	0.40			
		-FLOOR	1	6.00	4.00	0.10	2.40			
						Total	4.76	cum	371.00	1765.96
3	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form								

SN	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
	work.								
1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).								
		6	1.50	1.50	0.10	1.35			
		4	2.55	0.60	0.10	0.61			
		2	3.40	0.60	0.10	0.40			
		1	4.00	6.00	0.10	2.40			
	-FLORR	1	6.00	4.00	0.10	2.40			
	-DRAIN	1	30.00	1.00	0.10	3.00			
					Total	10.16	cum	2970.00	30175.20
4	2.1 Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.								
	-COLUMN FOOTING	6X4	1.20	0.50		14.40			
	-COLUMN	6X4	0.30	1.20		8.64			
	-P BEAM	2X2	4.00	0.30		4.80			
		2X2	6.00	0.30		7.20			
	-DRAIN	2X2	30.00	0.40		48.00			
					Total	83.04	sqm	139.00	11542.56
1.5	Columns, Pillars, Piers and likes- rectangular or square in shape								
	-COLUMN	6X4	0.30	3.00		21.60			
					Total	21.60	sqm	297.00	6415.20
1.8	Beams, lintels, cantilevers & walls								
	-L BEAM	2X2	4.00	0.20		3.20			
		2X2	6.00	0.20		4.80			
	-CHUJJA	4	1.80	0.60		4.32			
		4X2	0.60	0.10		0.48			
	-FRONT CHUJJA	1	4.00	0.60		2.40			
		2	0.60	0.10		0.12			

SN	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
9	7.5 Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				Total	2.40	cum	469.00	1125.60
	5.4 Cement Mortar 1:6 (1 cement : 6 coarse sand)								
		4	2.55	0.40	0.20	0.81			
		2	3.40	0.40	0.20	0.54			
		4	2.55	0.30	0.40	1.22			
		2	3.40	0.30	0.40	0.81			
	-S/S	2	2.55	0.20	3.00	3.06			
		1	3.40	0.20	3.00	2.04			
					Total	8.48	cum	3263.00	27670.24
10	7.6 Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:								
		2	2.55	0.20	3.00	3.06			
		1	3.40	0.20	3.00	2.04			
					Total	5.10	cum	121.00	617.10
11	1.17 Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.								
		1	5.40	7.40	0.70	27.97			
					Total	27.97	cum	65.00	1818.05
12	9.6 Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.								

SN	R	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
			2	4.00	1.20		9.60			
		-AGAN BADI	1	3.00	2.00		6.00			
			1	6.00	3.00		18.00			
			1	2.90	2.35		6.81			
			1	2.35	2.30		5.40			
			2	2.00	0.60		2.40			
			1	3.60	0.60		2.16			
			2	6.00	0.60		7.20			
			2	3.00	0.60		3.60			
			2	2.90	0.60		3.48			
			2	2.35	0.60		2.82			
			2	2.35	0.60		2.82			
			2	2.30	0.60		2.76			
						Total	111.45	sqm	1151.00	128278.95
15	12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.								
	7.1	Size upto 200x300mm								
		-TOILET	2	2.00	1.20		4.80			
			2	1.15	1.20		2.76			
						Total	7.56	sqm	587.00	4437.72
16	12.9	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.								
	9.1	Size 300x300mm								
		-TOILET	1	2.00	1.15		2.30			

SN	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
					Total	2.30	sqm	692.00	1591.60
17	16.3 Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.								
	3.3 In cement mortar.								
	-DRAIN	2	30.00	0.20	0.50	6.00			
					Total	6.00	cum	263.00	1578.00
18	16.37 Dismantling lime/ cement plaster or skirting at any height raking out joints and cleaning the surface for plaster including disposal of rubbish within 50 metres lead.								
		1	6.00	4.00		24.00			
	-AGAN BADI					50.00			
					Total	74.00	sqm	11.00	814.00
19	16.43 Demolishing cement concrete including disposal of material within 50 metre lead.								
	43.1 1:4:8 or leaner mix								
	-DRAIN	1	30.00	0.70	0.10	2.10			
					Total	2.10	cum	329.00	690.90
20	11.1 Providing and making 6mm thick cement plaster of mix:								
	1.2 In Cement mortar 1:4 (1 cement : 4 fine sand)								
		1	5.40	3.40		18.36			
		2	5.20	0.10		1.04			
		2	7.20	0.10		1.44			
					Total	20.84	sqm	87.00	1813.08
21	11.2 Providing and making 12mm thick cement plaster of mix:								
	2.4 In Cement Mortar 1:6 (1 cement : 6 fine sand)								
		2	5.40	3.00		32.40			
		2	3.40	3.00		20.40			

SN	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
	washing of surface etc. complete with:								
16.1	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)								
						52.80			
						100.75			
					Total	153.55	sqm	74.50	11439.48
26	14.14 Finishing walls with water proofing cement paint of required shade to give an even shade.								
14.1	On new work (Two or more coats applied @ 3.84 kg/10 sqm)								
						52.80			
					Total	52.80	sqm	41.00	2164.80
27	14.22 Painting on new work (two or more coats) to give an even shade with:								
22.1	Satin synthetic enamel paint								
	-C G GATE	2	3.40	2.40		16.32			
	-AGAN BADI					30.50			
					Total	46.82	sqm	55.00	2575.10

As per Estimate Amount Rs.	
Say Rs.	

Sub Engineer
Nagar Palik Nigam
Korba (C.G.)

E.E. Engineer
Nagar Palik Nigam
Korba (C.G.)