कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क./762/विद्युत/2019

कोरबा, दिनांक 06.06.2019

सिस्टम टेंडर क्र. 51703
ई– प्रोक्यूरमेंट निविदा आमंत्रण सूचना

नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग, छ.रा.वि.मंडल, एवं छत्तीसगढ़ अनुज्ञापन मंडल (विद्युत) में उचित श्रेणी में विद्युतीकरण कार्य हेतु पंजीकृत/लाईसेंसी ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियंता, लोक निर्माण विभाग (विद्युत) रायपुर द्वारा दिनांक 01.07.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान प्रतिशत दरों पर ई–प्रोक्यूरमेंट (E-Tendering) के माध्यम से निविदा आमंत्रित की जाती है :–

क	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रू में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र 14 पम्प हाउस में हाई मास्ट लाईट प्रदाय एवं स्थापना कार्य	5,73,579/–	4350/–	02 माह	वर्ग अ– श्रेणी	29.06.2019 से ..

शर्तें :–

1. निविदा दरे प्रचलित एस.ओ. आर. से कम या अधिक प्रतिशत दरों पर दिया जावे एस. ओ. आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा ई–प्रोक्यूरमेंट (E-Tendering) के माध्यम से ही स्वीकार किए जावेगे। निर्धारित तिथि को 3.00 बजे के पश्चात् प्राप्त निविदाऐं स्वीकार नही की जावेंगीं।
3. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य ना किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरूद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नही होगी।
4. निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर चुकता प्रमाण पत्र/पेन नम्बर एवं जी.एस.टी. का पंजीयन प्रमाण पत्र, कर्मचारी भविष्य निधि एवं कर्मचारी राज्य बीमा निगम सबंधी प्रमाण पत्र, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र एवं धरोहर राशि को स्केन कापी ऑनलाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
5. निविदा उन्ही ठेकेदारो को दिया जायेगा जिन्हे इस प्रकार के कार्यों का अनुभव हो।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत् पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ठेके से संबंधित निविदा उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन रायपुर एवं कर्मचारी राज्य बीमा निगम से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
8. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यो का विवरण राशि सहित मूल प्रति में शपथ पत्र देना अनिवार्य होगा।
9. सम्पूर्ण किए गए कार्यों के लिए प्रत्येक चल देयको में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 05 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में प्रत्येक चल देयको में से 03 वर्ष रोकी जावेगी।
10. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
11. ठेकेदारों को उपरोक्त कार्य हेतु लगे विद्युत श्रमिकों का भुगतान बैंक के माध्यम से किया जाना अनिवार्य होगा।
12. निविदा प्रपत्र अहस्तांतरणीय होगा। एवं सशर्त निविदाओं पर विचार नही किया जावेगा।
13. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त निर्णय अंतिम एवं सर्वमान्य होगा।
14. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
15. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम ,कोरबा के साकेत भवन स्थित विद्युत शाखा से प्राप्त किये जा सकते है

कार्यपालन अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		06.06.19	13.00	06.06.19	10.30	Release Tender
2		Bid Submission	06.06.19	10.30	28.06.19	17.30	
3	Tender Open		29.06.19	10.30	--	--	

EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)
ABSTRACT

Name of Work :SUPPLY & INSTALATION OF HIGH MAST LIGHT AT PUMP HOUSE WARD NO. 14
:SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD ELECTRICAL-01-08-2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	21.18	Supplying erection testing and commissioning of hot dipped galvanised (single dip 86 micron) 16 metre High mast pole on existing RCC foundation with all accessories and equipments, detailed as below to withstand wind pressure upto 180km/hr and minimum following specifications: a) HM shaft made of not more than 2 sections of suitable lengths with telescopic stressfit joints between sections without any circumpherencial welding, sheet thickness 4mm top and bottom sections, nominal dia 460mm on bottom and 150 mm on top, base flange 25mm thick 670mm dia, PCD of foundation bolts 650mm. b) Double drum winch for lowering & raising of lantern carriage on high mast with operatable with power tool/ manual handle attachment with a torque limiting device for safe locking of carriage. c) Raising/lowering type lantern carriage designed to carry specified nos of luminaries, control gear box, junction box. d) Top pulley assemble with weather proof cover. e) 3 Nos suitable length and size stainless steel wire ropes (minimum 6mm dia and 7/19 construction) for lowering & raising of lantern carriage. f) Suitable size and length multicore flexible copper power trailing cable (minimum 3 core 4 sqmm) g) Hinged service door in base section h) Base plate earthing terminal. i) Suitable arrangement for supply distribution with termination of suitable size underground cable in high mast. j) Lightning conductor finial made of 25mm dia 300 mm long G.I. tube having single prong. k) Anchor plate of size 840x840x6mm, tem-plates 3mm thick, GI foundation bolts 8 Nos of 30 mm dia 850 mm long (EN 8 Grade) along with nuts washers etc. (RCC foundation and luminaries will be paid separately)	Each	1.00	231425.00	231,425.00
2	21.12	Designing and providing suitable RCC foundation in Cement Concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) for 3 mere to 12 metre high GI octagonal pole including steel reinforcement (minimum 90kg per cum), form work, embeding 2 nos 50mm dia PVC pipe for cable entry in each foundation, excavation disposal of surplus soil and curing etc. as required.	cum	3.50	4906.00	17,171.00
3	17.1	Supplying and laying following sizes one number PVC insulated/ XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.				
	23	4 x 16 sq. mm.	Metre	100.00	291.00	29,100.00
4	17.15	Supplying and laying following sizes one number PVC insulated, PVC sheathed, unarmoured, copper conductor controle cable of 1.1 KV grade on				

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		surface/ existing cable tray with 1 mm thick GI saddle as required.				
	3	6 x 1.5 sq. mm	Metre	50.00	158.00	7,900.00
	9.19	Fabrication, supply, installation, testing and commissioning of cubicle type compartmentalized wall/ floor mounted power cum control panel board of specified size and following depth made out of not less than 2 mm thick CRCA MS sheet with suitable size compartments for bus bars, switchgears and necessary cutouts for voltmeters, ammeters etc as per specifications including powder coating painting but without busbars, switchgears and other accessories etc complete as required. (Only face area is to be measured)				
	2	Above 300 mm and upto 450 mm deep	sqm	1.50	7167.00	10,750.50
6	11.19	Supplying and fixing following rating, 415 volts, FOUR POLES, ISOLATOR in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
	3	100 amps	Each	1.00	679.00	679.00
7	8.30	Supplying, installation, testing and commissioning of following 230/250 volts LED street light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 5 KV surge protection on pole bracket complete as required and furnishing 2 Yrs Guarantee certificate from manufacturer.				
	6	135 watt	Each	12.00	22823.00	273,876.00
8	14.1	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. (but without charcoal or coke and salt) as required.	Set	1.00	2472.00	2,472.00
9	14.19	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ concealed conduit/ submain wiring/ cable as required.	Metre	10.00	20.50	205.00
					As per Estimate Amount Rs.	**573578.50**

Sub Engineer
Nagar Palik Nigam
Korba(C.G.)

Asst. Engineer
Nagar palik Nigam
korba(C.G.)

Executive. Engineer
Nagar palik Nigam
korba(C.G.)