

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. 482/2025

सिस्टम टेंडर नं. 181369

कोरबा दिनांक 09.12.2025

द्वितीय ई-निविदा आमंत्रण सूचना


कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 एवं विद्युत हेतु 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र Form-A में निविदा आमंत्रित की जाती है:-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि - 30.12.2025 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 30.12.2025 सायंकाल 4.00 बजे से

क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (डिमांड ड्राफ्ट)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क्र. 17 ढोड़ोपारा (नेहरू नगर भैसखटाल मेन रोड) काली मंदिर के पास मंगल भवन निर्माण कार्य (प्रभारी मंत्री मद)	20.00	15000/-	05 माह	750/-	वर्ग डी एवं प्रवर श्रेणी	30.12.2025 से

शर्तें:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशिप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र, पैन नम्बर, वैध जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमाण्ड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं निर्धारित प्रारूप में शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा के पते पर भेजना होगा। निर्धारित तिथि को सायं 03:00 बजे के पश्चात् फिजिकल सबमिशन लिफाफा स्वीकार नहीं किया जायेगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निर्धारित प्रारूप में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफारमेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी। सुरक्षा राशि एवं परफारमेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन (वर्तमान तक वैधता) एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे एवं कर्मचारी भविष्य निधि संगठन (ई.पी.एफ.) एवं विभिन्न प्रावधानों को धारा 1952 के तहत निविदाकार का जीवित पंजीयन होना आवश्यक है साथ ही निविदा आमंत्रण दिनांक से विगत तीन माह की अवधि में जमा किये गये TRRN Payment Detail चालान की प्रति प्रस्तुत करना तथा ऑनलाईन अपलोड किया जाना अनिवार्य होगा।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ईट से संबंधित निर्माण कार्यों में प्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वयं निरस्त मानी जावेगी।
10. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. निविदा प्रपत्र फार्म -ए की कंडिका 11 Price Adjustment (एस्कलेशन) देय नहीं होगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान कार्य विशेष हेतु बजट आबंटन एवं राशि उपलब्ध होने पर किया जाएगा।
16. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
17. कार्य क्रियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
18. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।



कार्यालय - अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		09.12.2025	15.30	09.12.2025	15.30	Release Tender
2		Bid Submission	09.12.2025	15.30	26.12.2025	17.30	
3		Physical Document Submission	09.12.2025	15.30	30.12.2025	15.00	
4	Tender Open		30.12.2025	16.00	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)
DETAILED ESTIMATE

Name of work:- Construction of ^{Mangal} Samudayik bhawan Infront of manas nagar ward no 17 c.s.e.b. 1dhodhipara, Near Kali Temple, nehrunagan.

As per SOR: Schedule of rates public works department (PWD BUILDING-01-01-2015)

S.N.	SOR Ref.	ITEM DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area).								
	1	In all types of soil								
			24	1.50	1.50	1.50	81.00			
		below plinth	4	8.20	0.60	0.60	11.81			
			5	9.10	0.60	0.60	16.38			
			1	6.20	0.60	0.60	2.23			
			2	1.80	0.60	0.60	1.30			
		septic tank	1	4.60	3.60	2.40	39.74			
		pipe line drainage	1	50.00	0.60	0.60	18.00			
						Total =	170.46	Cum	185.00	31535.10
2	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and								
	1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.								
		raft c1	24	4	1.2	0.30	34.56			
		footing	24	4	0.600	0.40	23.04			
		column below plinth	24	1	1.000	1.20	28.80			
		plinth beam	4	2	14.400	0.30	34.56			
			5	2	13.800	0.30	41.40			
			1	2	6.200	0.30	3.72			
			2	2	1.800	0.30	2.16			
						Total =	168.24	Sqm	139.00	23385.36
	5	Columns, Pillars, Piers and likes rectangular or square in shape								
			24	1		3.6	86.4			
			15	1		0.9	13.5			
						Total =	99.90	sqm	297.00	29670.30
	7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in								
		SLAB	1	14.40	13.80		198.72			
			2	14.40	0.125		3.60			
			2	13.80	0.125		3.45			
		chajja	12	1.80	0.600		12.96			
			12	3.00	0.100		3.60			
		PORCH	1	13.80	0.600		8.28			
						Total =	230.61	sqm	235.00	54193.35


		Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in											
		3 Cement Mortar 1:5 (1 cement : 5 coarse sand)											
			4	12.90	0.20	0.60	6.19						
			5	13.00	0.20	0.60	7.80						
			1	6.20	0.20	0.60	0.74						
			2	6.20	0.20	0.60	1.49						
			2	1.80	0.20	0.60	0.43						
			1	6.20	0.30	1.00	1.86						
							Total =	18.52	Cum	3350.00		62028.60	
		super structure 7.5.3+7.6											
			2	12.90	0.20	2.90	14.96						
			2	13.00	0.20	2.90	15.08						
			2	6.20	0.20	2.90	7.19						
			2	4.00	0.20	2.90	4.64						
			2	1.80	0.20	2.90	2.09						
			2	14.40	0.20	0.90	5.18						
			2	13.80	0.20	0.90	4.97						
			12	1.50	0.20	1.20	-4.32						
			1	3.50	0.20	2.10	-1.47						
							Total =	48.33	Cum	3471.00		167739.55	
								48.33	Cum	121			
10	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation											
12	12.12	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1											
		1 Size 600x600mm	1	14.40	13.80		198.72						
							Total =	198.72	sqm	963.00		191367.36	
13	12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed											
		2 Size above 200x300mm											
			4	3.00		1.50	18.00						
			4	1.80		1.50	10.80						
			1	6.00		0.60	3.60						
							Total =	32.40	sqm	587.00		19018.80	


		Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with								
	1	Size 300x300mm	2	3.00	1.80		10.80			
							Total = 10.80	sqm	692.00	7473.60
15	12.46	15 mm thick Table rubbed polished Granite stone slab in risers and treads of steps skirting dado and pillars laid on 12mm (Average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry including rubbing and polishing etc. complete (single stone is to be used for risers and treads of steps and width of stone for skirting and dado shall be equal								
	1	Granite stone grey/pink					2.40			
			8	1.00	0.30		1.20			
			8	1.00	0.15					
							Total = 3.60	sqm	1869.00	6726.40
16	9.15	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a								
		door	12	28.00			336.00			
		ventilator	2	12.00			24.00			
							Total = 360.00	Kg	67.50	24300.00
17	9.11	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with 38mm steel pulleys complete with bolts, nuts, locking arrangement stoppers, handles including								
			1	3.50			2.10	7.35		
							Total = 7.35	sqm	3330.00	24475.50
18	11.1	Providing and making 6mm thick cement plaster of mix								
	2	In Cement mortar 1:4 (1 cement : 4 fine sand)								
			1	13.8	14.40		199.72			
			12	1.80	0.60		12.96			
			2	13.80	1.10		30.36			
			1	6.20	1.10		6.82			
			2	9.80	0.90		17.64			

		Providing and making 12mm thick cement plaster of mix in Cement Mortar 1:6 (1 cement : 6 fine sand)			Total =	200.60	sqm	07.00	23185.50
			2	14.40	0.60	187.20			
			2	13.80	0.60	170.40			
					Total =	300.00	sqm	01.50	32543.90
20	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick in Cement Mortar 1:6 (1 cement : 6 fine sand)							
			2	14.00	3.30	92.40			
			2	14.40	3.30	95.04			
			6	6.20	3.30	122.76			
			4	4.00	3.30	52.80			
			4	3.50	3.30	46.20			
			4	1.80	3.30	23.76			
						392.96			
					Total =	392.96	sqm	107.00	42045.72
21	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI.				976.06			
					Total =	926.06	sqm	94.50	87512.67
						659.46	sqm	44.50	29345.97
22	14.1	Wall painting with acrylic premium emulsion (plastic) paint of required							
		1 On new work (Two or more				392.96	sqm	41.00	16111.35
23	14.14	Finishing walls with water proofing cement paint of required shade to give an even							
		1 On new work (Two or more							
24	8.13	Providing and fixing flush door shutters, conforming to IS 2202 (Part 1), interior grade, commercial type, core of block board construction with frame of first class hard wood and well matched commercial ply veneering							
		2 35 mm. thick (single leaf)+8.15 single leaf							
			4	1.00	2.10	8.40			
					Total =	8.40	sqm	1370.00	11508.00
25	8.137	Providing and fixing stainless steel sliding door bolts with 16mm rod, 2.5mm thick flap, necessary stainless steel nuts bolts and							
		2 250mm				15.00			

		Providing and fixing stainless steel door latch with 12mm rod, 2.5mm thick flap, necessary stainless				Total =	15.00	nos	228.00	3420.00
		2 250mm					15.00			
						Total =	15.00	nos	85.00	1275.00
27	8.139	Providing and fixing stainless steel tower bolts (Barrel type) with necessary stainless steel				Total =	34.00	nos	57.50	1955.00
		3 150 x10mm								
28	8.141	Providing and fixing Stainless steel "D" shape door handles made of 10mm dia rod with necessary				Total =	34.00	nos	49.50	1683.00
		8.141.2 150 mm								
29	8.58	Providing and fixing bright finished brass butt hinges with brass polished				Total =	51.00	nos	245.00	12495.00
		8.58.1 125x85x5.50 mm (Heavy								
30	8.143	Providing and fixing stainless steel hanging door stopper with necessary				Total =	15.00	nos	47.00	705.00
		1 Single					6.00	nos	362.00	2172.00
32	9.28	Providing and fixing 27.5cm long wire spring for rolling shutters.					6.00	nos	423.00	2538.00
33	9.30	Providing and fixing ball bearing for rolling shutters.								
34	9.29	Providing and fixing M.S. sheet top cover for rolling shutter					4.00			
		3 0.90mm thick	1	4.00			3.60			
			1	3.60						
						Total =	7.60	nos	399.00	3032.40
35	14.22	Painting on new work (two or more coats) to give an even								
		2 Premium synthetic enamel paint	5	1.20	2.10		12.60			
			17.5	1.00	2.10		36.75			
			10	0.75	2.10		15.75			
			24	1.80	1.20		51.84			
			1	3.00	1.20		3.60			
			5	0.90	0.60		2.70			
						Total =	123.24	sqm	47.00	5792.28
36	9.47	Providing and fixing aluminium work for doors, windows, ventilators and partitions made out of extruded aluminium standard sections (mainsection with minimum 1.5mm thickness) conforming to IS: 733, IS: 1285mitred and jointed mechanically including aluminium cleats, neoprene weather stripping gasket beveled edge beading, screws duly fixed in wall/ floor with fixing clips or hold fasteners or bolts and nuts as required aluminium sections shall be anodized transparent or								

					120.00	kg	331.00	39720.00
					110.00	kg	336.00	37180.00
38	9.51	For shutter of doors, windows & ventilators including providing and making provision for fixing of fitting wherever required including the cost of PVC/ neoprene gasket required						
		Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete. (Cost of aluminium snap beading shall						
		9.51.2 With float glass panes of 5 mm thickness						
		12	1.50	1.20				
					21.60			
					Total =	21.60	sqm	709.00
								15292.80
								TOTAL= 1875803.91
								Sanitation 63056.00
								electrical 61000.00
								Total= 1999859.91
								Say rs.= 2000000.00



 Asst. Engineer
 Municipal Corporation
 Korba (C.G.)



 Sub Engineer
 Municipal Corporation
 Korba (C.G.)

PART - B - SANITAION WORK

		Providing and fixing on wall face UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal								
	1	75 mm dia pipe.	1	12.00			12.00	metre	182.00	2184.00
	2	110 mm dia pipe.	1	20.00			20.00	metre	267.00	5340.00
2	18.1	Providing and fixing water closet squatting pan (Indian type W.C. pan),100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the					2	each	2899.00	5798.00
	3	White Orissa pattern W.C. pan of size 580x440 mm					2	each	2899.00	5798.00
3	18.17	Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the								
	1	White Size 550x450 mm								
6	18.77	Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving								
	1	Tee/ Tee with door/ Bend 45°/ Bend 90°					2.00	each	113.00	226.00
	1	75 mm					4.00	each	154.00	616.00
	2	110 mm								
	3	Vent covel					4.00	each	34.00	136.00
	1	75 mm					6.00	each	90.50	543.00
	6	Nahani trap 110x75mm								
7	19.4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent								
	1	15 mm nominal outer dia .Pipes.					50.00	metre	110.00	5500.00
	3	25 mm nominal outer dia .Pipes.					35.00	metre	199.00	6965.00
	4	32 mm nominal outer dia .Pipes.					40.00	metre	271.00	10840.00

		Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:							
	1	Bib cock (250 grams)							
10	19.14	Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required:				6.00	each	185.00	1110.00
	6	Stop cock (concealed) (600)							
	4	Pillar Cock (400 grams)				2.00	each	494.00	988.00
10	19.15	Providing and fixing stainless steel drain jali of approved				2.00	each	398.00	796.00
						4.00	each	51.00	204.00
12	19.51	Constructing masonry Chamber 60x60x75 cm, inside with modular well burnt clay bricks of 35 kg/cm ² in cement mortar 1:4 (1 cement : 4 coarse sand) for fire hydrants, with C.I. surface box 350x350 mm top and 165 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) necessary excavation foundation concrete 1:5:10 (1 cement : 5 fine sand:10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand)				2.00	each	4356.00	8712.00
14	18.42	Providing and placing on terrace (at all levels) polyethylene water storage tank ISI marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without				1000.00	litre	7.30	7300.00
								TOTAL =	63056.00
								Say Rs.=	


 Asst. Engineer
 Municipal Corporation
 Korba (C.G.)


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)