



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

फा.क्र./01/निर्माण कोसाबाड़ी जोन/2021-22

कोरबा, दिनांक 27.01.2022

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित **PWD Building SOR 01.01.2015 & PWD Electrical SOR 01.08.2015** से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :-

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि — 17.02.2022 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि — 17.02.2022 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	महिला समूहों को बाजार उपलब्ध कराने हेतु मल्टीएक्टिविटी सेन्टर के रूप में विकसित करने हेतु लाईवलीहुड कॉलेज के पास पूर्व निर्मित भवन ब्लॉक का मरम्मत एवं संधारण कार्य। (DMF)	16,00,000/-	12,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	17.02.2022

निविदा की शर्तें:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज हाथो-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. कॉलोनी रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र **Form - A/B/ABC** (जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
4. निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-
 - (अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. नगद निगम कोष में जमा कर जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
 - (ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
 - (स) तृतीय लिफाफा में उपरोक्त दोनों लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
6. निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कडिका क्र. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।

हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना कर्मोंक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा। निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।

9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष साथ ही 5 प्रतिशत पृथक (मरम्मत एवं संचारण मद को छोड़कर) से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्यूरिटी के रूप में रोकी जावेगी।
17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र कंडिका क. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
19. ईट से संबंधित निर्माण कार्यों में पलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
23. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।


प्रतिलिपि :- प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नवा रायपुर (छ.ग.) को Uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।

(ठेकेदार के हस्ताक्षर)

नाम

पूर्ण पता

मोबाईल नं.-


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA

DETAIL ETIMATE

Line of Work: PAINTING WORK OF EXISTING BUILDING BLOCKS AT LIVELYHOOD COLLEGE CAMPUS WN 33 KORBA (C.G.)

per SOR :SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015][PWD ELECCTRICAL-01.08.2015]

[illegible]

Sub. Engineer
Municipal Corporation
Korba (C.G.)

Asstt. Engineer
Municipal Corporation
Korba (C.G.)

Exe. Engineer
Municipal Corporation
Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA

DETAIL ETIMATE

ne of Work: ELECTRICAL WORK OF EXISTING BUILDING BLOCKS AT LIVELYHOOD COLLEGE CAMPUS WN 33 KORBA (C.G.)

per SOR :SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD ELECCTRICAL-01.08.2015]

REF	ITEM DESCRIPTION	UNIT	NO	L	B	H	QTY	RATE	AMOUNT
1.1	Wiring for light/ fan/ exhaust fan / call bell point with 1.5 sqmm FR PVC insulated stranded copper conductor single core cable in concealed steel conduit, with 5 amp piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with same size cable etc as required.								
1.1	Short Point	Point	3		1.00		3.00	297.00	891.00
1.2	Medium Point	Point	2		1.00		2.00	528.00	1056.00
1.3	Long Point	Point	8		1.00		8.00	806.00	6448.00
8.11	Supplying, installation, testing and commissioning of following T-5 fluorescent fitting (luminaries) complete with electronic ballast but without fluorescent lamp, on ceiling/ wall surface, earthing the fitting etc. as required.								
11.1	Single box type with decorative end caps	Each	1	15.00			15.00	635.00	9525.00
8.1	Supplying, installation, testing and commissioning of following sizes ceiling fan including wiring the down rods of standard length up to 30 cm with 1.5 sq. mm FR PVC insulated, copper conductor, single core cable, earthing etc. complete as required.								
1.3	1400 mm sweep	Each	1	6.00			6.00	1637.00	9822.00
6.4 Elec	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc								
4.1	75mmX75mm (1/2 Module)	Each	1	20.00			20.00	88.00	1760.00
4.4	200mmX75mm (6 Module)	Each	1	3.00			3.00	161.00	483.00
4.6	200mmX150mm (12 Module)	Each	1	2.00			2.00	273.00	546.00
4.7	16 Module	Each	1	6.00			6.00	373.00	2238.00
7.4 Elec	Supplying and fixing following modular switch, socket, other accessories on the existing modular plate & switch box including connections but excluding modular plate etc. as required.								
4.1	5/6 amps one way switch	Each	1	36.0			36.00	68.00	2448.00
4.3	Bell push	Each	1	2.00			2.00	81.50	163.00
4.5	3 pin 5/6 amp socket outlet	Each	1	20.00			20.00	87.50	1750.00
4.6	6 pin 15/16 amp socket outlet	Each	1	20.00			20.00	126.00	2520.00
4.8	Fan regulator (two module size) electronic stepped type moving all rounds	Each	1	12.00			12.00	203.00	2436.00
4.15	25/32 amp A.C. Starter switch	Each	1	5.00			5.00	233.00	1165.00
4.17	Ceiling rose 3 pin 5 amp	Each	1	20.00			20.00	36.00	720.00
8.30	Supplying, installation, testing and commissioning of following 230/250 volts LED street light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 5 KV surge protection on pole bracket complete as required and furnishing 2 Yrs Guarantee certificate from manufacturer.								
30.1	25-30 watt	Each	1	1.0			1.00	4890.00	4890.00
3.10	Wiring for light plug point with 2x2.5 sq mm FR PVC insulated stranded copper conductor cable in concealed PVC conduit along with modular type 6 Amp switch and 3 pin 6 amps socket outlet with modular base and cover plate, suitable size G.I. box, earthing the switch box and socket outlet with same size cable etc. as required.								
10.1	Short Point	Point	3		1.00		3.00	458.00	1374.00

N	REF	ITEM DESCRIPTION	UNIT	NO	L	B	H	QTY	RATE	AMOUNT
	10.2	Medium Point	Point	2		1.00		2.00	701.00	1402.00
	10.3	Long Point	Point	8		1.00		8.00	988.00	7904.00
	3.13	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FR PVC insulated copper conductor, single core cable in concealed PVC conduit as required.								
	13.1	3 X 1.5 sq. mm in 20mm conduit	M	1		10.00		10.00	83.50	835.00
	13.2	3 X 2.5 sq. mm in 20mm conduit	M	1		10.00		10.00	104.00	1040.00
	13.3	6 X 2.5 sq. mm in 25mm conduit	M	1		20.00		20.00	172.00	3440.00
	3.15	Supplying and fixing of following sizes PVC conduit along with accessories in concealed complete as required.								
	15.1	20 mm	M	1		20.00		20.00	40.00	800.00
	15.2	25 mm	M	1		20.00		20.00	46.50	930.00
										66586.00
										FOR 6 NOS BLOCK 399516.00
										TOTAL 399516.00
										SAY RS: 400000.00


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asstt. Engineer
 Municipal Corporation
 Korba (C.G.)


 Exe. Engineer
 Municipal Corporation
 Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA

DETAIL ETIMATE

Scope of Work: CONSTRUCTION OF ENTRY GATE AND BALANCE WORK OF EXISTING BUILDING BLOCKS AT LIVELYHOOD COLLEGE CAMPUS WN 33 KORBA

per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015][PWD ELECTRICAL-01.08.2015]

[illegible]

OFFICE OF THE MUNICIPAL CORPORATION, KORBA

DETAILED ESTIMATE

Work: WATER SUPPLY REPAIR & MAINTANANCE WORK & ROOF TREATMENT WORK OF EXISTING BUILDING BLOCKS AT LIVELYHOOD COLLEGE CAMPUS WN 33 KORBA

per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015][PWD ELECTRICAL-01.08.2015]

REF	ITEM DESCRIPTION	UNIT	NO	L	B	H	QTY	RATE	AMOUNT
17.2	Providing and replacing broken floor tile with ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including removing the broken tile and mortar, pointing the joints with white cement mixed with matching pigment etc., complete.								
2.1	Size 300x300mm		2	2.00	3.00		12.00		
		Sqm					12.00	1151.00	13812.00
17.7	Providing and replacing broken vitreous china water closet squatting pan (Indian type) including removing the broken squatting pan and mortar, cutting and making good the walls and floors wherever required:								
7.3	White Orissa pattern W.C. pan of size 580x440 mm		1		4.00		4.00		
		Each					4.00	1888.00	7552.00
18.17	Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :								
17.1	White Size 550x450 mm		2				2.00	1430.00	2860.00
		Each							
19.14	Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required:								
14.2	Long nose bib cock (500 grams)		3				3.00	455.00	1365.00
		Each							
12.65	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm								
65.20	Pigment Coloured (rubber mould) precast interlock concrete blocks		3				3.00	632.00	1896.00
		Sqm							
18.40	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required :								
4.3	White wall hung type								
		Each					2.00	4415.00	8830.00
18.7	Providing and fixing 10 litre capacity P.V.C. low level flushing cistern conforming to IS : 7231, with all fittings and fixtures complete.								
7.1	White wall hung type								
			1.00						
		Each					1.00	729.00	729.00
19.14	Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required:								
14.1	Bib cock (400 grams)						12.00	382.00	4584.00
14.2	Long nose bib cock (500 grams)						18.00	455.00	8190.00
14.10	Wall mixer with elegant knob (1400 grams)						3.00	1787.00	5361.00
14.11	Hand shower set with flexible extension pipe						8.00	754.00	6032.00
14.13	Toilet paper holder						4.00	248.00	992.00
14.14	Soap dish plate						2.00	163.00	326.00
14.15	Shower rose (revolving type) (150mm)						2.00	269.00	538.00
14.16	Towel rail (600mm long x 20mm dia)						6.00	338.00	2028.00
14.18	Wall mixer (telephonic type) with crutch arrangement for hand shower (1400gms)						1.00	1764.00	1764.00
		Each							

N	REF	ITEM DESCRIPTION	UNIT	NO	L	B	H	QTY	RATE	AMOUNT
9	17.1	Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :								
	1.1	Thickness upto 15mm								
				60	1.00	2.50		150.00		
			Sqm					150.00	132.00	19800.00
0	9.47	Providing and fixing aluminium work for doors, windows, ventilators and partitions made out of extruded aluminium standard sections (main section with minimum 1.5mm thickness) conforming to IS: 733, IS: 1285 mitred and jointed mechanically including aluminium cleats, neoprene weather stripping gasket beveled edge beading, screws duly fixed in wall/ floor with fixing clips or hold fasteners or bolts and nuts as required aluminium sections shall be anodized transparent or dyed to approved shade according to IS: 1868, minimum anodic coating shall be of grade AC-15. (Glazing to be paid for separately).								
	47.2	For shutter of doors, windows & ventilators including providing and making provision for fixing of fitting wherever required including the cost of PVC/ neoprene gasket required (Fittings shall be paid for separately).								
			Kg					250.00	338.00	84500.00
11	17.9	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 metres lead :								
	9.1	Door chowkhats		1		6.00		6.00		
			Each					6.00	441.00	2646.00
12	17.11	Making the opening in brick masonry for door/ window/ clerestory window including dismantling in floor or walls by cutting masonry and making good the damages to walls, flooring and jambs complete to match existing surface i/c disposal of malba/ rubbish to the nearest municipal dumping ground.								
				6	2.00		0.50	6.00		
			Sqm					6.00	272.00	1632.00
13	17.12	Renewing glass panes, with putty and nails wherever necessary:								
	12.1	Float glass panes of thickness 4 mm								
				48	1.20		1.50	86.40		
			Sqm					86.40	524.00	45273.60
14	8.12	Providing and fixing flush door shutters, conforming to IS : 2202 (Part-I), decorative type core of block board construction with frame of first class hard wood and well matched teak ply veneering with vertical grains or cross bands and face veneers on both faces of shutters excluding hinges.								
	12.1	40 mm. thick (single leaf)	sqm	4	1.20		2.10	10.08	2467.00	24867.36
15	8.150	Providing and fixing factory made 25mm thick PVC flush door shutters made out of a one piece Multi chamber extruded PVC section of the size of 762mm X 25mm or less as per requirement with an average wall thickness of 1mm ± 0.3mm. PVC foam end cap of size 23x10mm are provided on both vertical edges to ensure the overall thickness of 25mm. An M.S. tube having dimensions 19mm x 19mm is inserted along the hinge side of the door. Core of the door shutter should be filled with High Density Polyurethane foam. The Top & Bottom edges of the shutter are covered with an end-cap of the size 25mm X 11mm. Door shutter shall be reinforced with special polymeric reinforcements as per manufactures' specification.								
			sqm	16	1.20		2.10	40.32	2583.00	104146.56
5	8.58	Providing and fixing bright finished brass butt hinges with brass polished MS screws complete:								
	8.1	125x85x5.50 mm (Heavy Type)	Each	15	4.00			60.00	245.00	14700.00
7	8.61	Providing and fixing brass door latch with brass polished MS screws complete;								
	61.1	300x16x5 mm	Each	20	2.00			40.00	398.00	15920.00

N	REF	ITEM DESCRIPTION	UNIT	NO	L	B	H	QTY	RATE	AMOUNT
B	8.67	Providing and fixing of bright finished brass mortise latch and lock 100x65mm with six levers and a pair of lever handles with brass polished MS screws etc. complete.								
			Each	20	1.00			20.00	971.00	19420.00
										399764.52
								TOTAL		399764.52
								SAY RS:		400000.00

Exe. Engineer
Municipal Corporation
Korba (C.G.)