

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. 79/ निर्माण/2022

सिस्टम टेंडर नं 105293

कोरबा दिनांक 22.07.2022


ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदाएं आमंत्रित की जाती है :-

| क्र. | कार्य का नाम | प्राक्कलन राशि (लाख में) | धरोहर राशि | कार्यावधि | ठेकेदार का वर्ग | निविदा खुलने की तिथि |
|------|--|-----------------------------|------------|-----------|--------------------------|----------------------|
| 1 | आर.एस.एस. नगर जोन अंतर्गत दादर रोड से मानिकपुर मुक्ति धाम तक सी सी रोड निर्माण कार्य | 85.00 | 64000/- | 04 माह | वर्ग डी एवं प्रवर श्रेणी | 17.08.2022 से |

शर्त:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पैन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र स्कैन कर अपलोड करना अनिवार्य होगा।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में फ्लाइ एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।


कार्यालय अभियंता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

| Seq. No. | Nagar Nigam Stage | Contractor Stage | Start | | Expiry | | Remarks |
|-------------|-------------------|------------------|------------|-------|------------|-------|----------------|
| | | | Date | Time | Date | Time | |
| 1 | Release Tender | | 22.07.2022 | 17.30 | 22.07.2022 | 17.30 | Release Tender |
| 2 | | Bid Submission | 22.07.2022 | 17.30 | 16.08.2022 | 17.30 | |
| 3 | Tender Open | | 17.08.2022 | 10.30 | -- | -- | |


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA

ABSTRACT


Name of Work: Construction of CC Road From Dadar Road To Manikpur MuktiDham Under Ward No.30


per SOR SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015] & [PWD ROAD-01.01.2015]


| SN | ITEM DESCRIPTION | N | L | B | H/D | QTY | UNIT | RATE | AMOUNT |
|----|--|---|---|---|-----|---------|------|---------|------------|
| 1 | Scarifying existing bituminous surface to a depth of 50 mm (Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material with in all lifts and lead up to 1000 meters) as per clause 305.4.3. | | | | | 1920.00 | Sqm | 23.00 | 44160.00 |
| 2 | Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300. | | | | | 1300.00 | CUM | 95.00 | 123500.00 |
| 3 | Removal of Unserviceable Soil with Disposal up to 1000 meters including loading and unloading. | | | | | 1108.00 | CUM | 85.00 | 94180.00 |
| 4 | Construction of embankment with Material Obtained from Borrow Pits/Borrow Area (Construction of embankment with approved material/selected soil having C.B.R.>5 (unless specified otherwise in the contract) obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300-2) | | | | | 1794.00 | CUM | 223.00 | 400062.00 |
| 6 | Construction of granular sub-base by providing graded Material, , carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface watering, rolling and compacting with vibratory power roller at OMC to achieve the desired density, complete as per clause 401 Plant mix method (with Mechanically crushed stone only) For Lower Sub-base with | | | | | | | | |
| | Total | | | | | 907.80 | Cum | 1423.00 | 1291799.40 |
| | Dry Lean Cement Concrete Sub-base as per IRC:SP-49 (Construction of dry lean cement concrete Sub-base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 26.5 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing as per clause 601.) | | | | | | | | |

| DESCRIPTION | N | L | B | H/D | QTY | UNIT | RATE | AMOUNT |
|--|---|---------|------|------|---------|------|---------|------------|
| Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. | | | | | 546.44 | Cum | 2332.00 | 1274298.08 |
| P.C.C M-30 | | | | | | | | |
| | 1 | 438.00 | 3.60 | 0.20 | 315.36 | | | |
| | 1 | 1000.00 | 3.60 | 0.20 | 720.00 | | | |
| | | | | | 1035.36 | Cum | 4350.00 | 4503816.00 |
| 2 Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. | | | | | | | | |
| In all types of soil | | | | | | | | |
| | | | | | 197.40 | Cum | 185.00 | 36519.00 |
| 3 Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M. | | | | | 130.40 | Cum | 65.00 | 8476.00 |
| 4 Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete. | | | | | | | | |
| | | | | | 10.05 | Cum | 371.00 | 3728.55 |
| 5 Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. | | | | | | | | |
| i 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size). | | | | | 10.05 | Cum | 2970.00 | 29848.50 |
| ii 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | | | | | 9.87 | Cum | 4073.00 | 40215.17 |
| 6 Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work. | | | | | | | | |
| 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | | | | | 60.74 | Cum | 4163.00 | 252852.29 |
| 7 Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: | | | | | | | | |
| Thermo-Mechanically treated bars | | | | | 5952.32 | kg | 54.50 | 324401.66 |

| DESCRIPTION | N | L | B | H/D | QTY | UNIT | RATE | AMOUNT |
|---|---|---|---|-----|--------|------|--------|------------|
| ing and fixing formwork including centering, shuttering, ing, staging, propping bracing etc. complete and including removal at all levels, for: | | | | | | | | |
| oundings, footings, base of columns and plinth beam in any shape and size. | | | | | | | | |
| | | | | | 17.40 | Sqm | 139.00 | 2418.60 |
| Wall of any thickness including attached pilasters, buttresses etc. in super structure. | | | | | | | | |
| | | | | | 212.88 | Sqm | 228.00 | 48536.64 |
| Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ) | | | | | | | | |
| | | | | | 58.30 | Sqm | 235.00 | 13700.50 |
| 12 Carriage by mechanical transport upto 5 km lead: | | | | | | | | |
| Earth | | | | | 67.00 | Cum | 111.00 | 7437.00 |
| | | | | | | | | |
| Total Ammount | | | | | | | | 8499949.39 |
| SAY AS | | | | | | | | 8500000.00 |


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asst. Engineer
 Municipal Corporation
 Korba (C.G.)


 Executive Engineer
 Municipal Corporation
 Korba (C.G.)