



# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

कोसाबाड़ी जोन

फा.क्र./101, 102, 103 एवं 104/निर्माण (कोसा.)/2019

कोरबा, दिनांक 14.11.2019

## निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित **PWD Building SOR 01.01.2015 & PWD Electrical SOR 01.08.2015** से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :-

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 13.12.2019 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 13.12.2019 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	घरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र. 19 अंतर्गत विभिन्न पण्डाल मैदानों में कांक्रीटीकरण के कार्य एवं चबुतरा निर्माण कार्य। (पार्षद निधि, वर्ष 2019-20)	7,00,000/-	5500 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	13.12.2019
2	वार्ड क्र. 20 काशीनगर में सामुदायिक भवन का विकास कार्य। (पार्षद निधि, वर्ष 2019-20)	7,00,000/-	5500 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	13.12.2019
3	वार्ड क्र. 18 अंतर्गत विभिन्न स्थानों में आर.सी.सी. नाली का निर्माण कार्य। (पार्षद निधि, वर्ष 2019-20)	7,00,000/-	5500 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	13.12.2019
4	वार्ड क्र. 29 पोड़ीबहार स्थित राठौर मोहल्ला में आर.सी.सी. नाली एवं सी.सी. रोड मरम्मत आदि का कार्य। (पार्षद निधि, वर्ष 2019-20)	7,00,000/-	5500 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	13.12.2019

### निविदा की शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज हाथों-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. कॉलोनी रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट [www.korbamunicipal.in/uad.cg.gov.in](http://www.korbamunicipal.in/uad.cg.gov.in) डाउनलोड किया जाकर नवीन निविदा प्रपत्र **Form - A/B/ABC** (जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।

क्रमशः.....02



4. निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-

(अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी (निविदा आमंत्रण पत्र जारी दिनांक के पश्चात् का मान्य) एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. नगद निगम कोष में जमा कर जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।

(ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।

(स) तृतीय लिफाफा में उपरोक्त दोनों लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।

5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
6. निविदा हेतु इच्छुक ठेकेदारों को तकनीकी दस्तावेज यथा पिछले 03 वित्तीय वर्ष का आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन साथ ही विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क्र. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई. सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस, टाईम डिपॉजिट अथवा एन.एस. सी. जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्यूरिटी के रूप में रोकी जावेगी।
17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।



18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र कंडिका क्र. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
19. ईट से संबंधित निर्माण कार्यों में पलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
23. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

(ठेकेदार के हस्ताक्षर)

नाम .....

पूर्ण पता .....

.....

मोबाईल नं.- .....

कार्यपालक अभियंता  
नगर पालिक निगम  
कोरबा (छ.ग.)



**OFFICE OF THE NAGAR PALIK NIGAM, KORBA ( C.G.)**  
**ABSTRACT**


Name of Work **CONSTRUCTION AND EXTENSION OF CUMMUNITY MUNCH AT KASHINAGAR W.N20**  
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]


S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	17.19	185.00	3,180.15
2	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	1.37	371.00	508.27
3	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	cum	1.37	2970.00	4,068.90
4	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)	cum	25.05	3263.00	81,738.15
5	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	21.31	121.00	2,578.51
6	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	25.5	4163.00	106,156.50
7	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	16.32	139.00	2,268.48
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape	sqm	56	297.00	16,632.00
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	59.92	235.00	14,081.20
	1.8	Beams, lintels, cantilevers & walls	sqm	19.44	202.00	3,926.88
	1.13	Weather shade, chhajja, Cornices and mouldings	sqm	2.88	294.00	846.72
	1.15	Stair cases of all types excluding spiral and folded plate type, including risers and landings	sqm	19.2	230.00	4,416.00
8	11.1	Providing and making 6mm thick cement plaster of mix:				
	1.2	In Cement mortar 1:4 (1 cement : 4 fine sand)	sqm	71.38	87.00	6,210.06
9	11.2	Providing and making 12mm thick cement plaster of mix:				
	2.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	101.36	91.50	9,274.44
10	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				




S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	3.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	106.64	107.00	11,410.48
11	14.9	Distempering with acrylic washable distemper to give an even shade.				
	9.1	On new work (Two or more coats)	sqm	180	38.00	6,840.00
12	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alitek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	294	94.50	27,783.00
13	14.14	Finishing walls with water proofing cement paint of required shade to give an even shade.				
	14.1	On new work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm	115	41.00	4,715.00
14	12.13	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.				
	13.1	Size 600x600mm	sqm	112.66	1151.00	129,671.66
15	9.6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.				
	6.1	In stringers, treads, landings etc. of stair cases including use of chequered plate wherever required, all complete.	Kg	250.00	70.00	17,500.00
	6.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	Kg	150.00	68.00	10,200.00
16	9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	kg	450.00	75.00	33,750.00
17	14.22	Painting on new work (two or more coats) to give an even shade with:				
	22.1	Satin synthetic enamel paint	sqm	20.88	55.00	1,148.40
18	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.2	Thermo-Mechanically treated bars FE 500D	kg	2522	54.50	137,449.00

As per Estimate Amount Rs. 636353.80

  
Sub Engineer  
Nagar Palik Nigam  
Korba(C.G.)

  
Asst. Engineer  
Nagar palik Nigam  
korba(C.G.)

  
Executive Engineer  
Nagar palik Nigam  
korba(C.G.)



**OFFICE OF THE NAGAR PALIK NIGAM, KORBA ( C.G.)**  
**ABSTRACT**

Name of Work electrification work for community hall at kashinagar w.n20


As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]


S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	3.1	Wiring for light/ fan/ exhaust fan / call bell point with 1.5 sqmm FR PVC insulated stranded copper conductor single core cable in concealed PVC conduit, with 5 amp piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with same size cable etc as required.				
	1	Short Point	Point	10.00	236.00	2,360.00
	2	Medium Point	Point	4.00	388.00	1,552.00
	3	Long Point	Point	4.00	553.00	2,212.00
2	3.3	Extra for providing and fixing light plug point on board in concealed PVC conduit point wiring with piano type 3 pin 5 amp socket outlet and 5 amp switch including cost of phenolic laminated sheet and M.S. box etc. as required.etc. as required.	Point	2.00	95.00	190.00
3	3.4	Wiring for light plug point with 2x2.5 sq mm FR PVC insulated stranded copper conductor cable in concealed PVC conduit along with piano type 6 amp switch and 3 pin 6 amps socket outlet with suitable size M.S. box, phenolic laminated sheet, earthing the switch box and socket outlet with same size cable etc. as required.				
	2	Medium Point	Point	2.00	582.00	1,164.00
	3	Long Point	Point	2.00	869.00	1,738.00
4	3.13	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FR PVC insulated copper conductor, single core cable in concealed PVC conduit as required.				
	1	3 X 1.5 sq. mm in 20mm conduit	Metre	80.00	83.50	6,680.00
5	7.4	Supplying and fixing following modular switch, socket, other accessories on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
	17	Ceiling rose 3 pin 5 amp	Each	18.00	36.00	648.00
	19	Batten/ angle holder	Each	10.00	41.00	410.00
	5	3 pin 5/6 amp socket outlet	Each	4.00	87.50	350.00
	6	6 pin 15/16 amp socket outlet	Each	4.00	126.00	504.00
	8	Fan regulator (two module size) electronic stepped type moving all rounds	Each	4.00	203.00	812.00
6	8.1	Supplying, installation, testing and commissioning of following sizes ceiling fan including wiring the down rods of standard length up to 30 cm with 1.5 sq. mm FR PVC insulated, copper conductor, single core cable, earthing etc. complete as required.				
	3	1400 mm sweep	Each	4.00	1637.00	6,548.00
7	8.6	Supplying, installation, testing and commissioning of following sizes heavy duty (continuous running) 1400 rpm exhaust fan in existing opening in wall including earthing etc. complete as required.				
	3	450 mm sweep	Each	2.00	4228.00	8,456.00
8	8.9	Supplying, installation, testing and commissioning of following surface/ concealed type fluorescent fitting (luminaries) complete with electronic ballast/ copper ballast glow type starter but without fluorescent lamp, on				




S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		ceiling/ wall surface, earthing the fitting etc. as required.				
	1	4' x 40 W single patti type	Each	12.00	272.00	3,264.00
9	8.10	Supplying, installation, testing and commissioning of following concealed type fluorescent fitting (luminaries) complete with electronic ballast/ copper ballast glow type starter (if required) but without fluorescent lamp, in false ceiling hanged with 2 Nos G.I chain to ceiling/ truss frame earthing the fitting etc. as required.				
	1	4' x 40 W single mirror optics type	Each	12.00	876.00	10,512.00
10	8.18	Supplying, fixing, testing and commissioning of following CFL (Built in choke type) in existing lighting luminaries as required.				
	4	15 Watt	Each	6.00	183.00	1,098.00
	6	23 Watt	Each	6.00	267.00	1,602.00
11	11.11	Supplying and fixing SP MCB, 240 volts, 'C' curve, suitable for inductive load in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
	2	6 amps to 32 amps	Each	2.00	154.00	308.00
12	14.14	Supplying and laying 25 mm X 6 mm G.I. strip at 0.50 metre below ground as strip earth electrode, including soldering, excavation and refilling the trench etc. as required.	Metre	80.00	99.50	7,960.00
13	11.2	Supplying and fixing on surface/ recess following way, 240 volts SP&N MCB distribution board of sheet steel phosphatized and powder painted complete with tinned copper busbar, neutral busbar, earth bar, din bar, detachable gland plate, including interconnections, earthing etc. as required. (But without MCB/RCCB/Isolator)				
	1	4 way, Single door	Each	1.00	602.00	602.00
14	11.18	Supplying and fixing following rating, 240 volts TWO POLE ISOLATOR in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
	2	40 amps	Each	1.00	271.00	271.00
15	14.2	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as required.	Set	1.00	3454.00	3,454.00
16	14.13	Supplying and laying 6 SWG G.I. wire at 0.50 metre below ground level for conductor earth electrode, including soldering, excavation and refilling the trench etc. as required.	Metre	10.00	38.00	380.00

As per Estimate Amount Rs. **63075.00**

  
Sub Engineer  
Nagar Palik Nigam  
Korba(C.G.)

  
Asst. Engineer  
Nagar palik Nigam  
korba(C.G.)

  
Executive. Engineer  
Nagar palik Nigam  
korba(C.G.)