

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. 1288 / निर्माण / 2022

सिस्टम टेंडर नं 116189

कोरबा दिनांक 02.12.2022


ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 एवं विद्युत कार्य हेतु दिनांक 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदाएं आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	नगर पालिक निगम, कोरबा क्षेत्रांतर्गत कलेक्ट्रेट परिसर में सामान्य निर्वाचन शाखा कोरबा हेतु अतिरिक्त कक्ष एवं हॉल निर्माण कार्य।	25.37	19000/-	06 माह	वर्ग डी एवं प्रवर श्रेणी	27.12.2022 से

शर्तें:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पैन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र स्कैन कर अपलोड करना अनिवार्य होगा।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में फ्लाइ एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

प्रतिलिपि:-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		02.12.2022	16.30	02.12.2022	16.30	Release Tender
2		Bid Submission	02.12.2022	16.30	26.12.2022	17.30	
3	Tender Open		27.12.2022	10.30	--	--	



EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)

ABSTRACT

Time of Work : CONSTRUCTION OF ADDITIONAL ROOM NEAR GENERAL ELECTION BRANCH AT KORBA
 per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	99.78	185.00	18,459.30
2	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	cum	233.4	65.00	15,171.00
3	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	39.18	371.00	14,535.78
4	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	256.4	139.00	35,639.60
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape	sqm	156	297.00	46,332.00
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	138.6	235.00	32,571.00
	1.8	Beams, lintels, cantilevers & walls	sqm	143.8	202.00	29,047.60
	1.13	Weather shade, chhajja, Cornices and mouldings	sqm	34.2	294.00	10,054.80
5	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	cum	28.53	2659.00	75,861.27
6	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	103.58	4163.00	431,203.54
7	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	2.1	Thermo-Mechanically treated bars FE 415	kg	10358.00	54.50	564,511.00
8	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)	cum	86.93	3263.00	283,652.59
9	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	58	121.00	7,018.00
10	9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of	kg	1200	75.00	90,000.00

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. nusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.				
11	9.14	Providing and fixing steel door made of angle iron of suitable sizes with M.S. grill of approved pattern made of M.S. flats or square or round bars coat of red oxide zinc chromate primer.	kg	620	79.50	49,290.00
12	9.15	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	kg	1000.00	67.50	67,500.00
13	11.1	Providing and making 6mm thick cement plaster of mix:				
	1.2	In Cement mortar 1:4 (1 cement : 4 fine sand)	sqm	219.5	87.00	19,096.50
14	11.2	Providing and making 12mm thick cement plaster of mix:				
	2.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	383.42	91.50	35,082.93
15	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	3.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	427	107.00	45,689.00
16	12.13	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.				
	3.1	Size 600x600mm	sqm	152	1151.00	174,952.00
17	14.12	Applying one coat of cement primer on wall surface (applied @ 0.80 litres/10 sqm) complete.	sqm	840	23.00	19,320.00
18	14.9	Distemper with acrylic washable distemper to give an even shade.				
	9.1	On new work (Two or more coats)	sqm	540	38.00	20,520.00
19	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wali care, Alitek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	840	94.50	79,380.00
20	14.14	Finishing walls with water proofing cement paint of required shade to give an even shade.				
	4.1	On new work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm	300	41.00	12,300.00
21	14.22	Painting on new work (two or more coats) to give an even shade with:				
	2.1	Satin synthetic enamel paint	sqm	101.76	55.00	5,596.80
22	18.1	Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistem (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required :				
	1.3	White Orissa pattern W.C. pan of size 580x440 mm	each	2	2899.00	5,798.00
23	18.13	Providing and fixing white vitreous china urinal basin with waste fitting as per IS : 2556, and other couplings in C.P. brass complete:				
	3.1	Flat back half stall urinal of size 460x380x250mm	each	2	1776.00	3,552.00
24	18.25	Providing and fixing flexible P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.				
	5.1	32 mm dia	each	4	68.50	274.00
25	19.4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having				

REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	thermal stability for hot & cold water supply including all CPVC plain & threaded fittings l/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. INTERNAL WORK - EXPOSED ON WALL				
4.1	15 mm nominal outer dia. Pipes.	metre	40	110.00	4,400.00
4.3	25 mm nominal outer dia. Pipes.	metre	60	199.00	11,940.00
26 12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.				
7.1	Size upto 200x300mm	sqm	50.4	587.00	29,584.80
27 12.9	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.				
9.1	Size 300x300mm	sqm	25	692.00	17,300.00
28 18.18	Providing and fixing white vitreous china wash basin including making all connections but excluding the cost of fittings :				
8.1	White Size 550x450 mm	each	3	936.00	2,808.00
29 18.19	Providing and fixing vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings.				
9.1	White	each	3	1130.00	3,390.00
30 12.18	40mm thick marble chips flooring rubbed and polished to granolithic finish with under layer 34mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 12.5 mm nominal size) and top layer 6mm thick with white or black or white and black marble chips of size from 1mm to 4mm nominal size laid after mixing with cement marble powder in mix 3:1 (3 cement :1 marble powder by weight) in proportion of 4:7 (4 cement marble powder mix : 7 marble chips by volume)				
8.2	Light shade pigment with white cement	sqm	17.92	449.00	8,046.08
1 19.6	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This included jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. EXTERNAL WORK				
6.8	75 mm nominal inner dia pipes	metre	10	1682.00	16,820.00
6.9	100mm nominal inner dia pipes	metre	20	2325.00	46,500.00
18.77	Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.				
7.1	Tee/ Tee with door/ Bend 45° / Bend 90°	each	3.00	113.00	339.00
1.1	75 mm	each	2.00	154.00	308.00
1.2	110 mm				
7.3	Vent cover	each	1.00	34.00	34.00
3.1	75 mm				
19.13	Providing and fixing 15 mm nominal bore Brass bib/stop cock of				

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		approved quality:				
		cock (250 grams)	each	2.00	185.00	370.00
	3.3	Stop cock (350 grams)	each	6.00	237.00	1,422.00
34	19.14	Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required:				
	4.2	Long nose bib cock (500 grams)	each	1.00	455.00	455.00
	4.4	Pillar Cock (400 grams)	each	3.00	398.00	1,194.00
35	19.42	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	LTR	1000.00	7.30	7,300.00

As per Estimate Amount Rs. 2,327,319.59
 ✓ FOR ELECTRIFICATION WORK Add Above 9 % 209,458.76
 Grand Total Rs. 2,536,778.35
 Say Rs. 2537000 = 00


 sub Engineer
 Nagar Palik Nigam
 Korba (C.G.)


 Assit. Engineer
 Nagar Palik Nigam
 Korba (C.G.)