

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क्र. 230 / 2025

सिस्टम टेंडर नं.174455

कोरबा दिनांक 28.08.2025

द्वितीय ई-निविदा आमंत्रण सूचना


कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा हेतु दिनांक 01.01.2015 एवं MP SOR 01.01.2024 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र Form-A में निविदा आमंत्रित की जाती है:-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि — 18.09.2025 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि — 18.09.2025 सायंकाल 4.00 बजे से

क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (डिमांड ड्राफ्ट)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	बरबसपुर सी.बी.जी. प्लांट हेतु नवीन प्रस्तावित स्थल पर प्रीकास्ट बाउण्ड्रीवाल तथा ब्रिकवर्क बाउण्ड्रीवाल, एंटी गेट एवं मिट्टी फिलिंग का कार्य (जि.ख.न्या. मद)	199.58	150000/-	10 माह	3000/-	वर्ग सी एवं प्रवर श्रेणी	18.09.2025 से

शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र, पेन नम्बर, वैध जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाइन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं निर्धारित प्रारूप में शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई. चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा के पते पर भेजना होगा। निर्धारित तिथि को सायं 03:00 बजे के पश्चात् फिजिकल सबमिशन लिफाफा स्वीकार नहीं किया जायेगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निर्धारित प्रारूप में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात को, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्युरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन (वर्तमान तक वैधता) एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे। कर्मचारी भविष्य निधि संगठन (ई.पी.एफ.) एवं विभिन्न प्रावधानों की धारा 1952 के तहत निविदाकार का जीवित पंजीयन होना आवश्यक है साथ ही निविदा आमंत्रण दिनांक से विगत 03 माह की अवधि में जमा किये गये TRRN Payment Details चालान की प्रति प्रस्तुत करना तथा ऑनलाइन अपलोड किया जाना अनिवार्य होगा।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ईट से संबंधित निर्माण कार्यों में पलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
10. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. निविदा प्रपत्र फार्म -ए की कंडिका 11 Price Adjustment (एस्कलेशन) देय नहीं होगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान कार्य विशेष हेतु बजट आबंटन एवं राशि उपलब्ध होने पर किया जाएगा।
16. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
17. कार्य कियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
18. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।
19. निविदाकार को निर्माण स्थल पर स्वयं अथवा किराए का प्री कास्ट बाउण्ड्रीवाल के निर्माण हेतु प्लांट स्थापित करना अनिवार्य होगा। इस हेतु निविदाकार को स्वयं के प्लांट होने पर प्लांट के बिल की प्रति अथवा किराये का प्लांट होने पर प्लांट का किरायानामा (एग्रीमेंट) की प्रति संलग्न करना अनिवार्य होगा। प्रस्तुत नहीं करने पर निविदा अस्वीकार्य होगा।



अधीक्षक अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		28.08.2025	17.30	28.08.2025	17.30	Release Tender
2		Bid Submission	28.08.2025	17.30	16.09.2025	17.30	
3		Physical Document Submission	28.08.2025	17.30	18.09.2025	15.00	
4	Tender Open		18.09.2025	16.00	--	--	


SUPERITENDING ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION KORBA (C G)
DETAILED ESTIMATE

of Work - Construction of Brick work Boundary Wall Work at Barbaspur CBG Plant site

or Sor - Schedule of Rates Public Works Department [PWD BUILDING 01-01-2016]

ITEM DESCRIPTION

ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
Excavation for All Types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and levelling of pits								
In All Types of soil								
For Boundary Wall Work	140	1.50	1.50	1.20	378.00			
	1	400.00	0.40	0.50	80.00			
For Gate Work	4	1.80	1.80	1.80	23.33			
					481.33	Cum	185.00	89045.68
Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M and lift upto 1.5 M					192.53	Cum	65.00	12514.53
Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete								
For Boundary Wall Work	140	1.50	1.50	0.10	31.50			
	1	400.00	0.40	0.10	16.00			
	4	1.80	1.80	0.10	1.30			
					48.80	Cum	371.00	18103.32
Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work								
1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)								
For Boundary Wall Work	140	1.50	1.50	0.15	47.25			
	1	400.00	0.40	0.10	16.00			
	4	1.80	1.80	0.10	1.30			
	2	20.00	5.00	0.15	30.00			
					94.55	cum	2659.00	251397.81
1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone Aggregate 20mm nominal size)								
	1	400.00	0.20	0.08	6.40			
	4*2	5.00	2.40	0.15	14.40			
	2	20.00	5.00	0.15	30.00			
					50.80	cum	4073.00	206908.40
Providing and fixing formwork including centering, shuttering, strutting, staging, propping, bracing etc. complete and including its Removal At All levels, for								
Foundations, footings, base of columns and plinth beam in any shape and size								
	140	4.00	1.40	0.40	313.60			
	140	2.00	0.20	1.50	84.00			
	140	2.00	0.30	1.50	126.00			
	1	2.00	400.00	0.30	240.00			
	4	4.00	1.60	0.50	12.80			
	4	4.00	0.40	1.20	7.68			
	4	2.00	4.00	0.30	9.60			
	2	2.00	20.00	0.15	12.00			
					805.68	sqm	139.00	111989.52
Columns, Pillars, Piers and likes- rectangular or square in shape								
	140	2.00	0.20	2.40	134.40			
	140	2.00	0.30	2.40	201.60			
	4	4.00	0.40	3.00	19.20			
					355.20	sqm	297.00	105494.40
Beams, lintels, cantilevers & walls								
	6	5.00		0.30	9.00			
					9.00	sqm	202.00	1818.00

DESCRIPTION		H	L	B	H/D	Qty	Unit	Rate	Amount
Providing and laying minimal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work									
1:1 cement 1:3 coarse sand 1 graded stone aggregate 20mm nominal size)									
Forming									
		140	1.40	1.40	0.40	109.76			
		140	0.30	0.20	1.50	12.60			
		1	400.00	0.20	0.30	24.00			
		140	0.30	0.20	2.40	20.16			
		4	1.60	1.60	0.50	5.12			
		4	0.40	0.40	1.20	0.77			
		2	5.00	0.20	0.30	0.60			
		2	0.40	0.40	3.00	0.96			
		1	5.00	0.30	0.30	0.45			
Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth						174.42	cum	4163.00	726102.13
Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete						21.57	cum	97.50	2103.08
Thermo-Mechanically treated bars						16220.87	kg	54.50	884037.63
Brick work with modular fly-ash lime bricks (FALG Bricks) conforming to IS 12894-2002 of class designation 4.0 in foundation and plinth in (Cement Mortar 1:6 (1 cement 6 coarse sand)									
		1	400.00	0.20	0.60	48.00			
		1	400.00	0.20	2.40	192.00			
						240.00	cum	3263.00	783120.00
10 Extra for brick work in superstructure Above plinth and upto floor five level						192.00	cum	121.00	23232.00
11 Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer						790.00	kg	67.50	53325.00
12 Providing and making 12mm thick cement plaster of mix. In Cement Mortar 1:6 (1 cement 6 fine sand)		1	400.00		3.00	1200.00	sqm	91.50	109800.00
13 15mm thick cement plaster on the rough side of single or half brick wall of mix. In Cement Mortar 1:6 (1 cement 6 fine sand)		1	400.00		3.30	1320.00	sqm	107.00	141240.00
Applying one coat of cement primer on wall surface (applied @ 0.80 litrs/10 sqm) complete						2520.00	sqm	23.00	57960.00
14 15 Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with									
14.15 On new work (Two or more coats applied @ 1.43 litr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)						2520.00	sqm	56.00	141120.00
15 Painting on new work (two or more coats) to give an even shade with Satin synthetic enamel paint									
		4	5.05		3.05	61.61			
						61.61	sqm	55.00	3388.55
Total Amount Per SOR Rs.									3722700.05

Sub Engineer
Municipal Corporation
Korba (C.G.)

Asst. Engineer
Municipal Corporation
Korba (C.G.)


Estt. Engineer
Municipal Corporation
Korba (C.G.)


OFFICE OF THE MUNICIPAL CORPORATION KORBA (C G)
DETAILED ESTIMATE

Work Construction of Precast Boundary Wall Work At Barbaspur CBG Plant site.
Schedule of Rates Public Works Department [M.P.SOR 01 01 2024]

ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
Providing and fixing of prestressed vertically casted concrete panels (both surfaces should be smooth and having grooves on both faces) of M-40 grade of concrete of size 2100x300x50 mm having minimum 4 nos of high tensile steel wire As Per IS 6006 2014 of dia 3 mm placed horizontally in full length of panel with prestressed precast concrete column of M 40 grade of size 3000x150x150 mm having minimum 7 nos of high tensile steel wire As Per IS 6006 2014 of dia 3 mm placed vertically in full length to erect precast boundary wall panels to height 2100 mm from G.L. including excavation of pit of size 750x750x900 mm in all kind of soil except rock for erection of columns and grouting the pit with M-20 grade of concrete Manufacturing, transportation and installation At site All complete As Per the direction of Engineer in-Charge								
	1	3300.00			3300.00			
					3300.00			
Extra for every additional height of 0.3 m up To Height of wall 3 Meter								
	2	3300.00			6600.00			
Total Amount								


Sub Engineer
Municipal Corporation
Korba (C.G.)


Asst Engineer
Municipal Corporation
Korba (C.G.)


Engineer
Municipal Corporation
Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION KORBA (C G)
DETAILED ESTIMATE


of Work - Proposed Soil Filling work at Barbaspur CBG Plant area.

er Sor - Schedule of Rates Public Works Department [PWD BUILDING 01-01-2016]

ITEM DESCRIPTION	N	L	B	WD	Qty	Unit	Rate	Amount
Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in Depth/ Height including disposal of rubbish upto 1.5 m lift and lead upto 50m (At least 5m Away from the Dressed Area)	1	22.20	4047.00		89843.40			
					89843.40	Sqm	7.20	646872.48
Providing filling and compacting local earth (from Approved Source Pit) in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing Etc. Complete	1	45.00	4047.00	0.05	9105.75			
					9105.75	Cum	242.00	2203591.50
Total Amount As Per BOR Rs.								2850463.98
Say Amount Rs								


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asst Engineer
 Municipal Corporation
 Korba (C.G.)


 Asst Engineer
 Municipal Corporation
 Korba (C.G.)